

MACHINERY

OCTOBER 22, 1958

ONE SHILLING & THREEPENCE


*For
Maximum
Production*

Ward

No. 10 COMBINATION

TURRET LATHE

Swing over bed
covers 2 ft.
4½ in. dia. hole
through spindle
Hydraulic actuation
of driving clutch
giving finger stop
gear change




Photograph by courtesy of Zwick Ltd., Slough



**H.W. WARD & CO
LTD**

SELLY OAK BIRMINGHAM 29

TELEPHONE SELLY OAK 1131



ASQUITH

FOR ACCURATE HEAVY-DUTY

MILLING, DRILLING & BORING

Available for early delivery, the Asquith NHB type horizontal borer with 6in. dia. spindle, as illustrated above, can now be supplied to meet urgent demands. Write today for full details of this machine.

WILLIAM ASQUITH LTD.
HALIFAX • ENGLAND

Sales & Service for . . .

DRUMMOND-ASQUITH


. . . the British Isles

DRUMMOND-ASQUITH (SALES) LTD., KING EDWARD HOUSE, NEW ST., BIRMINGHAM

'Phone: Midland 3431 (7 lines) Grams: Maxishape, Birmingham. Also at LONDON: 'Phone: Trafalgar 7224 (5 lines) and GLASGOW: 'Phone Central 0922

Top men, Shop men,
 fast-coming-up-men
 For weldability call for Group 2
 But Group 3's slag removal
 Earns the welder's approval;
 They're combined
 in the new. . .

VELVARC TWO



The new Velvarc Two electrode, with thirty years of ACTARC experience behind it, combines the excellent weldability of Group 2 electrodes with the good slag removal of Group 3.

Write for details of the full range of ACTARC welding transformers and plant, welding electrodes for all purposes and welding accessories.

ACTARC

the name for dependable electrodes

ARC MANUFACTURING CO. LTD.

ACTARC WORKS • NITSHILL • GLASGOW, S.W.3.

Telephone: BARRHEAD 2293/7

Telegram: ACTVARC GLASGOW

LONDON OFFICE: 15 HERCULES ROAD, WILKINSON, EDDY. Telephone: Uxbridge 9651/2

**YOU'LL BE MUCH BETTER OFF
WITH A HARRISON**

Built to a standard above its price
— your Harrison 11" swing lathe
will be giving you accurate service
for more years than you expected.


SPECIFICATION

Swing over bed 11"
Swing in gap 18"
Between centres 24" or 40"
8 or 16 spindle speeds

11" SWING

£370.0.0


**With inbuilt hydraulic copying equipment
£700.0.0**



**SEND FOR FULLY DETAILED
LEAFLET TODAY**

T. S. HARRISON & SONS LIMITED • HECKMONDWIKE • YORKSHIRE

When answering advertisements kindly mention MACHINERY.



See what Fescol can do

Here's the perfect before and after story of the Fescol process. The ram on my left is untreated, and has become corroded and pitted by wear and corrosion, in this condition it has reached the end of its useful life. Now look at the other ram, it was just the same before it was 'Fescol'-ised and now it will retain its new look almost indefinitely. That's because the nickel or chromium protection provided by the Fescol process withstands wear and corrosive attack being an even harder, more durable surface than the original metal. The process has proved so successful in the salvage of worn rams that now we have them treated before installation. Then we more or less forget about them.

If you would like to know more about the Fescol process of electro-chemical deposition, and its applications in a variety of industries, please write for publication M.11.



Established 1920

FESCOL LIMITED - NORTH ROAD - LONDON N7
BRANCH WORKS: PORT GLASGOW, HUDDERSFIELD AND BROWNHILLS, WALSALL

Sole Licensees for Australasia: De Havilland Aircraft Pty. Ltd., Milperra Road, Bankstown, N.S.W.


TGA 959

When answering advertisements kindly mention **MACHINERY**.

*Specify***SPEEDICUT****SUPERLEDA
BUTT WELDED TOOLS**

Machining alloy steels forgings
Speedicut Superleda Butt Welded
Tools, working with $\frac{1}{2}$ " cut $\frac{3}{8}$ " feed at
50 feet per min. removed an average
of 1900 lbs. of metal per hour.

Take advantage of the latest
techniques in toolmaking
Specify Speedicut!

**17 CWT. OF METAL**

for **HEAVY DUTY
TURNING & PLANING**




F B T
FIRTH BROWN TOOLS LTD.

SPEEDICUT WORKS

CARLISLE STREET EAST

SHEFFIELD



REMOVED PER HOUR !



*** LIES THE SECRET**
of successful Automatic Production

ON BATCHES AS SMALL AS 40 COMPONENTS

This new machine will give you on short runs three to four times more production than a capstan. It is worth while investigating.

Only

TAREX

GIVES TURRET ROUGHING & HYDROCOPY FINISHING

ensuring **SIMPLE TOOLING** - **FAST SETTING** - **QUICK CHANGEDOVERS** -
HIGH PRECISION - **FINE FINISH** ELIMINATING MANY GRINDING OPERATIONS

SIX TYPES FOR BAR WORK FROM 1 1/2" TO 2 1/2" DIA.
 TWO TYPES FOR CHUCKING WORK UP TO 2 1/2" DIA.
 THREE UNIVERSAL MODELS FOR BAR WORK
 UP TO 2" DIA. CHUCKING UP TO 7 1/2" DIA.

TAREX (England) LTD

22 BUCKINGHAM GATE
LONDON, S.W.1.

TELEPHONE
 TATE GALLERY 3191

When answering advertisements kindly mention MACHINERY.


HIGH PRECISION small bore HONER

- FULLY
AUTOMATIC OPERATION
- AUTOMATIC SIZING
- AUTOMATIC
AFTER-GAUGING



*This British equipment built to toolroom
standards, hones to incredibly
fine limits with high-production cycle and
completely automatic work
handling.*

model 738 MICROHONER



SERVICE—Jones-Shipman Field Engineers always prove this Honer in your Works. Your interest in both practical and economic performance is their job.

Refer to Machinery, October 8th, 15th and 29th for details of other Jones-Shipman Micromatic Honing Machines.


A. A. JONES & SHIPMAN LTD.,

Narborough Road South, Leicester.
Tel: 823222 Telegrams: "Chuck" Leicester.
London Office: Murray House,
5 Vandon St., Buckingham Gate S.W.1.
Tel: Abbey 5908 9

Made in the United Kingdom under the provisions of a Licence for Micromatic Hone Corporation, Detroit, Michigan, U.S.A.

When answering advertisements kindly mention MACHINERY.

MACHINERY



F. PRATT & CO LTD., · HALIFAX · ENGLAND

*Under Licence from N. A. Woodworth Co., Detroit, U.S.A.
Proprietors of the Trade Mark "Woodworth"*



diaphragm chucking

LARGE AND THIN

The features of a Woodworth diaphragm chuck eliminate the locating problems on parts like the one shown.

Large thin walled jet parts require surrounding type jaws to avoid distortion from chucking pressure.

By completely filling the internal diameter of this part, the chucking action forces the part round. In this way uniform wall sections are obtained and accurate diameter and length dimensions can be machined.

➤ The ultimate in precision chucking.

➤ Consistent repeated accuracy to .0001"/.0002".

➤ Dust and swarf proof mechanism.

➤ No wearing parts.

➤ Distortion totally eliminated.


➤ Pitch line chucking on gearing made easy.

➤ Determined pressure of grip constantly repeated.


➤ Send us your problem.

RATTT

CHUCKS



With one machine and one 'Unitool' cutter



you can produce all three types of gears

Now it takes only a relatively small capital investment to equip a shop for producing prototypes or small quantities of spiral, Zerol bevel and hypoid gears.

The new Unitool Method requires only one machine, the No. 116 Hypoid Generator shown above or the smaller No. 106, and one Unitool cutter to rough and finish both gears and pinions of a particular combination.

A total of six Unitool cutters cover gears and pinions of all designs from 1.3in. to 8in. cone distance, 0.4in. to 2.2in. face width, and 16 to 2.5 D.P.

Simplified, slide-rule calculations make it possible for even inexperienced personnel to turn out gears of high quality.

Gleason Generators are Versatile

The Unitool Method is only one of four that you can use on the No. 106 and 116 Generators. The same machines can be used for Standard Generating for medium gear and pinion production. In addition, for volume gear production they can be specially arranged for the Single-Cycle Method where each

tooth of a roughed out, non-generated gear is finished in one cutting revolution of the Single-Cycle cutter, or the Cyclex Method where non-generated ring gears are both roughed and finished in one cut from the solid blanks. For further information on the Unitool Method and for assistance with any design or manufacturing problems involving bevel gears, just write us.

BUCK & HICKMAN LTD

Machine Tools—Otterspool Way, Watford by-pass, Herts.
Head Office—P.O. Box No. 74, Whitechapel Road, London, E.1.
Branches—Alpert-on - Birmingham - Glasgow - Leeds - Manchester

Sole Agents in the British Isles for—

GLEASON WORKS

BUILDERS OF BEVEL GEAR MACHINERY FOR OVER 90 YEARS

When answering advertisements kindly mention MACHINERY.

Jacobs **CHUCKS**



UNSURPASSED FOR . . .
GRIPPING POWER, PRECISION
& ALL-ROUNDED PERFORMANCE



. . . and who better than JACOBS should
know the formula for these attributes?

Long experience of chuck production has yielded the
invaluable data on design, choice of materials and
methods of manufacture which are incorporated in
every JACOBS chuck, and upon which has been built
a world-wide reputation.

IF IT'S A
JACOBS
IT HOLDS

THE JACOBS MANUFACTURING CO., LTD.
MILLHOUSES, SHEFFIELD, 8.

When answering advertisements kindly mention MACHINERY.

Fine Boring **The** **PRECIMAX***Way*



★ **THREE-POSITION AUTOMATIC HYDRAULIC
CROSS SLIDE SOLVES PROBLEM OF BORING
CLOSELY SPACED HOLES AT ROVER CO. LTD.**

The problem of fine boring close centre holes in this Rover gearbox is ingeniously overcome by use of the PRECIMAX three position hydraulically operated cross slide. The necessary transverse movements are preselected and linked with the longitudinal feed motions in a fully automatic cycle.

The three bores (two at 0.625in. dia. and one at 0.6875in. dia.) are repeated by two spindles at the opposite end and in addition to close limits on diameter and relative position, this multiple operation fulfils exacting demands in the accurate alignment of the opposing bores. The six holes are bored using solid tungsten carbide shank boring bars in a floor-to-floor time of 2.85 minutes.

Send for full details of PRECIMAX Fine boring Machines to . . .

LANDIS LUND LTD., CROSS HILLS, KEIGHLEY. 'Phone: Cross Hills 3211

When answering advertisements kindly mention MACHINERY.



AN **APE** PRODUCT


The
MICROBALL
HEIGHT GAUGE &
BALL COMPARATOR
MADE TO MEASURE

12" UNIT
£26
24" UNIT
£60
INDICATORS EXTRA

TRADE ENQUIRIES INVITED—SEND FOR ILLUSTRATED LITERATURE

ALL PRECISION ENGINEERING LTD . KINGS ROAD . HORSHAM . SUSSEX . HORSHAM 2277/8

When answering advertisements kindly mention MACHINERY.



MR. STEEL'S NEW WAREHOUSE FOR CARBON & ALLOY STEELS

Macready's Metal Company Ltd. has this additional special warehouse at King's Cross devoted to the supply of Carbon and Alloy Steels.

Very large stocks are held and the warehouse is completely equipped with the modern facilities required to maintain the quick delivery service for which Macready's are famous. Production delays are eliminated when you use Macready's.

5000 TONS OF BRIGHT STEEL are always available at our main warehouse at Usaspead Corner for immediate delivery. Avoid delays by using the Macready service.

MACREADY'S

METAL COMPANY LIMITED

USASPEAD CORNER, PENTONVILLE ROAD, LONDON, N.I.

Telephone : TERminus 7060 (20 lines). Telegrams : Usaspead, London, Telex. Telex No. 22788

When answering advertisements kindly mention MACHINERY.

Introducing the **SYNTRON EB.00**



The EB.00 is the newest and smallest feeder in the Syntron Bowl Feeder range, being only 6 in. in diameter and 6½ in. high. It is supplied with a quick release bowl, clockwise or anti-clockwise discharge and easy-to-operate controller. This compact unit and the other Syntron Bowl Feeders in the range provide the orientated feeding of small parts one at a time.

SYNTRON ***KEEPS THINGS MOVING***

FULL DETAILS AVAILABLE ON REQUEST

RILEY (IC) PRODUCTS LIMITED • ONE OF THE INTERNATIONAL COMBUSTION GROUP OF COMPANIES
NINETEEN WOBURN PLACE, LONDON, W.C.1. TELEPHONE: TERMINUS 2622

*GA 140


When answering advertisements kindly mention MACHINERY.

*The fastest method of
grinding two surfaces
simultaneously!*

ROWLAND

DUPLIX SURFACE GRINDERS

* Illustrated here are but a few of the very many types of 'Duplex' surface grinding machines that we manufacture.




DISC DISC

30in. Type ADD/H


* All machines are capable of extremely impressive rates of production, coupled with high degrees of accuracy and surface finish.

Our technical representatives are ready, able and willing to co-operate with you.




C-CLIPS

30in. Type ADD/F



CALCULATOR PARTS

20in. Type HDD/C



CONNECTING RODS

30in. Type ADD/O

**F.E. ROWLAND
& CO. LTD.**

Telephone:
HEATON MOOR
3201-2-3
Telegrams:
HEROIC, REDDISH


REDDISH • STOCKPORT • ENGLAND

Sole Export Agents: DRUMMOND ASQUITH (Sales) LTD., Halifax House, Strand, London, W.C.2. Tel: TRAlgar 7814

When answering advertisements kindly mention MACHINERY.



Electro-Hydraulic Thrustors




Smooth straight-line constant-pressure thrust from start to finish of stroke.

From 40-lb. thrust, 2-in. stroke to 800-lb. thrust, 12-in. stroke.

Just switch on—

the thrustor does the work



BRITISH THOMSON-HOUSTON

THE BRITISH THOMSON-HOUSTON COMPANY LIMITED • RUGBY • ENGLAND
Member of the AEI group of companies

A4000

When answering advertisements kindly mention MACHINERY.

6^x4=24


TYPES
OF FEED

SPEED
RANGES

POSSIBLE
COMBINATIONS

that's
the
beauty
of the

A & S MODEL '1' HORIZONTAL MILLER



6 With automatic cycle.

1

Hand Feed—lever, screw, lever.

2

Hand Feed—lever, lever, lever.

3

Hand Feed—Screw, screw, screw.

4

Multiform—semi-automatic cycle.

5

Normal automatic feed.

WHY PAY FOR 'SPECIAL' FEATURES YOU MAY NEVER USE?

When you equip with A. & S. Model '1' Millers you choose from 4 ranges of speeds and 6 different feed arrangements the best combination* for a particular job. Both hand-feed and automatic types can, however, be supplied with special attachments for special operations. No other small milling machine offers similar versatility or higher production capacity for so wide a range of work.

TABLE 26" x 7"

LONGITUDINAL TRAVERSE = 10"

VERTICAL TRAVERSE = 10"

TRANSVERSE TRAVERSE = 5 1/2"-6"

*With the A. & S. Model '1' brochure in front of you, you would know exactly what we mean.

Built up to a standard—not down to a price

Write for illustrated leaflet.

ADCOCK & SHIPLEY LTD.

P.O. Box 22, Ash Street, Leicester. Telephone: Leicester 24154-6


Telegrams & Cables: Adcock, Leicester.

MACHINERY

18 October 22, 1958

'HABIT'

PRECISION TOOLING means...



*Faster Output
More Accurate Work
Lower Production
Costs*

To-day, more than ever, to boost up production and pull down costs is a dire necessity, and HABIT ingenuity and vision help you to do both. Look at the way HABIT themselves are forging ahead!

The 'HABIT' SINE DIVIDING TABLE

Here is an example. Study this new HABIT Compound Sine Table. Notice its low overall height (only 21"), yet it will set or measure every possible compound angle. In addition, it will carry out dividing operations to an accuracy far closer than that of an optical table.

Acceptable on every machine, this is the most practical and productive sine table ever made. So obvious—why didn't someone think of it before!

HABIT DIAMOND TOOLING LIMITED, 294-296 LILLIE ROAD • FULHAM • LONDON, S.W.6.

Telephone: FULHAM 7944

Telegrams: 'HABIT, LONDON, S.W.6.'

'HABIT'

When answering advertisements kindly mention MACHINERY.



For MORE ACCURATE GEARS...

SPURS
HELICALS
WORMWHEELS
SPLINES
SERRATIONS




UNIVERSAL HOBBER

Model V.8

8" dia. 7" face—12 D.P.

If you want more accurate gears—and we do mean *more* accurate—then you need a DOWDING V.8. From the drawing board right down to the last detail of production the V.8 is designed and built to produce more gears—more accurately. Ample rigid for production hobbing—climb or orthodox. Built-in differential for helicals. Fast traverse, tangential feed and cam operated plunge feed too—if you need them. Hundreds of DOWDING hobbers are in constant service, many users having multiple installations.



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14


Telephone: WESTERN 0077 (8 lines)

Telegrams: ACCURATOOL HAMMER LONDON



Write for this
catalogue today

When answering advertisements kindly mention **MACHINERY**.



360° Swivelling Table

saves Setting Time and errors

SWISS


DIXI '60'

OPTICAL PRECISION JIG BORER

The table swivels through 360° with microscope setting to 1 min.—6 sec. can easily be estimated; the job can thus be swivelled right round and machined at any angle without disturbing the original setting. Other features include hydraulic control to the longitudinal and cross traverses, microscope setting to all traverses and additional 17½" precision optical table for mounting horizontally or vertically.

TABLE SIZE 28½" x 32½"
SPINDLE DIAMETER 2½"
SPINDLE SPEEDS 34 TO 1400 R.P.M.

Also DIXI '75', a heavier machine with 3" spindle.



Ask for illustrated catalogue

Sole U.K. Distributors.




DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14

Telephone WESTERN 8077 (8 lines)

Telegram ACCURATOO HAMMER LONDON

When answering advertisements kindly mention MACHINERY.



YOURS CONSISTENTLY...

The Sykes VS4A is a machine designed first and foremost for the fast shaving of fine pitch gears to a *consistently* high degree of accuracy; especially for the precision finishing of fine pitch gears for electronic instruments, control mechanisms and similar precision apparatus.

The VS4A can shave spur and helical gears up to 4 inches in diameter and 1 inch face width, with a pitch as coarse as 16 D.P.

As with all Sykes machinery, the VS4A is built to the highest standards of accuracy and rigidity. It occupies the minimum of floor space, and its simple loading enables it to be operated quite easily by unskilled labour. If required, automatic loading can also be employed.

The VS4A, once loaded, will rapidly and automatically perform a full cycle of operation varying from 13 to 45 seconds—depending on the material and characteristics of the component.

If you want perfection . . .

highest accuracy, best surface finish and quietest operation is achieved by gears which have been shaved. If the fine pitch gears you produce have a total composite error of more than 0.0003 inches, you should find out more about the VS4A.



**PRECISION
GEAR SHAVERS**

W. E. SYKES LTD • STAINES • MIDDLESEX • ENGLAND

and associated companies

Sykes Tool Corp. Ltd., Georgetown, Ontario, Canada

Sykes Machine & Gear Corp., Newark, N.J., U.S.A.

W. E. Sykes Ltd., Mascot, Sydney, N.S.W., Australia

When answering advertisements kindly mention **MACHINERY**.




Indicating r.p.m. of electric motor.



Indicating shaft speed, showing use of extension.



Indicating surface speed.



The Right REVS

Run your machinery at the optimum speed for peak efficiency. Any deviation from this speed almost certainly means that it—and you!—are running at a loss.

Cut this loss by making spot checks of r.p.m. with a SMITHS Hand Tachometer. Such a check can be made in an instant, even in unfavourable conditions. What's more, the reading is accurate to within $\frac{1}{2}\%$.

SMITHS HAND TACHOMETERS can be used for checking:—

Rotational speeds of shafts, spindles, gears, rotors and rolls.

Linear speeds in ft/min or metres/min of metal strips, textiles, paper, wire, plastic, film and conveyed material.

Surface speeds in ft/min or metres/min of cutting or grinding operations of machine tools, processing rolls, unwind rolls or wind up rolls for extrusion and strip production.

Readings can be taken in bad lighting conditions or where the dial is visually obscured.

AVAILABLE IN CHOICE OF FOUR MODELS:—

Model A.T.H. 4 (0-50,000 r.p.m.) Illustrated

Model A.T.H. 6 (0-10,000 r.p.m.)

Model A.T.H. 7 (0-20,000 r.p.m.)

Model A.T.H. 10 (0-5,000 r.p.m.)

ALL FOR L.H. OR R.H. DIRECTION OF ROTATION

PRICE (complete with strong case and full range of accessories)

£14.14.0

postage and packing extra.

**POST
THIS
FOR
FULL
DETAILS**

Please send full details of your
HAND TACHOMETERS

NAME

ADDRESS

.....
.....
.....

SMITHS

INDUSTRIAL INSTRUMENT DIVISION

Chronos Works, North Circular Road, London, N.W.2. Telephone: GLAdstone 1136


When answering advertisements kindly mention **MACHINERY**.



TAKE MY TIP

USE GOOD CONTROL GEAR

Motors and machines need careful handling . . . with reliable control of their operations. Efficient starters give easy control and full protection to motor, machine and operator. BROOK control gear is simply designed with a minimum of moving parts. The range is comprehensive, covering a wide variety of control features, direct-on-line, reversing, star-delta, multi-speed, etc. in the lighter horse powers. Automatic or hand-operated.



BROOK MOTORS LTD. HUDDERSFIELD


58/14

When answering advertisements kindly mention **MACHINERY**.

Crofts

couplings

are the finest you can buy!



★ Type C: for coupling two shafts

★ Type P: for V-rope drives

Complete details of speeds, powers, and dimensions are published in catalogues 5814, 5730, 5748, 5747, 5732, 457, 5736, detailed overleaf. Send us your name and address on this postcard to get your copies.

Postage
will be
paid by
Licensee

No Postage Stamp
necessary if posted
in Great Britain or
Northern Ireland

BUSINESS REPLY CARD
Licence No. BD377


**CROFTS (ENGINEERS) LIMITED
THORNBURY
BRADFORD 3
YORKSHIRE**



TAKE MY TIP

USE GOOD CONTROL GEAR

Motors and machines need careful handling . . . with reliable control of their operations. Efficient starters give easy control and full protection to motor, machine and operator. BROOK control gear is simply designed with a minimum of moving parts. The range is comprehensive, covering a wide variety of control features, direct-on-line, reversing, star-delta, multi-speed, etc. in the lighter horse powers. Automatic or hand-operated.




When answering advertisements kindly mention **MACHINERY**.

Crofts

couplings

are the finest you can buy!



★ Type C: for coupling two shafts

★ Type P: for V-rope drives

Complete details of speeds, powers, and dimensions are published in catalogues 5814, 5730, 5748, 5747, 5732, 457, 5736, detailed overleaf. Send us your name and address on this postcard to get your copies.

Postage
will be
paid by
Licensee


No Postage Stamp
necessary if posted
in Great Britain or
Northern Ireland

BUSINESS REPLY CARD
Licence No. BD377

CROFTS (ENGINEERS) LIMITED
THORNBURY
BRADFORD 3
YORKSHIRE

CROFTS FLEXIBLE COUPLINGS


**Crown Pin Flexible
Couplings**



Suitable for virtually every application.

Publication 5730.

Perfect Flexible Couplings



Perfect for small power drives.

Publication 5747.


**Disc Type Flexible
Couplings**



An ideal, medium power, shock absorber.

Publication 5748.

Multiflex Flexible Couplings



Suitable for high or low speeds

Publication 5732

**MB Internal Gear Flexible
Couplings**



For heavy duty industrial drives.

Publication 457.

**NTS Internal Gear Flexible
Couplings**



Coupled or uncoupled in a few seconds.

Publication 5736.

FLEXIBLE COUPLINGS

Please send without obligation.....copies of publication/s
5814 5730 5748 5747 5732 457 5736
to:—

Mr. Chief Designer


Mr. Plant Engineer

Mr.

Company Address.....

.....
.....

Crofts have
branches at:—
BELFAST
BIRMINGHAM
BRISTOL
CARDIFF
DUBLIN
GLASGOW
IPSWICH
LEEDS
LIVERPOOL
LONDON
MANCHESTER
NEWCASTLE
NORTHAMPTON
NOTTINGHAM
SHEFFIELD
STOKE



DISHED and FLANGED ENDS

Fabrication of pressure vessels may be greatly facilitated by drawing upon Harvey resources for the production of die-pressed Dished and Flanged Ends.

Capacities range from 6in. to 9ft. diameter. Edges are prepared for welding or riveting if desired.

STOCK SIZES: Ends pressed from Boiler Quality or Ship Quality Mild Steel up to $\frac{1}{2}$ in. thickness, in most sizes up to 7ft. diameter, are normally available from stock.

SEMI-ELLIPSOIDAL HEADS can be produced on the Rotapress; diameters 5ft. to 15ft.; thicknesses $\frac{1}{2}$ in. to 4in.

For details, please ask for List No. MN 965



Harvey

G. A. HARVEY & CO. (LONDON) LTD., WOOLWICH ROAD, LONDON, S.E.7. Phone: GREENWICH 3232 (22 LINES)

When answering advertisements kindly mention MACHINERY.



YOUR OWN HEAVY MACHINE TOOLS —“SOAG-REBUILT”

SOAG'S Rebuilding Service is offered to all users of heavy machine tools. Your worn machines can be removed to our recently enlarged works in Battersea or Lambeth, completely rebuilt and then re-installed in your own premises in the shortest possible time.

Soag's reputation for economical rebuilding of the highest quality is founded on more than thirty years of specialised skill and experience—more than thirty years of growing customer-satisfaction throughout the world. Remember—all “Soag-Rebuilt” machines are fully guaranteed.



**WRITE NOW GIVING DETAILS OF YOUR MACHINES FOR
A QUICK “SOAG-REBUILDING” ESTIMATE.**


SOAG MACHINE TOOLS LTD. LONDON

JUXON STREET • LAMBETH • S.E.11

PHONE RELIANCE 7201 • GRAMS SOTOOLSAG, LONDON, S.E.11

When answering advertisements kindly mention MACHINERY.

the GROMMET story



4 good reasons for fitting BTR High Test V-BELTS



HIGHER
HORSEPOWER

Grommet construction makes the most efficient use of high tensile cords to produce the strongest V-belts yet made. For grommet construction ensures that *all* the cords of a belt share the load *equally*—which is the condition for maximum transmitting efficiency. Furthermore, a grommet, being an endless loop of high tensile cords, has no joints to weaken the belt, no overlapping sections to stiffen it.



MORE
GRIPPING POWER

Grommet construction ensures that the belt exerts full driving grip on the walls of the pulley groove, for there are no central cords to dip and 'dish' the belt, pulling it away from the walls under load. This extra driving grip allows heavier loads and prevents belt slip.



MORE OUTPUT FOR
ELECTRICITY CONSUMED

Despite its superior strength, a grommet is the most flexible V-belt load carrying device yet developed. Thus the belt runs cool and absorbs minimum energy in flexing around the pulleys. This saving in power appears in extra pay-load for electricity consumed.



LONGER
BELT LIFE

Operating with a higher safety factor than ordinary V-belts, BTR grommet V-belts last longer because they are stronger and also because being so flexible they are subject to little strain in flexing round the pulleys.




BTR HIGH TEST GROMMET V-BELTS

Patented in Great Britain by BTR Patent No. 567406

BTR Industries Ltd HERGA HOUSE, VINCENT SQUARE, LONDON S.W.1 TEL: VIC 3848

D1359

When answering advertisements kindly mention MACHINERY.





Confidence

*inspired by
experience...*

Experience harvested in almost a century's service to industrial undertakings, large and small, has inspired a well based confidence in both the products and manufacturing facilities of S. E. Opperman Ltd.

145,000 square feet of factory space is devoted to, manufacturing and processing bays equipped with machinery capable of producing such varied engineering products as jet engine compounds, marine and aircraft radar units, agricultural and industrial vehicles, gear boxes, gears of all types and Television convertors.



The confidence in S. E. Opperman experience-gained ability can be yours should you give us the opportunity to serve you.

S. E. OPPERMAN LTD.

BOREHAM WOOD - HERTS - ELSTREE 2021


Erwoods

When answering advertisements kindly mention MACHINERY.

Are You Satisfied with Your Plant Lubrication System?



This is neither economical nor efficient —



But this is — the **"LUBRICAR"**

A self-contained mobile unit for regular, economical, efficient lubrication of machine tools and other types of machinery. Pumps and filters are fitted for extracting and filtering used oil.

In charge of a suitably-trained operator working on a regular routine, the Lubricar prevents breakdowns and stoppages due to lack of lubrication.

ALFRED

HERBERT


LTD., COVENTRY



AD.374

When answering advertisements kindly mention **MACHINERY**.

tool corporation limited



facing and boring machines

SCOTISH machine

These Type B facing and boring machines are designed to meet the growing demand for a simple yet robust machine with plenty of power for removing metal. Many users who find their own work growing increasingly specialised no longer need the great variety of features by which general purpose machines are made as versatile as possible. Type B machines are available with several different gearboxes, feed boxes, etc., so that the total outlay can be confined to the features which are actually required. Two basic sizes are available for facing up to 30" diameter and 48" diameter. Write for descriptive booklet.

17, Lynedoch Crescent, Glasgow, C.3. DOUGLAS 6596/9

58, Victoria Street, London, S.W.1. VICTORIA 2106

2, Sir Harry's Road, Edgbaston, Birmingham, 5. CALTHORPE 2541

The Building Centre, Brunswick Terrace, Leeds, 2. LEEDS 25250



When answering advertisements kindly mention **MACHINERY**.

TOOLROOM PRECISION *plus* **PRODUCTION OUTPUT!**

TWO MODELS FROM OUR RANGE

CARDIFF 'MAJOR'

7½ in. S.S. and S.C. LATHE


Gap Bed 40in., or 60in., alternatively Chip Flow Bed, 30in., 40in. or 60in.

18 Spindle speeds, 27 to 757 r.p.m. or 35 to 1,000 r.p.m.

Patented totally enclosed feed box providing wide range of threads and feeds.

Hardened and ground gears in gearbox and headstock—all meshing faces tooth rounded for easy engagement.

Patented snap action feed controls on apron.



CARDIFF 'SENIOR'

8½ in. S.S. and S.C. LATHE


Gap Bed 30in., 48in. or 80in. alternatively Chip Flow Bed 48in. or 80in.

18 spindle speeds 20 to 970 r.p.m., higher or lower ranges optional.

Patented totally enclosed feed box providing wide range of threads and feeds.

Hardened and ground gears in gearbox and headstock—all meshing faces tooth rounded for easy engagement.

Patented snap action feed controls on apron — feeds can be varied whilst cutting.



MANUFACTURED BY

B. ELLIOTT (MACHINERY) LTD.

(MEMBER OF THE B. ELLIOTT GROUP)

VICTORIA WORKS, WILLESSEN, LONDON, N.W.10


Telephone: ELGar 4050 (10 lines) Telegrams: Elliottona, Harles, London

Overseas Subsidiaries: CANADA, U.S.A., AUSTRALIA, S. AFRICA



NRP2020

When answering advertisements kindly mention **MACHINERY**.



* BAMBER FOR BEVELS

*** IMMEDIATE
CAPACITY AVAILABLE**

*for Gleason high-class straight bevel gears
supplied complete or from customers blanks, $\frac{3}{8}$ " to
12" P.C.D., 48 to 4 D.P. • Enquiries welcomed for all types
of gears. Call, write or telephone.*

JOHN BAMBER ENGINEERING LTD.

**WALMGATE ROAD, PERIVALE
GREENFORD, MIDDLESEX
PERIVALE 8476/7/8**

When answering advertisements kindly mention MACHINERY.



Wild-Barfield Progressive Hardening Machine at **MORRIS** Engines Limited

Hardening of valve rocker shafts at Morris Engines Ltd., is carried out on Wild-Barfield Progressive Hardening Machines. (Note the hardness pattern on the rocker arm that is being removed.) This is a typical application of this proved unit of the well-known Wild-Barfield range of induction heating equipment.

Some technical facts.

This fixture caters for lengths from 1" to 30", or longer in special cases, diameters from 1" upwards depending on the size of Wild-Barfield A.H.F. Generator used. A simple cam change enables any desired hardness pattern to be obtained giving hard and soft zones as required. The construction follows machine tool practice and incorporates traverse speed control which, together with power control on the generator, makes the equipment extremely versatile.

WILD-BARFIELD ELECTRIC FURNACES LTD
(High Frequency Division)

ELECFURN WORKS,
OTTERSPOOL WAY,
WATFORD BY-PASS,
WATFORD, HERTS.

Tel: Watford 26091 (8 lines)




**INDUCTION HEATING
SPEEDS PRODUCTION**

WB 75

When answering advertisements kindly mention MACHINERY.

C

NO MAINTENANCE —



Photograph by courtesy of Dorman Long (Chemicals) Ltd.

These Travelling-Grate Stokers made by Babcock & Wilcox supply annually 22,000 tons of coal to boilers which in turn supply the entire steam requirements of the large heavy-chemical works of Dorman Long. MORGANITE CARBON BEARINGS situated in the hot zone have to withstand severe treatment.

MORGANITE CARBON BEARINGS are the answer to this problem—they will answer yours today. Please write or 'phone for leaflet SD.63 or ask for one of our Technical Advisers to call.


MORGANITE CARBON BEARINGS withstand high temperatures, will run in liquids; resist chemical atmospheres and corrosive conditions; need no lubrication; are useful for inaccessible positions; are non-contaminating and eliminate maintenance.

MORGANITE BEARINGS

THE MORGAN CRUCIBLE COMPANY LIMITED, BATTERSEA CHURCH ROAD, LONDON, S.W.11.
Telephone: BATtersea 8822
C65a

When answering advertisements kindly mention MACHINERY.

AJAX *high speed* FORGING PRESSES



**INTEGRAL SOLID
STEEL FRAME**

**DIRECT ACTING
AIR CLUTCH**

BUILT IN 13 SIZES

**CAPACITIES
FROM 300 TO 8000
TONS**

**LET US
DEMONSTRATE
TO YOU**

Sole agents for the range of Ajax Forging Machinery

**VAUGHAN
ASSOCIATES LIMITED**



4 Queen Street, Curzon Street, London, W.1

Telephone: GROSVENOR 8362-5

Midland Office and Demonstration Room:
WILFORD CRES., NOTTINGHAM. Tel.: Nott. 88008

NRP

When answering advertisements kindly mention MACHINERY.



STEEL STAMPINGS LTD

use

HARPER MEEHANITE CAST-TO-FORM TOOLS for their high grade presswork

- 1 Produced from 8 S.W.G. Stainless Steel.
- 2 Produced from 15/32" Mild Steel. Pressed cold in tools fitted with Harper Meehanite Inserts. 28,000 pressings have been produced without any tool reconditioning.
- 3 Produced from 18 S.W.G. Stainless Steel. 9,800 pressings made without any tool reconditioning.
- 4 Produced from 14 S.W.G. Mild Steel. 10,700 pressings produced; tools only reconditioned once.
- 5 Produced from 10 S.W.G. Mild Steel. 2,350 pressings produced without any tool reconditioning.

Harper quality covers grey iron, ductile iron and Meehanite castings, also metal pressings and other finishes and sub-assembly work.

HARPER CASTINGS



JOHN HARPER & CO. LTD. JOHN HARPER (MEEHANITE) LTD.
ALBION WORKS Phone: WILLENHALL 124 (5 lines) Grams: HARPERS, WILLENHALL **WILLENHALL**

LONDON OFFICE: SEAFORTH PLACE, 57, BUCKINGHAM GATE, LONDON S.W.1 Tel.: TATE GALLERY 0286

MANCHESTER OFFICE: c/o B. J. Brown & Partners Ltd. 248/9 Royal Exchange, Manchester 3

1620

When answering advertisements kindly mention *MACHINERY*.



**POSITIONING WITH OPTICAL
READINGS IN .0001"**

**IMMEDIATE
DELIVERY
FROM STOCK**

Write for full details or see a demonstration at our Battersea Works


SOLE AGENTS IN THE UNITED KINGDOM—

SOAG MACHINE TOOLS LIMITED

JUXON STREET, LONDON, S.E.11. 'Phone: RELiance 7201



When answering advertisements kindly mention **MACHINERY**.



Automatics.
Progressive
Tools.
Transfer
Presses.
Multi-Form.

Accurate
Press Tools
to the
finest
limits

Specialists
in Heat
Treatment


SPECIALISTS IN SPRING STEELS
BERYLLIUM COPPER AND OTHER ALLOYS
IMMEDIATE ENQUIRIES INVITED
SPRING STEEL PRODUCTIONS LTD.
784 - 788 HIGH ROAD, TOTTENHAM, N.17 PHONE: TOT 0732/0940

Springs
and wire
shapes
in all metals
Helical
Tension
Compression
and Torsion
Springs
from 40 s.w.g.
to 3/16" dia
wire
in any
quantity

Fully A.I.D.
and A.R.B.
approved

When answering advertisements kindly mention **MACHINERY**.

ORMEROD



* Shapers 10"-36"
* Slotters 4"-24"

TRAVERSING HEAD SHAPING MACHINES

FOUR SIZES 16", 20", 26", 32"
SINGLE OR DOUBLE HEAD, BED LENGTHS TO SUIT REQUIREMENTS

Powerful, Precise, Versatile, with a capacity for machining large components of unusual shape, a variety of tables available, or with special vee block equipment as illustrated.

● WRITE FOR DETAILS

ORMEROD SHAPERS LIMITED


HEBDEN BRIDGE · YORKS

Phone: Hebden Bridge 17

When answering advertisements kindly mention MACHINERY.

Portable Power with

DONOVAN "RUNCTACT" overhead bus-bar equipment
travelling contact type



Illustrated is an installation fitted to
a 2-ton crane, manufactured by
AaBACas Engineering Co. Ltd.

Donovan "Runctact" power duct is ideally suitable for feeding electric power to hoists or small cranes, and enables portable power to be supplied over long lengths with the utmost facility. Other applications are Moving Test Lines, Production and Assembly Lines, and Portable Tools. Outstanding features include:

- Enclosed conductors which eliminate hazards of exposed wiring.
- Standard straight or curved sections can be applied to most installations.
- Adaptable to existing as well as new installations.

Further details on application.

THE DONOVAN ELECTRICAL CO. LTD.

GRANVILLE STREET - BIRMINGHAM 1

Phone MIDland 5683

London Depot: 149-151, York Way, N.7. Phone: GULliver 7898.

Glasgow Depot: 22, Pitt Street, C.2. Phone: CENTral 0056/7.

Sales Engineers available in LONDON - BIRMINGHAM - BELFAST - MANCHESTER - GLASGOW - BOURNEMOUTH

When answering advertisements kindly mention MACHINERY.


BRITISH-BUILT MULTISLIDE MACHINES



offer new opportunities



to produce *Intricate Stampings*



automatically and cheaply!

Most stampings, from simple brackets to intricate parts, which previously required operations on several presses, each with its own operator, can now be produced automatically with great accuracy, at high speed, on *ONE* British-Built U.S. Multi-Slide Machine. If you use a number of presses to produce stampings or if you use progression tools for parts made from coiled material up to 3½" wide, here are reasons why we are almost certain to be able to send you a most interesting proposal.

1. The extreme accuracy of the feed employed and the fact that bending tools can be adjusted independently

makes it much easier to obtain a high quality part. 2. Sturdy construction of machine and its attachments as well as instantaneous braking through monitoring devices, increase tool life and reduce risk of tool breakages.

3. Material is saved because no extra material width is usually required either for piloting or side-cropping. The developed blank is in continuous strip, *not* held in a material webbing which becomes scrap. Material savings up to 25 per cent. are possible. In some cases production can be doubled by making two components from one strip.

ROCKWELL
MACHINE TOOL CO. LTD.

For further particulars write or telephone TODAY

WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033

ALSO AT BIRMINGHAM—TEL: SPRINGFIELD 1134/5 • STOCKPORT—TEL: STOCKPORT 5241 • GLASGOW—TEL: MERRYLEE 2822


When answering advertisements kindly mention MACHINERY.

C★

Great News


in PRECISION SURFACE

MATRIX
COVENTRY GAUGE &
TOOL COMPANY LTD.




THOMPSON
SURFACE
GRINDER Type 'B'



Normal Crushing Position also Truing or Dressing



Touching up Position



Re-processing Position



THOMPSON
TRUFORMING
CONTOUR
GRINDER

Write or telephone TODAY for full details.

WELSH HARP, EDGWARE ROAD, LONDON, N.W.2. Telephone: GLAdstone 0033

When answering advertisements kindly mention MACHINERY.

E CONTOUR GRINDING!

COVENTRY GAUGE & TOOL CO LTD

MANUFACTURE

THOMPSON GRINDING MACHINES

From 8" x 24" to the very largest sizes and TRUFORMING MACHINES

OUTSTANDING FEATURES OF THE THOMPSON SURFACE GRINDERS

MAXIMUM RIGIDITY.

Bed ways twice length of worktable surface. Exceptionally heavy column supports cross-slide on flame-hardened and ground dove-tail ways. Accurate wheel-head positioning to work. Patented anti-friction elevating nut eliminates 'wind-up' between nut and screw.

INTEGRAL MOTOR DRIVE AND WHEEL SPINDLE.

Dynamically balanced unit delivers full power to wheel, running in anti-friction or the famous Thompson plain bearings.

ACCURACY, QUALITY and FINISH

are assured by use of small increments of down feed and wide increments of cross-feed up to 100 feet per minute table speed.

AUTOMATICALLY LUBRICATED TABLE WAYS.

Cross slide and column ways lubricated by centralised one-shot oiling system. Extra large built-in coolant tank.

'IN POSITION' TRUING.

Hydraulic feed to wheel-head for rough and finish dressing. Vertical hand wheel graduated to .0005" and cross feed hand wheel to .001". Table speeds: 10 to 100 feet per minute. Rapid traverse: 240 feet per minute.

BRIEF SPECIFICATION OF THE THOMPSON TRUFORMING CONTOUR GRINDER

The "TRUFORMING" principle was pioneered by Thompson and is indispensable for the grinding of complex contours on aircraft engine parts, thread chasing dies, automotive components and office machinery parts.

A feature of this machine is the integral motor drive to wheel spindle with additional slow-speed drive.

The worktable is equipped with reference roll station and power driven work roll station.

Hydraulic table feeds range from 75 feet to 3" per minute and all the many well-known Thompson features are embodied in this superb grinder.

The diagrams on the left show how the Thompson 'Truforming' principle operates with two crushing rolls, a work roll and a reference roll.

SOLE SELLING AGENTS

ROCKWELL
MACHINE TOOL CO. LTD.

ALSO AT BIRMINGHAM—TEL: SPRINGFIELD 1134/5 • STOCKPORT—TEL: STOCKPORT 5241 • GLASGOW—TEL: HERRYLEE 2822

When answering advertisements kindly mention MACHINERY.

NEW DESIGN!

**LARGER
CAPACITY!**

Latest

THIEL

FILING & SAWING MACHINE

for the manufacture of Dies,
Gauges etc. to very close limits



MODEL
115

**SPECIAL ATTACHMENT
PERMITS FILING & SAWING
OF HARDENED STEEL
& TUNGSTEN-CARBIDE**



SPECIAL FEATURES include—

- Infinitely Variable Speed
- Infinitely Variable Stroke Adjustment
- Stroke adjustment does not necessitate altering table height
- Table tilts 15° in both directions
- Tungsten-Carbide and Hardened Steel filing and sawing (Special attachment)

ROCKWELL
MACHINE TOOL CO. LTD.

For further particulars write or telephone **TODAY**

WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033

ALSO AT BIRMINGHAM—TEL: SPRINGFIELD 1134/5 • STOCKPORT—TEL: STOCKPORT 5241 • GLASGOW—TEL: MERRYLEE 2022

what are you waiting for?

You want Precision Hobs? We can supply them! Spur, helical, worm wheel, spline or serration, made precisely to your requirements,

Our standard Spur and Helical range is designed to cover all normal requirements and to give you speedy deliveries, in many cases actually from stock.

If you have not been using David Brown Precision Hobs, write now for Leaflet E313.9 and get yourself acquainted with our quality and our service.




THE
DAVID BROWN
CORPORATION (SALES) LIMITED
TOOL DIVISION
PARK WORKS HUDDERSFIELD

When answering advertisements kindly mention MACHINERY.



ROLLS-ROYCE

use the best—
and the fastest
method of milling
LIGHT ALLOYS



Wadkin Vertical Milling Machine L.H.1. with cutting speeds up to 18,000 r.p.m. face milling a steering box. Photographs by courtesy of Rolls-Royce Ltd., Crewe.

***This steering box
is face machined
in 20 seconds!***

Rolls-Royce Ltd., like many other famous firms, appreciate the benefits of using a machine specially designed for milling Non-ferrous metals. Their Wadkin Vertical Milling Machine L.H. face mills their light alloy components, such as the steering box shown above, in a fraction of the time taken by any other method. And it does so with the accuracy and finish associated with Rolls-Royce standards. The Wadkin type L.H. consists of one basic machine of plain, robust and inexpensive design, with three alternative head arrangements. Each head has cutting speeds far higher than orthodox millers, permitting feeds as high as 84" per minute. Leaflet No. 811, giving full details will be sent on request.

Tel: Leicester 68151

Wadkin Ltd., Green Lane Works, Leicester

Wadkin

Tel: MAYfair 7048

London Office: 62-64 Brook Street, W.1

When answering advertisements kindly mention MACHINERY.

GIUSTINA Hydraulic UNIVERSAL GRINDERS


*These outstanding
grinders are now
available in
six sizes*

- ★ Hydraulic feed to table.
- ★ Automatic hydraulic feed to grinding wheel.
- ★ Wheel can be mounted on both sides of spindle.
- ★ Rapid change over from external to internal grinding.
- ★ Separate motor drive to internal grinding spindle.

12" x 40" capacity
IMMEDIATE DELIVERY
FROM LONDON STOCK
OTHER SIZES EARLY DELIVERY

INTERNAL GRINDING

Max. dia. of hole 10"
Spindle speed ... 18,000 r.p.m.



PLEASE SEND FOR FULL DETAILS

Exclusive Distributors in the United Kingdom

ELGAR

MACHINE TOOL COMPANY LIMITED

RIGHT OPPOSITE NORTH ACTON STN.

172-178 VICTORIA ROAD · ACTON · LONDON W3 · Telephone ACORN 5555

Midlands Office and Showrooms: 1075 KINGSBURY ROAD, ERDINGTON, BIRMINGHAM 24. Tel. Castle Bromwich 3781/2

Scottish Agents and Showrooms: ANGUS & CRICHTON (SALES) LTD., 37 DALMARNOCK ROAD, RUTHERGLEN, LANARKSHIRE
NRP

STOCK OFFICE



90,000 *high-speed toolbits
in 80 different types*

30,000 *butt-welded tools
in 55 standard shapes
and 15 shank sizes*

**WE HOLD THESE IN STOCK TO MEET
YOUR IMMEDIATE REQUIREMENTS**

Our monthly stock list will be sent on request

JESSOP-SAVILLE

*high-speed steel
butt-welded tools and toolbits*

WM JESSOP & SONS LTD

BRIGHTSIDE WORKS SHEFFIELD



J J SAVILLE & CO LTD

TRIUMPH WORKS SHEFFIELD

A Member of the BSA Group

When answering advertisements kindly mention MACHINERY.



Model U100 T.A.

The NEW PEGARD

UNIVERSAL HORIZONTAL BORING & MILLING MACHINE

These magnificent machines perform a wide variety of boring, facing and drilling operations at high speeds and to precision standards. They are specially designed to give the maximum output at the lowest possible costs. The operator can control all operations from one position at the headstock, and an illuminated control panel gives clear pre-indication of all motions selected.

One of our Technical Representatives will gladly visit you, on request, to discuss any special machining problems as Pegard machines can readily be adapted to a variety of applications.

BRIEF SPECIFICATIONS

SPINDLE DIAMETER	4 ins.
SPINDLE TAPER	No. 6 Morse
SPINDLE TRAVERSE	39½ ins.
FACING HEAD DIAMETER	23½ ins.
TRAVERSE OF THE SLIDE IN FACING HEAD	11 ins.
MAXIMUM DIAMETER OF FACING	43 ins.
18 SPEEDS OF THE SPINDLE	71 to 1400 r.p.m.
9 SPEEDS OF THE FACING HEAD	71 to 280 r.p.m.
HORSE POWER OF THE MAIN MOTOR	13½ h.p.

Sole Agents in the
United Kingdom

GEORGE COHEN

SONS AND COMPANY LIMITED



SUNBEAM ROAD, LONDON, N.W.10 TEL. ELGAR 7222/7

STANNINGLEY, NE. LEEDS TEL. PUDSEY 3341

When answering advertisements kindly mention MACHINERY.

Electro-Heat

The ways in which electricity can be used to advantage in industry are many and varied. Some are well known but others are not known well enough. For this reason the Electrical Development Association has prepared a series of detailed data sheets on various applications which will be printed in this journal from time to time.

All the applications of electro-heat have these advantages in common:—

- 1 Electro-heat is clean both in regard to its application and the method of generation.
- 2 It can easily be controlled more precisely than any other form of heat, manually or automatically.
- 3 It can be brought to the job instead of having the job brought to it.
- 4 It permits better use of floor space and the elimination of unnecessary handling.
- 5 In many of the newer processes it is the only possible form of heat which can be used.
- 6 It often ensures a higher quality of products with fewer rejects.
- 7 It gives the best working conditions.
- 8 It effectively reduces or eliminates fire and explosion hazards.

Below will be found brief notes on some of the various methods of generating heat by electricity.

Resistance Heating

This is the best known form of electric heating. The elements provide a high resistance to the passage of electricity and thus heat is generated. It can be used in furnaces for melting or heat treatment of any material whether metal or not, or the resistance of the workpiece itself can cause the generation of heat.




Induction Heating

Eddy currents are induced in the surface of a conducting workpiece, heating it up. The depth to which this heating will penetrate is determined by the time it is given.



High-frequency Dielectric Heating

This form of electro-heat can be used only on non-conducting materials such as wood, plastic and rubber. The material is placed between two electrodes to which a high voltage is applied at a high frequency. This has the effect of generating heat inside the material rapidly and uniformly throughout its entire thickness.



Infra-red Heating


This method employs pure radiant heat. The bulk of the radiation takes place in the infra-red portion of the radiation frequency spectrum. The heaters may take the form of reflector lamps or sheathed wire elements. The method is extremely flexible and has many uses, including paint drying and pre-heating plastics.



Arc Melting

This form of heating is chiefly used for melting steel. The diagram illustrates one method of operation.

Very large charges can be melted; melting units of 200 tons capacity are now in operation.



The Application of Electro-Heat

All these methods of electric heating can be applied in almost an infinite variety of ways. Some of these ways will be dealt with in subsequent sheets.

For further information, get in touch with your Electricity Board or write direct to the Electrical Development Association, 2 Savoy Hill, London, W.C.2.

Excellent reference books on electricity and productivity (8/6 each or 9/- post free) are available — "Induction and Dielectric Heating" is an example; "Resistance Heating" is another.



E.D.A. also have available on free loan a series of films on the industrial use of electricity. Ask for a catalogue. 4869/4

ARCHDALE

18" VERTICAL MILLER WITH FIXED OR SWIVELLING HEAD

With a range of eighteen spindle speeds from 80 to 2000 r.p.m. and four rates of automatic longitudinal table feed for each speed, these machines are capable of handling a very large range of work at fast rates. At Integral Ltd., Wolverhampton, several operations are carried out on aircraft hydraulic pump casings as shown.


Table working surface 10" x 31". Maximum distance, spindle nose to table 18". Available with fixed or swivelling head. Ask for details.



*** WIDE RANGE OF SPEEDS FOR
MAXIMUM PRODUCTION ON ALL
MATERIALS**

JAMES ARCHDALE & CO. LTD.
LEDSAM STREET, BIRMINGHAM, 16.
Telephone No. EDGBaston 2276

A Member of the Staveley Coal & Iron Co. Ltd. Group
Sole Agents: **ALFRED HERBERT LTD.**
COVENTRY
Telephone No. 89221



When answering advertisements kindly mention MACHINERY.

EFFICIENT PRESS SHOPS NEED UP TO DATE FEEDING EQUIPMENT


Vertical Motorised coil feeder or
winder



Inclinable Motorised coil feeder or
winder takes 3 cwt. coils




M.I.1



M.4

Inclinable Motorised Straighten-
ing Machine up to 6" wide x
.080" thick material



M.I.C.6

M. 1 takes 3 cwt. coils
M. 4 takes 4 cwt. coils
M.10 takes 10 cwt. coils

Rate of feed on all models 0 to
35 ft. per minute, controlled by
trip arm

* MOTOR, BEARINGS, FRICTION CLUTCH & MERCURY OR MICRO
SWITCH ALL TOTALLY ENCLOSED

WRITE NOW for full details of these and other items of Press Shop Equipment
including non-motorised types

W. T. ATKIN (TOTTENHAM) LTD



178 ST. ANN'S ROAD • LONDON N.15

Tel: STAmford Hill 6686-7 • Grams: Pressing, Southtot, London • Overseas Cable: Pressing, London

When answering advertisements kindly mention MACHINERY.

Prolite**FUTUR MILLS**

for
**GIRDER END
FACINGS**



* For further particulars please consult our engineers who are always available to assist with all tungsten carbide machining problems.

The 'Prolite' Futur Mill has been selected for use on the new Girder End Facing Machine manufactured by William Asquith Ltd. of Halifax.

This cutter has proved itself to be ideal for this and similar applications within the constructional steel industry because of the simplicity of servicing, no elaborate cutter grinding being necessary. Its usefulness is, however, not confined to one particular industry; wherever face milling is undertaken the Prolite Futur Mill can prove its merits.

Home Sales: **PROTOLITE LIMITED** (a subsidiary company of Murex Ltd., Rainham, Essex), **CENTRAL HOUSE, UPPER WOBURN PLACE, LONDON, W.C.1.** EUSion 8265. Telegrams: *Prolite, Kincross, London.*
Export Sales: **MUREX LIMITED** (Powder Metallurgy Division), **RAINHAM, ESSEX.**
Telex: 28632. Telegrams: *Murex Rainham-Dagenham Telex.*

When answering advertisements kindly mention **MACHINERY**.



Photograph by kind permission of Guy Motors Ltd.

Carrying the load


Contributing to the reliable performance and ease of operation of vehicles made by Guy Motors Limited, Torrington Needle Bearings are used in transmissions, brake cam shafts, change speed mechanisms and brake hook-up arrangements.

Smooth efficient operation and easy maintenance are assured since the bearings start and operate with the minimum of friction and retain lubricant effectively.


If your product would benefit from compact, anti-friction Needle Bearings with high capacity, long service life at low cost, write to our Bearings Division.

TORRINGTON BEARINGS


THE TORRINGTON COMPANY LTD.
BEARINGS DIVISION: TORRINGTON AVENUE, COVENTRY
LONDON & EXPORT OFFICE: 7-10 ELDON STREET, E.C.3
GLASGOW OFFICE: 14 MOIR STREET, CI



The Henry Meadows Type 450 C5 five-speed gearbox, in which Torrington Needle Bearings support mainshaft gears, transmits the power in the Guy 'Invincible' Chassis.



TURNERS INTRODUCE
THIS SYMBOL



CONVEYOR AND
POWER BELTING

The mark of Better Belting


TURNER BROTHERS ASBESTOS CO. LTD. ROCHDALE ENGLAND

A MEMBER OF THE TURNER & NEWALL ORGANISATION

dmTA41

When answering advertisements kindly mention MACHINERY.

D2



Where
strict
accuracy
is
demanded

important firms
SPECIFY DELAPENA EQUIPMENT

The production of hydraulic cylinders for Testing Machines demands a high degree of accuracy, and W. & T. Avery Limited have increased their output of these components by using the Delapena 276 Beam Stroker for bores varying from $\frac{3}{8}$ " to $16\frac{1}{4}$ " and up to 4' 6" in length.

Combined with this versatility are speed and accuracy unequalled by any other process, coupled with better finish and closer tolerances that have reduced rejections to a minimum. Can you afford to ignore the many advantages that honing by Delapena equipment can bring? Why not give us a ring and talk it over?

Delapena


HONING EQUIPMENT

DELAPENA & SON LIMITED

Manufacturers of Induction Heating and Precision Honing Equipment


ZONA WORKS • CHELTENHAM • ENGLAND

Telephone: CHELTENHAM 86341



When answering advertisements kindly mention MACHINERY.

**Skilled hands
appreciate . . .**



The Eclipse Range of tools includes:—


Hack Saw Blades and Frames . . . Sheet Saws . . . Surface Gauges
Automatic Centre Punches . . . Scribers . . . Tap Wrenches . . . Pin Vices
Pin Tongs . . . Angle Plates . . . Vee Blocks . . . Tool Bits & Tool Bit Holders
Saw Sets . . . Coping Saws . . . Junior Saws . . . Piercing Saws . . . Fret Saws
Jig Saw Blades . . . Trammel Heads . . . Instrument Vices . . . Pad Handles
Permanent Magnets . . . Magnetic Chucks and Magnetic Tools

Made by James Neill & Co. (Sheffield) Ltd., and obtainable from all tool distributors

UX13

When answering advertisements kindly mention MACHINERY.

**TRADITIONAL
CRAFTSMANSHIP
BACKED BY
THE LATEST
TECHNICAL
RESOURCES**



Bakersteel

**FINE STEEL CASTINGS
CARBON • ALLOY • STAINLESS**

We would never pretend that our castings are perfect, but we do know that they are as good as eighty years' experience, the finest electric melting plant and strict metallurgical and physical control can make them.


Our capacity is from a few pounds to 30 cwt. in carbon, alloy and stainless steel, and your enquiries for small or large quantities will receive prompt attention.

W. A. BAKER & CO., LTD., WESTGATE WKS., NEWPORT, MON.


PHONE: NEWPORT 64845.

**DIVISION OF BLACK-CLAWSON INTERNATIONAL, LTD.
MAKERS OF PAPER MILL PLANT**

When answering advertisements kindly mention MACHINERY.

AMAR*interchangeable* TOOL SET*Bigger range and new features*

Now available in four sizes of bolster sets to accommodate twelve sizes of dies from 3" x 3" to 7" x 9". Tool changing is achieved on the press within seven minutes, without disturbing bolsters. Bolsters on the larger sizes incorporate ball-bearing bushes, for easy assembly and freedom from jamming.



Manufactured under British Patent No. 709066

For full information write for publications 507/1 and 1101

AMAR TOOL AND GAUGE COMPANY LIMITED

Amar Works, Grove Road, Chadwell Heath, Essex

Telephone: Seven Kings 3471-2-3, 5090 and 5369 • One of the Plessey Group of Companies

 P.T.4A

Appointed Stockists of NYLOC, FIBRE & PINNACLE self-locking nuts—the modern method of safe assembly

- 1 THE ALDER HARDWARE & ELECTRICAL CO. LTD.**, 199 New King's Road, Fulham, LONDON, S.W.6.

Telephone: Renown 6421. P.B.X.

LEWIS HUNTER & CO., 25 Laurence Pountney Lane, Cannon Street, LONDON, E.C.4.

Telephone: MINcing Lane 8805 and 9082.

H.S.S. LTD., 25 Church Road, TEDDINGTON, Middlesex.

Telephone: Molesey 4441-5.

H.S.S. LTD., Cox Lane, CHESSINGTON, Surrey.

Telephone: Lower Hook 1005-9.

F. MILLER & CO. (LONDON) LTD., Rectory Road, Acton, LONDON, W.3.

Telephone: Acorn 5201. P.B.X.

F. MILLER & CO. (LONDON) LTD., Cambridge Avenue, SLOUGH, Bucks.

Telephone: Slough 25511 (10 lines).

TELCO LTD., 3 Newman Street, LONDON, W.1.

Telephone: MUSeum 5701 (4 lines).

- 2 W. H. & G. WALKER & CO.**, 11 Edward Street, Parade, BIRMINGHAM 1.

Telephone: CENTral 0575.

G. F. BRIDGES LTD., 63 Snow Hill, BIRMINGHAM 4.

Telephone: CENTral 3911 (5 lines).

- 3 RANDALLS LTD.**, 20-22 St. Mary Street, BEDFORD.

Telephone: BEDford 67488.

- 4 THE NEEDHAM ENGINEERING CO. LTD.**, P.O. Box No. 23, Townhead Street, SHEFFIELD 1.

Telephone: SHEffield 27161 (10 lines).

- 5 THE HULL FACTORING CO. LTD.**, 227-229 Anlaby Road, HULL, East Yorkshire.

Telephone: 36725 (3 lines).

- 6 MACNAYS LTD.**, G.P.O. Box 14, MIDDLESBROUGH, Yorks.

Telephone: Middlesbrough 45111 (7 lines).

- 7 D. F. WISHART & CO. LTD.**, P.O. Box No. 74, 18 Picardy Place, EDINBURGH, 1.


Telephone: Waverley 1444 (5 lines).

- 8 LAND, SPEIGHT & CO. LTD.**, 2 Fitzroy Place, Sauchiehall Street, GLASGOW, C.3.

Telephone: CENTral 1082-3.

- 9 KENNEDY & MORRISON LTD.**, 12 Library Street, BELFAST.

Telephone: BELfast 30231 (5 lines).



- 10 SMITH, NICHOLSON & WEST LTD.**, P.O. Box No. 10, Gaol Lane, HALIFAX.

Telephone: HALifax 5757 (6 lines).

- 11 J. A. CHALLINER & CO. LTD.**, 77-83 Downing Street, MANCHESTER 1.

Telephone: ARDwick 3221-2-3.

- 12 J. R. SMITH & SONS (STRUCTURAL) LTD.**, Hamworthy, POOLE, Dorset.

Telephone: POole 1300 (7 lines).

- 13 JOHN HALL (TOOLS) LTD.**, 23 Churchill Way, CARDIFF and all branches.

Telephone: CARDiff 22242 (7 lines).

- 14 WOODBERRY, CHILLCOTT & CO. LTD.**, 122 Victoria Street, BRISTOL 1. G.P.O. Box 236.

Telephone: BRistol 26524 (6 lines).

- 15 TOM WALLACE (LIVERPOOL) LTD.**, Hope Street, LIVERPOOL 1.

Telephone: LIVERpool Royal 6401 (5 lines).

TOM WALLACE (LIVERPOOL) LTD., 52 Cleveland Street, BIRKENHEAD.

Telephone: BIRkenhead 3434.

Merchant enquiries to nearest Stockist please!

SIMMONDS AEROCESSORIES LIMITED

TREFOREST, PONTYPRIDD GLAMORGAN


Branches: London, Birmingham, Manchester, Glasgow, Stockholm, Copenhagen, Ballarat, Sydney, Johannesburg, Naarden, Milan and New York



A MEMBER OF THE FIRTH CLEVELAND GROUP


The **NEW** Improved design of the **VICKERS-DETROIT** solenoid pilot operated directional valves

- 1 Provision for manual shift of spool with dustproof and moistureproof seal
- 2 Standard continuous duty solenoid (safety interlock with cover)
- 3 Ample porting for large capacity
- 4 Sealed and chained nameplate cover reversible for reading
- 5 Ample wiring space— $\frac{3}{4}$ " B.S. conduit connections on 2 sides
- 6 Gasket or subplate (Threaded conn.) mounting
- 7 Readily converted for internal or external pilot pressure
- 8 Pilot spool retained when solenoids removed
- 9 Test connections
- 10 Precision ground surfaces



by **STEIN ATKINSON**
S.A.V. HYDRAULI

EASIER INSTALLATION
LESS MAINTENANCE
LONGER SOLENOID LIFE



VICKERS-DETROIT hydraulic 2- and 4-way valves provide the optimum in directional control. They are compact, versatile, and are designed for heavy duty, continuous and rapid cycling operation on all types of industrial machinery. More than a decade of application experience and years of research and development back all the valves' features.

Seven spool types satisfy a wide variety of circuit needs and operate at pressures to 3000 psi.

Installation is simplified with ease of wiring and a minimum of piping. The valves are available for gasket or sub-plate mounting. Mounting position is unrestricted except in "no-spring" models.

The valves conform to JIC Standards and are available in $\frac{1}{8}$ " and $\frac{1}{4}$ " direct solenoid operated models . . . $\frac{3}{8}$ " and $1\frac{1}{4}$ ", solenoid controlled pilot operated models.

For further information, write for Publication 1 /43.

STAND NO. 582: NATIONAL HALL GALLERY,
PUBLIC WORKS & MUNICIPAL SERVICES
EXHIBITION—Olympia, Nov. 18-15.

VICKERS HYDRAULICS LIMITED
197 Knightsbridge London S.W.7

Broadway/savh/43

An Invitation

THE MORTIMER ENGINEERING COMPANY

and

STANHOPE MACHINE TOOLS LTD.

invite you to a

JOINT EXHIBITION OF OUTSTANDING MACHINE TOOLS

on

October 20th — October 31st, 1958

at 202-206 Acton Lane, Harlesden, London, N.W.10

(5 minutes Harlesden Underground)



Special Machines to be demonstrated under power include:

RAVENSBURG KH 55 — Unicop Electronic Hydraulic Face Copying Lathe

This is the new model with solely hydraulic movements: there is no similar machine available on the market today.

RAVENSBURG KT 45 — Hydraulic Face Copying Lathe

MAHO Universal Jig Miller and Die Sinker — 3 models

FROMAG Hydraulic Keyseaters

GAMBIN Universal Milling Machines with bi-rotary sliding heads

G.S.P. Automatic Co-ordinate Jig Boring Table

ROUCHAUD Automatic Cycle Production Milling Machine



also **KOPING** Lathes and Milling Machines, **THULE** Surface Grinders,

Carstens Precision Grinders, **Webo** Radial Drilling Machines (with infinitely variable speeds and feeds), **G.S.P.** high-speed Shaping Machines, etc. The **Ainjest**

revolutionary screwcutting attachment enabling standard lathes to be used for high-speed screwcutting.

Telephone: ELGar 3834

REFRESHMENTS

When answering advertisements kindly mention MACHINERY.



DANGER—eyes at work

Danger—flying sparks! Danger—molten metal! Danger—splashing acids!

Tough, clear and shatter-proof, Celastoid acetate sheeting is a safe shield against so many industrial hazards. Uniquely suitable for visors, goggles and machine guards, Celastoid does not shatter, crack or splinter. Between the worker and his work Celastoid provides economic and lasting protection.

**need the
safety of**

* *The Celanese Technical Advisory Service, with its unrivalled experience, is freely available to assist you with any special safety problems you may have.*

Celastoid

ACETATE SHEET

Shatterproof Celastoid is a product of the

PLASTICS DIVISION, BRITISH CELANESE LTD., HANOVER SQUARE, LONDON W.1 MAYfair 8888

RM A-5




Never satisfied! Always improving! A steady progress towards perfection — burbled the Managing Director in his most self-satisfied voice. Take Pneumatic Drills. Efficient, you say—but perhaps a trifle noisy for the assembly line.

Sir, you are living in the past. This Little Horse here ("this 'ere Little Horse, if you please" muttered the Little Horse in question) operates a drill. Note that we have fitted him with a kind of gag or muffler, thus reducing the operating noise level by more than 50%. The principle is really very simple—as I will now demonstrate. I place this muffler over my mouth . . . so . . . I will now ask any member of the audience to wrap the ends—thank you sir, — round behind my ears . . . and N'mm M'mm Er'm Ah'rmm Hurh'mm mm-m-mm . . .!

(The audience agreed that the noise level had indeed dropped by well over 50% and the Managing Director was carried out, black in the face, amid loud cheers).

These drills are now fitted with a chuck guard silencer and an improved plastic grip. Let us send you a leaflet giving you full details of the whole new range.



THE NEW **DESOUTTER** **SILENT DRILLS**


Manufactured by Desoutter Bros., Ltd., London.

DESOUTTER BROS. LIMITED, THE HYDE, HENDON, LONDON, N.W.9.
TEL: COLINDALE 6346. 'GRAMS: DESPNUCO, HYDE, LONDON.

CRC 281B

When answering advertisements kindly mention **MACHINERY**.

Think hard-think
EDIBRAC



For further details
write for catalogue

EDIBRAC LIMITED

Manufacturers of

Tungsten Carbide Tipped Tools and Cutters

Made entirely at

CENTURION WORKS BROADHEATH NR. MANCHESTER


dm EC21/1

TAP FASTER TAP BETTER

and at less cost
with

ARCHER


AUTO-REVERSE
TAPPING ATTACHMENTS



Automatic reverse
at twice the
tapping speed

- ★ Simple to operate.
- ★ Takes Standard Hand Taps.
- ★ Fitted with safety friction drive.
- ★ Hardened nickel chrome steel gears.

Safety friction
drive eliminates
tap breakages



★ Ask for List
No. 105

"ARCHER" Tapping Chucks are also made as separate units for tapping operations where the auto-reverse is incorporated on the machine, and can be supplied with friction drive having the Morse Taper Shank integral with the friction box; or for positive drive having Jacobs No. 2 series taper bore.

FRANK GUYLEE & SON LTD.

ARCHER TOOL WORKS · MILLHOUSES · SHEFFIELD 6

Telegrams: "Guylee, Sheffield".

Telephone: 50061-2

When answering advertisements kindly mention **MACHINERY**.

Diamonds for Industry

- * Wheel dressing diamonds.
- * Shaped diamond tools for turning and boring.
- * Thread grinding tools.



VAN MOPPES LTD **DIAMOND TOOL SPECIALISTS**

Consult us on your requirements for industrial diamonds for all purposes. We can place at your disposal a long and specialised experience covering a wide variety of problems. Meantime, write for a copy of our latest brochure.

S. L. VAN MOPPES LTD


Head Office : ST. ANDREW'S HOUSE, 32/34 HOLBORN VIADUCT, LONDON, E.C.1

Tel.: FLEET ST. 2731-2

When answering advertisements kindly mention MACHINERY.



For all practical purposes, there is no limit to the size, ratio and type of worm reducer you can order from Holroyd. We can give immediate delivery of our standard units up to 12 inch centre distance, from a choice of 340 combinations of type, ratio and size shown in the table below. Reduction gears over 12 inch centre distance can usually be assembled for you fairly quickly. Send for the 50-page book about Holroyd worm speed reducers and you will always have complete details of the whole range by you for quick reference.



Holroyd HU	Single reduction underdriven with horizontal input and output shafts. Centre distances 3, 4, 5, 6, 7, 8, 9, 10 and 12 inches.
Holroyd HO	Single reduction overdriven with horizontal input and output shafts. Centre distances 3, 4, 5, 6, 7, 8, 9, 10 and 12 inches.
Holroyd HV	Single reduction with vertical output shafts and horizontal input. Centre distances 3, 4, 5, 6, 7, 8, 9, 10 and 12 inches.
Holroyd Verso	2½ inch centre distance. Suitable for underdriven, overdriven or side mounting.
Holroyd F	Made in three sizes—1½, 1¾ and 2½ inch centre distance, and suitable for a variety of mounting positions.
All the above are available with any of the following ratios:—5, 7½, 10, 15, 20, 25, 30, 40, 50, 60 and 70 to 1.	

**All these
can be
delivered
from stock**


Holroyd

90 YEARS OF GEARS

JOHN HOLROYD & CO. LTD., MILNROW, LANCASHIRE

When answering advertisements kindly mention MACHINERY.

CRC 191



This large SKODA LATHE was supplied by The Selson Machine Tool Co., Ltd., to the new Faringdon (Leyland) Factory of BTR Industries Ltd., by whose courtesy this photograph is reproduced.

The Selson Machine Tool Co. Ltd

41-45 MINERVA ROAD, NORTH ACTON, LONDON, N.W.10

Telephone: Elgar 4000 (10 lines) Telegrams: Selsomachi, London, N.W.10



Fifty years of High Precision



MIKRON S.A. (1908-1958)

*who this year celebrate their Golden Jubilee
offer their extensive experience and knowledge for*

ALL FINE PITCH GEARS

in the following machines

- ☆ Precision Gear Hobbers (12-400 D.P.)
- ☆ Shaping Machines
- ☆ Thread Millers
- ☆ Hob Sharpening Machines
- ☆ Hobs and Cutters
- ☆ Precision Lathes and Millers

Often Copied—Never Equalled

Sole U.K. Agent :

HENRY TURNER *(Machine Tools) LIMITED*

58 UPPER TOOTING ROAD, LONDON S.W.17


SUPER HIGH SPEED DRILLING **DEMANDS** **CORONA**

**SINGLE OR MULTIPLE SPINDLE
MODELS TO SUIT EVERY NEED**

- ▶ **ADJUSTABLE HEADS**
- ▶ **$\frac{1}{8}$ in. CAPACITY DRILL CHUCK**
- ▶ **8 SPEEDS THROUGH PICK-OFF GEARS**




MODEL 15 HF
BENCH MACHINE UP TO SIX SPINDLES



MODEL 15 HFHD
DOUBLE END WITH ADJUSTABLE HEADS
CAN BE SUPPLIED WITH COUPLED FEED
ALSO AVAILABLE WITH SINGLE HEAD

MODEL 15 HA
COLUMN MACHINE
WITH ADJUSTABLE TABLE
UP TO SIX SPINDLES




FREDK POLLARD & CO LTD
CORONA WORKS, LEICESTER, ENGLAND
TELEPHONE: LEICESTER 67534 (5 lines)

London Office: COASTAL CHAMBERS, 15 ELIZABETH ST., BUCKINGHAM PALACE RD., S.W.1 TEL: SLOANE
Scottish Representatives: WALTER S. LANG & CO., 48 OSWALD STREET GLASGOW C.1. TEL: CENTRAL 2539

HY-OP

JIG BORING MACHINE



Manufactured by: Apparatebau Burkhardt, Pfullingen-Würt.

Direct optical reading of co-ordinates.

B O R I N G I S N ' T I T ?

We beg you will not trouble to read this—unless, of course, you are interested in the precision boring of jigs, machine tool parts, prototypes or single components to the greatest accuracy. The HYOP 54 Co-ordinate Machine, designed primarily as a high-precision jig-borer, will handle, also, finish-milling, internal grinding and honing. Hydraulic control—infinately variable in all directions—of the table and sliding head, with **infinately variable** spindle speeds, give this machine its very considerable versatility.

Specialised design has achieved both great capacity and an extremely fine surface quality. The HYOP 54 has an **optical measuring** system which gauges, on its luminous screen, accurately to within 0.0002in. (Adjustment accuracy 0.0001in.)

We believe that never before have production-speed, high-quality finish and absolute precision been so effectively combined in one jig-borer.

In use at such famous factories as: Daimler-Benz, Citroen, Admiralty, Wavis Engineering, Renault, Volkswagen, etc. Also in America (6), Sweden and Japan.

Size of table 47½in. by 30½in. Max. between table and spindle 25½in. or special 35½in. Boring rectangle 31½in. by 24½in.


stuart
DAVIS

STUART DAVIS LTD • MUCH PARK STREET • COVENTRY • PHONE: COVENTRY 63091-2

When answering advertisements kindly mention MACHINERY.

E2

Tapping Rod Ends at Lockheed



Galtona
TRADE MARK

GROUND THREAD TAPS

GALTONA ground thread taps are widely used at Lockheed Hydraulic Brake Co., Ltd., because of their ability to maintain high precision and long life under all conditions of service.

On a five-spindle automatic for instance, track rod ends are blind tapped 1 in. U.N. 16 t.p.i. using a special GALTONA ground thread five-flute tap.

GALTONA ground thread taps, standard or special, can be supplied to give improved accuracy and finish on all materials. Illustrated catalogue available on request.

Richard Lloyd Limited

GALTON HOUSE, ELMFIELD AVENUE, TYBURN, BIRMINGHAM, 24

Telephone Ashfield 1801. Telegrams "Cogs, Birmingham"

Northern Area Office: Britannia House, Wellington Street, Leeds 1. Telephone: Leeds 21212
London Area Office: 240 Romford Road, Forest Gate, London, E.7. Telephone: Maryland 7304-5

Still the best straight oil
SWIFT *



*when cutting
tough steels*

No matter the application, SWIFT oil, in its many forms, is a blessing when the tougher steels are tooled. Its sulphur-activated base prevents localised welding of chips to the tool face and materially assists the attainment of high output schedules.

There are SWIFT grades specially adapted to automatics, gear cutting, thread milling, form grinding, broaching and honing operations. And if you wish to cut non-ferrous materials on the same machines as steel, without changing the oil, the unique SWIFT S.S. series is your logical choice.

By asking for Publication SP.173—on your business letterhead please—you will receive up-to-date information on FLETCHER MILLER cutting fluids.



one of the

FLETCHER MILLER

cutting fluids

FLETCHER MILLER LTD., ALMA MILLS, HYDE, CHESHIRE.

Telephone: HYDE 3471 (5 LINES)

Telegrams: EMULSION, HYDE

Also at LONDON, WEST BROMWICH, NEWCASTLE-ON-TYNE, CARDIFF, GLASGOW AND BELFAST

CF 117

When answering advertisements kindly mention MACHINERY.



*moving only
in the best
circles—*

The **QUALCUT** twist drill

*the polished drill
with the polished performance—*

look for the




QUALCUT TOOLS LIMITED

Workshop Road, Sheffield 9,

Telegrams and cables: "Qualcut" Sheffield 9. Telephone 4102314

When answering advertisements kindly mention MACHINERY.



PRECIPITRON Electrostatic Oil Mist Filter
serving a centreless thread grinder.

Precipitron
REG. TRADE MARK SOLE LICENSERS

ELECTROSTATIC OIL MIST FILTER UNIT

... removes oil coolant mists at source from high speed cutting, grinding and other machining operations.

- Oil is salvaged.
- The filtered air may be safely returned directly to the workshop.
- Heat losses are reduced.
- Working conditions are improved.
- Damaging effects to machinery, fittings and building surfaces are prevented.

Electrostatic oil mist filtration was pioneered by Sturtevant in the United Kingdom with PRECIPITRON

For full particulars write for our publication MY 7106.

STURTEVANT



ENGINEERING CO. LTD.

Southern House, Cannon Street, LONDON, E. C. 4.


AUSTRALIA: STURTEVANT ENGINEERING CO. (AUSTRALASIA) LTD. 400 SUSSEX STREET SYDNEY N.S.W.

When answering advertisements kindly mention MACHINERY.

whatever
your
product...



can offer a
complete service



The Birmingham Tool & Gauge Company offers an unsurpassed service to an ever-increasing number of manufacturers in diverse fields of metal working. Although primarily manufacturers of special cutting tools of every description, both in High Speed Steel and Tungsten Carbide, our capacity embraces high quality precision engineering work and the manufacture of jigs, fixtures and inspection gauges. The same rigid adherence to meticulous standards of quality and finish that has always been reflected in our range of cutting tools, for which we have been renowned for nearly half a century, is now strictly observed in our new fields of activity.

BIRMINGHAM TOOL & GAUGE CO. LTD
SOHO HILL, HANDSWORTH, BIRMINGHAM, 19
Telephone: NORTHERN 3344 Telegrams: Relief, Birmingham, 19
London Office: 25 Holborn Viaduct, London, E.C.1
Telephone: Fleet Street 6454 Telegrams: Birmtool, Cont, London

Beardmore

increased output

Almost unlimited machining operations are performed by Sentinel Unit Machines, providing improved quantity and higher output. A wide range of standard columns, rotary tables etc. is available, and the installation shown is arranged for milling, drilling and cleaning the threaded end of a swivel axle for an automotive product.

**less time—less rejects
—less space—less effort
and overall economy with**

Sentinel

*unit machines
incorporating
the Renault-
France
system
electro-
mechanical
head*



Sentinel

adaptability — versatility — flexibility

Sentinel Unit Machines are built up from standard bases (with enclosed switchgear) and rotary tables, all of which have machined mating faces for assembly into varied combinations of units




SENTINEL (SHREWSBURY) LTD SHREWSBURY ENGLAND

When answering advertisements kindly mention MACHINERY.



**NO
LOSS OF
EFFICIENCY HERE**

*through vibration
or 'whip'*

When machines must operate
under load fluctuation
or conditions of misalignment



DUNLOP FLEXIBLE COUPLINGS HELP SMOOTH WORKING



Dunlop Couplings consist of flexible rubber elements bonded to metal ends. The rubber can be compounded with varying degrees of stiffness as required by the task the coupling has to do, but the physical properties are always controlled within fine limits. Dunlop Flexible Power Transmission Couplings can be used with confidence in applications where precision is vital.

DISC COUPLINGS

For heavier equipment, operating at up to 96 h.p. per 100 r.p.m.

BARREL COUPLINGS

For light machines and motors, operating at up to 0.54 h.p. per 100 r.p.m.

For any problem in precision rubber engineering
CONSULT DUNLOP AT BLUE-PRINT STAGE

Dunlop Rubber Co. Ltd. (Engineering Components Division), Fort Dunlop, Erdington, Birmingham 24

882/103

When answering advertisements kindly mention MACHINERY.


THE NEW SCRIVENER

No. 3

Centreless Grinding Machine

For continuous high production of precision ground parts the Scrivener feature of controlled cycle plunge grinding offers special economy unattainable by any other grinding method.

This example illustrates typical production.



Stub Axle. Plunge grinding two dia. ($\pm 0.0002''$) and two tapers (to gauge) magazine feed.

Total time. 30 seconds. 120 pieces per hour. Stock removed $0.012''$ to $0.015''$ in two passes.

The largest machine in the Scrivener range, this new Centreless Grinding Machine was introduced at the International Machine Tool Exhibition, and received wide approbation.

Employing the Scrivener system of controlled cycle operation, it demonstrated the plunge grinding of a stub axle in a total cycle time of 30 seconds (for two operations).

Scrivener machines incorporate, in addition to features for straight-through or hand-operated plunge grinding, a system for semi- or fully-automatic controlled cycle operation. By adopting the latter method, very economical mass production rates can be achieved, the machines feed, grind and eject in sequence and can be incorporated into automatic production lines.

The complete range comprises:

Model	No. 1D	No. 2	No. 3
Grinding wheel dia. and width	12" x 3"	20" x 6"	20" x 10"
Control wheel dia. and width	7" x 3"	12" x 6"	14" x 10"
Max. opening between rear wheels	2½" x 2"	6" x 4½"	9" x 9"

*Machines with controlled cycle operation.

WICKMAN LIMITED

FACTORED MACHINE DIVISION, FLETCHAMSTEAD HIGHWAY, COVENTRY


Telephone: Coventry 74321

449F20

When answering advertisements kindly mention MACHINERY.

AUTOMATION FOR YOUR BATCH PRODUCTION ARBOMAT

AUTOMATIC TURRET DRILLING MACHINE



*Prompt
delivery*

The ARBOMAT is a fully automatic turret machine, with 2 to 6 stations of $\frac{1}{2}$ in. capacity, or 2 to 4 stations with 1 in. capacity, in steel. It drills, reams, counter-sinks, taps or screws at different tool speeds, pre-selected for each station, in an automatic cycle.

It is a matter of minutes only to change the individual speed, rapid traverse and feed stroke for any station, or to vary the rate of feed or the number of stations, for another job. The ARBOMAT is, therefore, as economical for medium or even short runs as for continuous production.


THOKA

THOKA MACHINERY SUPPLIES LTD.
2 DRAPERS GARDENS • LONDON • E.C.2

Phone: NAtional 7391.

Cables: THOKANE, London.

When answering advertisements kindly mention MACHINERY.



15 minutes—and the die is cast!

In quarter of an hour this heading die was shaped from hardened high-speed steel. Besides being speedy and accurate, the method was simple; electro-erosion by GKN SPARK MACHINE. GKN electro-erosion greatly speeds and simplifies the cutting of complex shapes. It eliminates the difficulties involved with hard-to-handle materials such as hardened steels and tungsten carbide. GKN Spark Machining gives a high cutting rate

with low electrode wear and a good surface finish for dies, moulds, press tools and form tools in designs of an intricate nature. It is extremely simple and safe in operation. Accuracy? In general, a tolerance of .002" can easily be held and if required this can be reduced to .001" or even .0005". If you would like to know more about GKN Spark Machining, please get in touch with Welsh Metal Industries or Sale Agents.

GKN spark machine

DESIGNED BY THE GKN RESEARCH LABORATORY

Manufactured by

WELSH METAL INDUSTRIES LTD. Caerphilly, Glamorganshire.

Sales Agents

M. C. Layton Limited, 96-98 Victoria Street, London, S.W.1.
Rudkin & Riley Limited, Cyprus Road, Aylestone, Leicester.



When answering advertisements kindly mention MACHINERY.

*Something
New!* **CEJ**
"HI-TEN"
TAPS

**HAVE YOU ANY REALLY TOUGH
TAPPING PROBLEMS
IN HIGH TENSILE STEELS?**

A NEW MANUFACTURING PROCESS IS GIVING
AMAZING RESULTS AND MUCH LONGER TAP LIFE
ON THESE DIFFICULT MATERIALS

CEJ JOHANSSON LTD. *★ Tell CEJ about your problems and they will find the answer*
SOUTHFIELDS ROAD, DUNSTABLE, BEDS.

DBH/7097

When answering advertisements kindly mention MACHINERY.



* Figure supplied by Gt. Raymond Paper Co. of Lac Brûlé, Canada.

ACTUAL COSTS FOR

2606½ HOURS RUNNING WERE:

Diesel fuel (less tax : 1178 gals.).....\$259.27
 Lubricating oil, filters etc.....\$81.71
 Spare parts (fuel filter assembly).....\$20.35
 Fuel consumption (Gals/Hour).....0.441

YEARS OF KNOW-HOW: The diesel engines are manufactured with the same precision as Armstrong Siddeley's world-famous aero engines.

MATERIAL - CHECKED: Armstrong Siddeley experts regularly visit suppliers of materials and components to check on their quality controls.

PRODUCTION - CHECKED: As well as the standard bench test, which every engine undergoes, far more extensive tests are regularly made on engines taken at random from the production lines and all ASM diesels are approved by Lloyds and the Dutch Bureau Veritas.


THERE IS NO MORE RELIABLE DIESEL ENGINE.

Three models: 6-11 h.p., 14-22 h.p., 20-33 h.p.

Write now for brochures.

What does it cost to drive
 a 10 kW Generator from a
 14/22 h.p. Armstrong Siddeley
 Air Cooled Diesel?

\$0.01385 (1.175d.) per kW/hour*



ARMSTRONG SIDDELEY Air Cooled Diesels



ARMSTRONG SIDDELEY — COVENTRY AND BROCKWORTH, ENGLAND

A MEMBER OF HAWKER SIDDELEY | ONE OF THE WORLD'S INDUSTRIAL LEADERS

When answering advertisements kindly mention MACHINERY.


The logical advance in

Retaining



OLD WAY

Threaded studs were spot welded (or inserted if die-cast) to the nameplate. To hold this in position, washers and nuts were laboriously assembled with great difficulty especially on blind applications.



THE SALTER WAY

Studs are cast in with the nameplate, and the Fixes are simply pushed on, even on blind applications. The whole is firmly retained with an even spring tension.

save material — reduce assembly time — cut costs

When it's a question of assembling components in any engineering field, Salter Retainers are the answer. They replace nuts and bolts, screws, cotter pins, and eliminate expensive threading

and machining operations. A large standard range is at your immediate disposal, and we should welcome the opportunity to assist in developing special retainers to solve your problems.

Send for the Salter Retainer catalogue — no designer is complete without it.

NEATER — MORE POSITIVE — PERMANENT RETAINING

SALTER

TRADE MARK



Circlips



Fasteners



Retainers




Fixes

Geo. Salter & Co. Ltd., West Bromwich · Spring Specialists since 1760

84-10-444

When answering advertisements kindly mention MACHINERY.




A Multi Station Transfer Machine producing Rear Axle Castings for the Massey-Ferguson 35 Tractor at a production time of one pair (R.H. & L.H.) Casings per 100 seconds, in the Banner Lane Factory of The Standard Motor Co. Ltd.

... demand
the latest techniques
in steel making
for machine and
tool alike

**FIRTH
BROWN**

ALLOY STEELMAKERS • FORGEMASTERS • STEEL FOUNDERS • HEAVY ENGINEERS
THOS FIRTH & JOHN BROWN LIMITED • SHEFFIELD • ENGLAND

When answering advertisements kindly mention MACHINERY.





HBM

AUTOMATIC SIZING

INTERNAL GRINDING MACHINE

CHURCHILL Automatic Sizing Internal Grinding Machines are renowned for their accuracy and speed of production. The extensive experience gained from supplying very many machines has been fully utilised in the Model 'HBM' to ensure highly efficient operation over a wide range of work.



THE CHURCHILL MACHINE TOOL CO. LTD., BROADHEATH, nr. MANCHESTER
Telephone: Altrincham 3262

Telegrams: Churchale, Manchester

Export Sales Organisation: Associated British Machine Tool Makers Ltd,
London Branches and Agents.

Home Selling Agents: Charles Churchill & Co. Ltd., Birmingham and
Branches.

Single or double automatic cycle operation according to work.

Plunge cut and traverse grinding.

Feed accelerator reduces production time.

Exceptionally wide range of roughing and finishing feeds.

Diminishing rate of feed to zero with variable electric dwell at size position.

Adjustable oscillation for building-up finish on blind end and open short length bores.

Hand feed to dead stop for plain internal grinding.


Operational safety—provision for immediate interruption of automatic cycle for emergency run-out—enclosing of dogs and plungers eliminates "finger traps".

Can be equipped for combined hole and face grinding.

PRECISION *plus* PRODUCTION

When answering advertisements kindly mention MACHINERY.

C661



It takes only seconds to set-up Dedlock Cutters with perfect accuracy and rigidity, giving complete visibility of the work and eliminating overarm arbor supports. Moreover, Dedlock Cutters are made of the finest high speed steel, with teeth perfectly designed for long life. The amazing range of 2" to 6" diameters eliminates the need for costly and out-dated Shell End Mills, Face Mills, Large Taper Shank End Mills, and Cylindrical Cutters. The Dedlock principle "the heavier the cut, the tighter the grip" allows hitherto impossible working feeds and speeds. *Delivery by return from Clarkson depots—at maker's prices*

Cut with

Clarkson

NEWCASTLE	241 Westgate Road, 1	NEWCASTLE 2-5248
BIRMINGHAM	15 Heath Mill Lane, 9	Victoria 3994
LONDON	124 Hammersmith Road, W.6	Riverside 8241
MANCHESTER	98 Oxford Road, 13	ARDwick 4804
BRISTOL	17 Cumberland Street, 2	Bristol 2-8464
BELFAST	32 Shaftesbury Square	Belfast 20025
GLASGOW	430 Crown Street, C.5	SOUTH 1942
LEEDS	Room 8a, Britannia House, 1	Leeds 26369

CLARKSON (ENGINEERS) LTD. Head Office: Nuneaton. Phone: Nuneaton 2261

When answering advertisements kindly mention MACHINERY.

★ **CONSISTENCY . . . FIRST TO LAST!**



DORMER

We insist on the latest methods of heat treatment, developed and proved by our own technicians.

In order to achieve the maximum cutting strength and durability of **DORMER TOOLS**, the most thorough scientific control is maintained.

Consistently high performances result.

**THE
SHEFFIELD TWIST DRILL
& STEEL COMPANY LIMITED
SHEFFIELD • ENGLAND**

**DORMER TOOLS ARE OBTAINABLE
FROM YOUR USUAL ENGINEERS'
MERCHANTS**

October 22, 1958

MACHINERY

NO. 75 91

Let us
"HANDLE"
your machines



The above display is a small selection from our range of 104 shapes and sizes of standard handles and 10 sizes of handwheels in both dished and flat type.

Why add to your costs by making special form tools? This is our job! Makers of machine tools and machinery of all descriptions appreciate our specialised service in **BALL HANDLES AND HANDWHEELS**. Handles with moulded knobs too! They not only save time but also reduce production costs.

WM. WHITELEY & SONS, LTD. *incorporating* **J. CHARLESWORTH**
(MACHINE TOOL DIVISION) PROSPECT IRONWORKS, LOCKWOOD, HUDDERSFIELD, YORKS.


Telegrams: Drying, Huddersfield

Telephone: Huddersfield 4410/11

makers of Machine Components since 1854

**TAYLOR-
HOBSON**


Micro Alignment Telescope



Set and check alignment, parallelism, squareness and generate plane surfaces of Diesel Engines, Turbines and Generators, Machine Tools, Aircraft Jigs, Nuclear Reactors by Optical Tooling.




A Division of
RANK PRECISION INDUSTRIES LTD.



TAYLOR TAYLOR & HOBSON LTD. LEICESTER ENGLAND

AT/18

When answering advertisements kindly mention MACHINERY.



THE LINDNER WORM AND THREAD GRINDING MACHINE


Distance between centres .. 32in.
Maximum grinding length .. 20in.
Maximum grinding diameter .. 10in.
Maximum helix angle right and left 40°
External and internal grinding with
single and multi-profile wheels.
Automatic in-feed grinding.

Other models of thread grinders available for continuous thread up to 13ft.

LINDNER

THE LINDNER JIG BORER

- Optical adjustment
- Measuring system free from wear
- Pre-selection of adjustments
- Projection optics
- Open-front design
- Automatic locking and releasing of the co-ordinate table and boring head
- Centralized lubrication
- Setting accuracy 0.0004in.
- Spindle Speeds 25—1900 infinitely variable.



SOLE AGENTS FOR GT. BRITAIN:

STEDALL MACHINE TOOL CO.

145-157 ST. JOHN STREET,
CLERKENWELL, LONDON, E.C.1

Telephone: Clerkenwell 1010 Telegrams: Lockstone-Smith, London

When answering advertisements kindly mention MACHINERY.

announcing**the new****DIAL TYPE****AGENTS**

Chas. Churchill & Co. Ltd.
London, Birmingham, Manchester
Gateshead, Glasgow.

range of Model "LL" MILLING MACHINES

with **ARBOR-LOC**

MORE TABLE TRAVEL 34" TO 60"

**GREATER SPINDLE POWER WITH 15 TO 40 H.P.
AND INDEPENDENT FEED DRIVE MOTOR**

**INCREASED VERSATILITY WITH PUSH BUTTON SPINDLE CONTROL
AUTOMATIC BACKLASH ELIMINATION AND AUTOMATIC TABLE-CYCLES**

EVEN GREATER ROBUSTNESS WITH SQUARE GIBBED COLUMN WAYS

Plus

THE NEW QUICK-CHANGE CUTTER FEATURE ARBOR-LOC

CINCINNATI


IN THE FOREFRONT OF MACHINE TOOL DESIGN

Send NOW for Catalogue No. M1915E

CINCINNATI MILLING MACHINES LIMITED, BIRMINGHAM 24

Now the A15—

joins the *Austinlite* rotary switches




This new switch is identical in principle to the well established A50 and A30 rotary switches. It has the same rolling, self-cleaning contacts with extended horns to keep any arcing away from the contact faces—a feature exclusive to Austinlite rotary switches. It has a similarly powerful and positive switch mechanism, and can be built in the same variety of forms to switch in sequence or simultaneously very large numbers of circuits.

It is extremely compact, the smallest of the Austinlite multi-cell rotary switches.

It bridges the gap between the A30 and the little single-cell 10-amp switch.

Delivery, on standard applications, can now be made in four weeks.

Our brochure "*SIMPLIFIED SWITCHING*" will tell you more about the advantages of Austinlite Rotary Switches. May we send you a copy?



The four Austinlite Rotary Switches—A50, A30, A15 and A10

Austinlite

ROTARY SWITCHES

tailor-made by


STONE-CHANCE LTD.

(Makers of Sumo Pumps and Stone-Chance lighthouses). Crawley, Sussex

When answering advertisements kindly mention MACHINERY.

USE THE 'SLUG' TECHNIQUE

**—and cut
the cost
of chucking work**



Photograph shows various size steel blanks cut in six hours. One operator can work more than one machine, once setting-up and loading are completed. The cycle is automatic and even the swarf is collected in a bin.

NOBLE & LUND

fluifeed

AUTOMATIC COLD SAW

MODEL AL/CC

28in. Size with chip conveyor — parts slugs from bars in a fraction of the normal lathe or automatic time

Close control of production times has proved without doubt that the use of pre-cut slugs on single spindle bar automatic and turret lathes can show savings of from 30 to 75 per cent.

The new FLUIFEED automatic cold saw has been specially developed to give production shops the full advantage of the 'slugging' technique, and really revolutionary production

times are being recorded. We will gladly co-operate with you on your own work. Get in touch with us without delay.

FOUR SIZES OF THE 'FLUIFEED' AUTOMATIC

- 22in. ADMITS UP TO 7½in. DIAMETER.
- 28in. ADMITS UP TO 10in. DIAMETER.
- 38in. ADMITS UP TO 14in. DIAMETER.
- 48in. ADMITS UP TO 17in. DIAMETER.


NOBLE & LUND

NORTHERN MACHINE TOOL WORKS

FELLING-ON-TYNE

TELEPHONE: FELLING 82272
TELEGRAMS: LATHES GATESHEAD

When answering advertisements kindly mention MACHINERY.



**HYDRAULICALLY
OPERATED**


**RAPID POWER
ELEVATION OF KNEE**

**HIGH PRODUCTION
WITH VERSATILITY**

**SENSITIVE CONTROLS
WITH RUN OUT TO
LOADING POSITION**

**ACCURACY TO .0001
WITH PERFECT FLATNESS
AND FINISHES TO
1.5 MICRO INCHES
ON SUITABLE MATERIAL**

TABLE WORKING SURFACES



This latest development model SG3H is "the" Machine for rapid Surfacing in the Toolroom or Production Shop. Detachable Spindles are available for deep and intricate work.

Hydraulic Control allows the operator to "inch" the Table along or stop instantaneously in any position at will.

Auto Run-out of Table to loading position.

Built in Coolant system with separation unit in Base.

Uses 4" Diameter Cylinder Wheels for faster Surfacing and Maximum wheel economy.

ABWOOD LTD., PRINCES ROAD, DARTFORD, KENT

Telegrams: ABWOOD DARTFORD

Machinery 98
Oct. 22, 1958

SG-1



THE TOOLS YOU NEED

Quick-change Drill Chuck

Tools can be quickly inserted and removed without stopping the spindle, thus enabling a single spindle drilling machine to do work which would otherwise have to be performed on a multi-column machine. Range of chucks available to suit machines having 2, 3, 4 and 5 morse taper spindles.

Saftork Tapper

For use on drilling machines having a reverse to the spindle. The drive is transmitted by a multi-disc friction clutch, adjusted to slip under any predetermined cutting load. Tap breakage is therefore largely avoided. Available in two sizes— $\frac{3}{4}$ in. and 1 $\frac{1}{4}$ in. capacity.

Combined Drill Chuck/Tapper

Combines the essential features of the Quick-change Drill Chuck and Saftork Tapper. Ranges of collets are available for all taps and taper shank drills within the respective capacities.

AD.424

When answering advertisements kindly mention MACHINERY.



ROUND NOSE PLANING TOOLS

FLAT FINISHING PLANING TOOLS

SIDE ROUGHING TOOLS

HEAVY DUTY CLAMPTIP PLANING TOOLS

on the Veraloy principle perform
better and cost less to buy and to regrind.
Write for particulars to:

VERALOY VERALOY PRODUCTS LTD.

BEECH ROAD · THE MARSH · HIGH WYCOMBE · BUCKINGHAM
Telephone: High Wycombe 2795-8. Telegrams: Veraloy High Wycombe


When answering advertisements kindly mention MACHINERY.

9 Applications of the

Crawford

"TRUGRIP" COLLET CHUCK


With the Crawford "Trugrip" Collet Chuck, work is held true, instantly, by the turn of a key. Absence of drawtube or sleeve means that full bore of spindle can be used. Powerful, positive action, with no distortion, and no marking of previously machined surfaces, makes it ideal for second operation work. Wide range of collets greatly increases capacity of machine, nine typical examples shown below.




Sizes: 5in. dia., 1in. capacity;
2in. dia., 2in. capacity




Turning using Standard Collet.




Facing and turning using Ring Collet.




Facing and boring using Disc Collet.




Boring an irregular shaped Component




Grinding using Standard Collet.




Internal grinding using Oversize Head Collet.



Grinding O.D. and face dead true with bore using Expanded Mandrel.



Milling on Index Fixture.



Milling on Expanded Mandrel.

CRAWFORD COLLETS LTD

HEAD OFFICE: TOWER HILL WORKS · WITNEY · OXON · Tel. No. WITNEY 334

London Stockists: ACBARS LTD., 16-18 Macleod St., Walworth Rd., London, S.E.17. RODNEY 7191

Midland Stockists: RETSELP ENGINEERING LTD., Vulcan Rd., Industrial Site, Lode Lane, Solihull, Birmingham. SOLIHULL 2239

Agents for South West England and Wales
MESSRS: W.O. BULLOCK & SONS LTD., 126 RODBOURNE ROAD, SWINDON, WILTS. TEL: SWINDON 6331

Agents for Scotland
R. MCKIMMING & CO., 65 WEST REGENT STREET, GLASGOW, C.2. TEL. DOUGLAS 7391/2

WICKMAN S-LASH

EXPANSION REAMER PRICES

The benefit of our lower production cost is yours.

The considerable demand for Wimet Expansion Reamers has resulted in the introduction of new manufacturing methods. These have led to lower costs which are now being passed to you in the form of lower prices.

Wimet tipped tools already possess a life many times greater than ordinary tools and in the Expansion Reamer this is multiplied many times over by the ability to expand it and regrind to size.

Delivery of all commonly used sizes can be made from stock. Please write or 'phone your enquiries.

Wimet

EXPANSION REAMERS



PRICES

SIZE	Finished Reamers	* Blanks for sizing
	B.S.I. Limits	Grinding Allowance on Nominal
1"	64/3	47/9
1 1/8"	76/-	58/-
1 1/4"	84/-	64/6
1 1/2"	89/3	68/3

Finished Reamers
+ 0.0005" / 0.001" + 0.0005" / 0.0008"

Prices for intermediate sizes available on request.

* Blanks for sizing are finished in all respects but left with grinding allowance for circular grinding and backing-off by customer.

WICKMAN LIMITED

WIMET DIVISION, TORRINGTON AVENUE, COVENTRY

Telephone: Tole Hill 64621

518 ST

When answering advertisements kindly mention MACHINERY.

MACHINERY is registered as a newspaper at the General Post Office and the name is a registered trade mark

Published every Wednesday by
The Machinery Publishing Co., Ltd.

© The Machinery Publishing Company, Limited, 1958. All rights of reproduction and translation reserved by the publishers by virtue of the Universal Copyright and International Copyright (Brussels and Berne) Conventions and throughout the World
Price 1/3

LESLIE R. MASON
Managing Director
CHARLES H. BURDER
Editor

LONDON OFFICE

REGISTERED OFFICE, EDITORIAL, SMALL AND CLASSIFIED
ADVERTISEMENTS DEPARTMENT AND ENQUIRY BUREAU

CLIFTON HOUSE
83-117 EUSTON ROAD
LONDON, N.W.1.
Telephone: Euston 8441/2
Telegrams: Machtool, Norwest, London

HEAD OFFICE

SUBSCRIPTION, ADVERTISEMENT, SERVICE,
PHOTOGRAPHIC, ACCOUNTS AND BOOK DEPARTMENTS

NATIONAL HOUSE
21 WEST STREET
BRIGHTON, I.

Telephone:
Brighton 27356
(4 lines)



Telegrams:
Machtool,
Brighton

NEW YORK:
93, Worth Street

PARIS:
15, Rue Bleue

SUBSCRIPTIONS:—Inland and overseas, 52 shillings per annum, post free. Cheques and Money Orders should be made payable to the Machinery Publishing Co., Ltd.

ADVERTISEMENTS:—Copy for displayed advertisements, if proofs are required, should reach the Brighton office 21 days in advance of publication. Rates on request. Small (classified) advertisements can be accepted, space permitting, at the London office up to Wednesday, for publication on the following Wednesday. For rates, see p. 147

Blocks are held at advertisers' own risk; no responsibility for loss is accepted by the publishers.

MANUSCRIPTS FOR BOOKS covering all branches of engineering production will receive careful consideration and should be sent to the Manager, Book Dept., MACHINERY, National House, 21 West St., Brighton, I.

MACHINERY

A JOURNAL OF METAL-WORKING PRACTICE
AND MACHINE TOOLS

Vol. 93, No. 2397

October 22, 1958

COPIES PRINTED.....11,500 per week

CERTIFIED DISTRIBUTION.....11,376 per week

CERTIFIED PAID DISTRIBUTION10,566 per week

CONTENTS

Editorial	PAGE
Ultrasonic Welding	919
Principal Articles (For Abstracts see next page)	
The Production of Ford Commercial Vehicles.....	920
Typical Operations on Components for the Convair 880 Jet-propelled Air-liner	934
Lost Wax Investment Casting.....	941
New B.M.C. Body Painting Plant.....	950
Open Days at the A.I.D. Laboratories.....	963
Short Articles	
Frigolux Cold-light Illuminated Magnifier.....	940
"Rapid" Deep-field Circular Lifting Magnet.....	948
Andantex Speed Reduction Pulleys.....	949
Churchill Gear Machines Linked Line for Cluster Gears....	966
Grinding Machine Demonstration.....	967
New Production Equipment	
Craven 30-ft. Vertical Boring and Turning Mill.....	955
Birfield-Somua Type Z1B Milling Machine.....	956
Asquith Horizontal-spindle Milling Machine for Facing the Ends of Girders.....	958
New Small Wheel Attachment for the Wickman Optical Profile Grinder	958
Seneca Falls Precision Boring Machine.....	959
Genelin Plate Bending Rolls.....	960
Burgmaster Turret Drilling Machine with Automatic Indexing Version 1,000-ton Press Brake.....	960
Crowthorn Heavy-duty Lathe for Facing Crankcases.....	961
Rotaform Grinding Fixture.....	962
Bronx 5-roll Levelling Machine.....	962
News of the Industry	
Glasgow and District	969
Classified Advertisements.....	147
Index to Advertisers.....	177

CONDITIONS OF SALE AND SUPPLY.—MACHINERY is sold subject to the following conditions:

That it shall not, without the written consent of the publishers first given, be lent, resold, hired out or otherwise disposed of by way of trade except at the full retail price of 1s. 3d. and, that it shall not be lent, resold, hired out or otherwise disposed of in a mutilated condition or in any unauthorized cover by way of trade; or affixed to or as part of any publication or advertising literary or pictorial matter whatsoever

Abstracts of Principal Articles

The Production of Ford Commercial Vehicles P. 920

For the Ford Thames Trader range of commercial vehicles, which includes units with carrying capacities up to 7 tons, a standardized rear axle design is employed, which is manufactured by efficient, quantity-production methods. For operations on the rear axle carrier casting, which provides bearings for the driving pinion and differential, only two machines are installed. On the first—a Ryder 6-spindle Verticalauto—rough turning and facing operations are performed and holes are drilled in the flange. The castings are then loaded into pallets on a 21-station Alfing in-line transfer machine, on which the driving pinion bores and faces are rough- and semi-finish machined and fine-bored, the bearing cap holding-down bolt holes are drilled and tapped, and the bearing caps are fitted manually, before rough-semi-finish- and finish-boring and threading are carried out. Features of interest on this machine include an arrangement for the return of the pallets on an overhead track, provision for turning the pallets so that operations on bores at 90 deg. to each other can be completed, and a shaping head which cuts V-shaped grooves to form chamfers at the edges of the bearing cap joint faces. The castings are unloaded and inspected at a gauging station equipped with a large receiver gauge for checking the relative positions of the bores, and pneumatic units for measuring diameters and ovality. (MACHINERY, 93—22/10/58.)

Typical Operations on Components for the Convair 880 Jet-propelled Air-liner P. 934

It is stated that the Convair Division of General Dynamics Corporation, U.S.A., has spent 22 million dollars in preparation for building the 880 jet-propelled air-liner, and, of this total, machine tools and associated equipment have accounted for nearly 4 million dollars. Some typical machines and operations are here discussed and it may be noted that advantage has been taken, where possible, of the facilities afforded by numerical control. An Onsrud spar mill, which is 105 ft. long, is available for operations on components up to 60 ft. long by 3 ft. wide and is arranged for both vertical and tilting movements of the cutter heads which are controlled by templates. Integrally stiffened skin panels are produced on a Giddings & Lewis skin mill with vertical and horizontal heads, on which all movements are controlled by the numericord system. There is also a Variax machine with a similar system arranged for controlling the cutter head about three axes. Other machines illustrated and briefly described include a Sundstrand profiler with a True-Trace hydraulic copying head; an Ekstrom-Carlson router; an Arrow profiler; and a Cyril Bath radial draw-former of 75 tons capacity. (MACHINERY, 93—22/10/58.)

Lost Wax Investment Casting P. 941

Certain developments and improvements have recently been made in connection with the Trucast method of lost wax investment casting. By using a "dual-gravity" refractory material, it has been possible to improve the strength of the mould, and the weight of metal which can be poured at one time has been increased to 30 lb. A new pre-coating material has been developed for the wax trees, to eliminate the type of surface defect known as "fusion," or "slag spots," which frequently occurs when casting chromium alloys of the martensitic type. The latest standard wax injection machine which has been designed and built allows wax models to be produced at the average rate of 4 per min. from a single impression die. Mention is made of the radio-frequency furnace which is employed exclusively for the Trucast process, and details are given of a number of instances where investment castings have been used in place of a part, or parts, which, hitherto, had been machined from the solid. Finally, a method of producing wax injection dies for turbine blades from strickled plaster moulds is discussed. (MACHINERY, 93—22/10/58.)

New B.M.C. Body Painting Plant... P. 950

The extensive programme of expansion that is being carried out by the British Motor Corporation includes a completely new body painting plant at the Cowley works of Morris Motors, Ltd., which has recently been brought into operation, and is stated to be one of the most efficiently-planned units of its kind. Two conveyORIZED paint lines are installed, each of which is capable of handling 26 bodies per hour. There is also a new Rotodip plant which augments existing facilities for applying the anti-rust treatment before the bodies pass to the paint lines. Features of the latter include fully-automatic spray booths, overhead stoving ovens to conserve space, and facilities for rapidly changing over to any one of 26 different paint colours in the finishing booths. (MACHINERY, 93—22/10/58.)

Contributions to MACHINERY

If you know of a more efficient way of designing a tool, gauge, fixture, or mechanism, machining or forming a metal component, heat treating, plating or enamelling, handling parts or material, building up an assembly, utilizing supplies, or laying out or organizing a department or a factory, send it to the Editor. Short comments upon published articles and letters on subjects concerning the metal-working industries are particularly welcome. Payment will be made for exclusive contributions.

IN FORTHCOMING ISSUES

Machining blades for gas turbine units—Safety arrangements for pressure die casting.

Ultrasonic Welding

The production engineer is called upon to provide strong, durable, permanent joints between the component metal or alloy parts of innumerable assemblies. These components differ very widely in characteristics, composition, and thickness, for example, and service requirements may be equally diverse and tend to become increasingly exacting. To enable the many problems that arise in this connection to be satisfactorily solved, a great deal of research work has been carried out in recent years, and there have been very important developments in such well-established processes as riveting; gas, resistance and arc welding; and brazing. As a result, the scope of these processes has been progressively extended, and the quality of joints obtainable has been improved. At the same time, other joining methods have been introduced and are proving very effective for certain applications. Among these newer methods, so far as the metal working industries are concerned, may be mentioned adhesive bonding, metal stitching, and cold pressure and ultrasonic welding.

As was explained in an article published recently in *MACHINERY*, aluminium, copper and most of their alloys, also high-purity lead, zinc, nickel, silver, palladium, platinum, and gold, can be pressure welded in the cold state. It is interesting to note, moreover, that a joint may be obtained by this method between two pieces of the same metal, or between pieces of any two different metals, of those listed. Sheet or foil may be joined by lap welding, and strip, wire or rod by butt welding. It is also possible to seal "cans" by cold ring or extrusion welding. In lap welding, some restrictions are imposed by the fact that the finished thickness at the point of welding is drastically reduced, and for this reason, a wavy weld line may be preferable to a straight line.

Ultrasonic welding, to which brief reference has previously been made in *MACHINERY*, is the latest of the processes mentioned, but according to information presented by Mr. J. Byron Jones and Mr. W. C. Potthoff during the course of a paper read recently before the American Society of Tool Engineers, there have already been rapid advances in this field. With the ultrasonic process, it may be recalled, the components to be joined are held in contact under comparatively light pressure, and are subjected to high frequency vibration, which causes the surfaces to weld together. As an indica-

tion of the progress that has been made, it is stated that in 1955 Alclad aluminium alloy sheet could not be welded ultrasonically. In 1956 it proved possible to spot weld 0.040-in. thick sheet, but the strength of the welds barely met specification requirements. By 1957, spot welds were being produced in 0.063-in. sheet with a strength considerably in excess of that specified, and early this year, the thickness which can be successfully welded was raised to 0.090 in.

These results, which have enabled the range of application of the process to be greatly extended, have been achieved by introducing improved transducer-coupling systems to enable more energy to be delivered to the weld zones, and by providing equipment for spot welding operations with capacities up to 8 kW. It has been found that ultrasonic welding can be performed over a broad frequency band, but attention has been directed to the development of equipment for operating in the range from 3,000 to 85,000 cycles per sec. The transducers employed incorporate stacks of thin-gauge nickel sheet, and it is pointed out that the coupling system employed must be force-insensitive. In other words, there must be no significant shift in the resonant frequency of the system when pressure is applied to the work.

Joints may be formed by single spots or by overlapping spots, the latter being obtained without difficulty since no electric current flows through the joints. It has been found that welds can be located close to the edge of the material without loss of spot strength, and it is therefore possible to reduce the amount of overlap. More recently, roller type ultrasonic welders have been introduced for producing continuous seams. With this method, the work may be passed between rotating rollers, one or both of which may form part of a transducer coupling system, or it may be supported on a table and traversed beneath a single roller.

It may be of interest to mention a few recent applications of ultrasonic welding as an indication of some of the problems that have been solved in this way. In one instance, a platinum-alloy resistance wire of 0.0015 in. diameter is welded across two copper lead wires, and sound mechanical joints, with consistent electrical resistance, are obtained. Another delicate operation involved the welding of two thicknesses of etched stainless steel

(Continued on page 970)



The Production of Ford Commercial Vehicles

Transfer Machining of Rear Axle Carriers for the Thames Trader Range

The recently-introduced range of Ford Thames Trader commercial vehicles includes types with rated carrying capacities of 1½, 2, 3, 4, 5, and 7 tons, and they can be supplied with a variety of bodies, including normal lorry and other designs, one of the latter being seen in the heading illustration. Several chassis lengths are offered, so that the most suitable wheel-base can be selected when special bodies are to be built for the carriage of particular kinds of goods. Power is provided by 4-cylinder engines for sizes up to 5 tons capacity, alternative petrol and Ford-built diesel units being available. Larger-capacity vehicles are powered by 6-cylinder engines, also in petrol and diesel types, and the ranges of engines have many components in common so that they may be produced by efficient methods.

Features of the engines include 5- and 7-bearing crank- and cam-shafts, and wet-liners which permit the use of long-wearing material for the cylinder walls, and are easily replaced, when necessary, instead of being re-bored. Radiator thermostats are fitted to ensure that the engines operate at optimum temperatures, and corrugated steel cylinder head gaskets are fitted. The diesel engines are designed for easy starting and low fuel consumption, and it is claimed that the four-hole injector nozzles employed ensure efficient combustion. With the 6-cylinder engine, 100 h.p. is generated at 2,500 r.p.m., and the maximum torque of 242 lb.-ft. is obtained at 1,500 r.p.m. The petrol

engines are of modern design, with wedge-shaped combustion chambers and overhead valves inclined at an angle of 13 deg. to the vertical, and the 6-cylinder unit develops 110 h.p. at a speed of 2,800 r.p.m.

Each vehicle in the range is fitted with a 4-forward speed, synchromesh gearbox, which has provision for power take-off, and the gearbox is so installed that it can be removed without disturbing the engine. The drive is transmitted through hypoid bevel gearing in the rear axle, and the bevel gear and pinion, together with the differential, are housed in a one-piece carrier of cast iron. The carrier, the machining of which forms the subject of this article, is housed in a banjo-shaped axle casing, and can be removed as a whole when servicing is required. Certain vehicles can be supplied with the Eaton 2-speed axle, and this unit is accommodated in the standard banjo housing, so that the minimum of extra cost is incurred. Other features of the range include servo-assisted hydraulic brakes and worm and roller steering.

The rear axle carrier casting, which is of grey iron, is shown in section and elevation in Fig. 1, and it will be seen that there is a main bore A, which accommodates the bearing for the outer end of the driving pinion shaft, and a smaller bore B, in a boss supported by projections and webs on the casting, for the inner end. At 90 deg. to the common axis of these bores, there are two other bores, formed half in the carrier casting and half

in two bearing caps attached to it by means of hexagon-headed bolts, the casting portion of one bore being indicated at C. These two bores provide housings for the bearings of the differential carrier, and in addition to being accurately machined, must be threaded at their outer ends.

OPERATIONS ON RYDER VERTICALAUTO

The preliminary operations on the casting are performed on a Ryder No. 10, 6-spindle, Verticalauto, and a view of this machine is given in Fig. 2. Driven by a main motor of 60 h.p., this machine is employed for several turning and facing operations, notably on the casting flange, and for drilling a total of 14 holes in the flange, of which two, indicated at D, Fig. 1, serve for location purposes throughout the remainder of the machining sequence. Rough castings, which weigh about 65 lb., are supplied in clean condition and painted to prevent rusting during storage, and they are loaded at the centre position in Fig. 2. Here, each casting is placed, by means of a hoist, with the outer face of the flange (in the final assembly) facing downwards and resting on three equally-spaced tapered pins, as at E, on which it is supported at the correct height in relation to the cutting tools.

Angular location of the casting, for the final drilling operation, is taken from two cast bosses F,

Fig. 1, on the underside, which are engaged by a sliding latch carried on the top surface of the steel block G, Fig. 2. This latch is spring-loaded towards the casting, and has a wedge-shaped end which enters the space between the bosses. Near the centre of the chuck there is a projecting stud with a nut, over which the pinion bore is passed when the casting is loaded, and a C-washer is fitted to this stud and the nut tightened, for initial clamping. Three hydraulically-operated jaws on the chuck are then tightened, to a controlled pressure, by moving the ball-ended handle H, on the machine base, and the automatic cycle is started by means of another lever J, above the operator's head.

The table indexes to the left at the beginning of the machine cycle, and the horizontal slide at the first machining station is equipped with two carbide-tipped tools, which provide for rough facing the flange and the upper ends of the pillars K, Fig. 1, to which the bearing caps are later attached. A vertical slide also carries two tools, which are fed down to rough turn the outside surfaces of the pillars and the main spigot diameter L, Fig. 1. At the second machining station, the tools are similarly disposed, and perform semi-finishing operations on the surfaces mentioned. Only one tool—on the vertical slide—is applied at the third station, to form a 0.04-in., 45-deg., chamfer at the edge of the spigot. At station




Fig. 1. The rear axle carrier casting for the Ford Thames Trader range of commercial vehicles is here shown in section and elevation




Fig. 2. For the first series of operations on the rear axle carrier casting, this set-up, on a Ryder 6-spindle Verticalauto, is employed, and provides for rough-turning and -facing, also drilling operations

four, there are two tools on the horizontal slide, which serve to finish the spigot diameter *L*, Fig. 1, to 13.494/13.499 in., also to finish face the flange and the ends of the bearing cap pillars *K*.

For all these operations, the tools are tipped with Wimet grade N tungsten carbide, and the cutting speeds range up to 250 ft. per min. Feed rates from 45 to 134 cuts per in. are employed, and the maximum depth of cut is approximately $\frac{1}{8}$ in. At the last station, which is seen at the right in Fig. 2, there is a column on the horizontal slide for a Mulhead 14-spindle drill head. This head is driven, at a speed of 387 r.p.m., by a vertical shaft, from the mechanism at the top of the central portion of the machine. At this station, the spindle is automatically turned, until a

raised automatically in readiness for indexing. These operations are completed in a floor-to-floor time of 3.9 min.

ALFING 21-STATION IN-LINE TRANSFER MACHINE

All the remaining operations on the rear axle carrier casting are performed on an Alfing (Associated Alfing Kessler, Ltd.), 21-station, in-line automatic transfer machine, a general view of which is given in Fig. 3. Of the platen type, this machine is more than 100 ft. long and has 14





Fig. 3. A general view of the Alfing 21-station in-line transfer machine employed for operations on the rear axle carrier. The cabinets opposite each head contain hydraulic pumps and control valves

Fig. 4. Close-up view of the loading station on the Alfing machine showing the platen in which the casting is supported with the main flange vertical. Clamping is performed semi-automatically by the head on the far side of the machine and the platens travel towards the right



working stations with a total of 87 spindles. The platens, which are square in plan, travel from the loading end of the machine, at the right in Fig. 3, towards the far end, and are turned through 90 deg. just after passing the half-way point, to enable the machining operations to be completed. At the far end of the machine, the platens are returned to their original position for unloading, and are moved on to a platform, whereon they are raised to the level of the overhead return track shown. A chain type conveyor then moves the platens back to the loading end, where they are lowered to the transfer track level, ready to pass through the machine again.

All the electrical switchgear is contained in a row of cabinets which are installed above the level of the machine, on a platform constructed from angle- and channel-section steel, where they are out of the way yet readily accessible. The movements of the machine heads, which are hydraulically powered, are controlled by mechanisms within the cabinets at each side, one cabinet serving one or more heads, depending on the complication of the operations performed. Hydraulic pressure for the movement of each head is supplied by a pump which is continuously driven by its own motor. The pump spindle extends beyond the pump housing to another pump, the drive being transmitted through an electro-magnetic clutch. Oil delivered by the constantly-driven pump serves for the slow feed motions of the head, and is passed through restrictor and directional control valves operated by knobs on the outside of the cabinet. When the rapid advance or withdrawal motion is required, the electro-magnetic clutch is engaged to drive the second pump, and the extra

oil thus supplied is passed to the feed cylinder to increase the speed of movement.

Since the distance between adjacent machining station is considerable, the platen bases measuring about 30 in. square, the transfer bar must make a fairly large movement, and it is operated by means of two long-stroke hydraulic cylinders, one at each end of the machine bed, which are supported on substantial outrigger brackets. The cylindrical bar is provided with ears at the positions adjacent to the machining stations, and is turned, by means of a transverse cylinder, to engage these ears with the platens in readiness for each transfer motion. Further reference to this cylinder, and the transfer motion, will be made later. Each platen rests on the surfaces of a location track at the machining and idle stations, but at the intermediate positions it travels on a separate transfer track.

The under-side of each platen is provided with a roller at each corner, which rests on the transfer track. At the machining and idle stations, the rollers enter gaps in the track, and the platen drops approximately 0.010 in. on to the location track. Wear of the location surfaces is thus minimized. At each station, the platen is located by two dowels of about 2½ in. diameter, with chamfered edges to facilitate entry, and is clamped at each corner, the dowels and the clamps being operated by two hydraulic cylinders at each position. Semi-automatic mechanisms are provided for clamping and unclamping the component





Fig. 5. In this lay-out of the stations on the Alfing machine, those which are idle, or are employed for fitting bearing caps, and for loading or unloading, have been omitted for clarity

at each end of the machine, and the equipment at the loading station is seen in Fig. 4, which is a view from the side opposite to that seen in Fig. 3.

Empty platens progress from the platform of the lowering unit at the left in Fig. 4, the housing of which can just be seen, along the transfer track to the loading station, designated No. 2. A casting from the Ryder machine is loaded by hand—although a hoist was originally provided—being placed initially on the central rib of the platen base and turned until the face *M* is in a vertical

position at the left. The casting is next raised until its flange face is almost vertical and the lower edge of the spigot is resting in a register hole in the vertical wall of the platen. In this position, the lower of two locating dowels can be engaged with the corresponding hole of the two marked *D* in Fig. 1, and the casting is then pressed forward to engage the other hole with its dowel and to carry the flange into contact with four pressure pads on the vertical face of the platen.

Holding the casting in place with one hand, the operator next turns the four clamping pads through about 90 deg., to overlap the flange and hold the casting in position while it is being clamped. Each clamping pad is attached to a bolt which extends through the fixture and has a special nut on the



opposite side, as may be seen in Fig. 12. The nut is of cylindrical form, and is cut away at the outer end to leave two projections whereby it can be engaged and turned by a spanner of similar shape. A unit head on the opposite side of the machine at this station is equipped with four spindles, each of which carries a spanner of this type, as at N (Fig. 4), and when the two widely-spaced buttons in the foreground are depressed, the head is advanced into the clamp-tightening position.

Each spindle is then driven, first to engage the spanners with the nuts, and then to tighten them, and the drive to each spindle is transmitted through a torque-limiting clutch so that only a pre-determined clamping pressure can be applied. As soon as the nuts have been tightened the spindles are stopped and the direction of the oil supply to the

traversing cylinder is automatically reversed. The head is then withdrawn, leaving the pallet ready for the next indexing motion of the machine. This motion is selected by the operator, as soon as the clamping sequence has been completed, by pressing a button on an adjacent panel, from which the entire machine can be controlled. Lights on this panel are illuminated to show the positions of all the heads on the machine, so that the tracing of any faults is facilitated and the completion of the operation cycle is indicated.

MACHINING OPERATIONS

The complete sequence of operations carried out on the Alfing machine includes rough- and semi-finishing the driving pinion bores and faces,




Fig. 6. Station No. 3, here seen from the left-hand side of the machine as viewed in the direction of platen-transfer, provides for milling the pinion boss and boring the small bore B, Fig. 1

machining chamfers on the bearing cap pillars, drilling, spot-facing where necessary, tapping, and assembly of the bearing caps by hand. Subsequently, the castings are turned, as mentioned earlier, before the differential bearing bores are finished and threaded, and the driving pinion bores

and faces are finished. This sequence of operations is shown diagrammatically in Fig. 5, from which an idle station, and those for platen raising and lowering, bearing cap fitting, and work loading and unloading, (numbered 1, 2, 11, 12, 20 and 21) have been omitted for clarity. From this diagram, it will be noted that there is a head at each side at the first machining station—No. 3—which can also partly be seen at the right in Fig. 4.

Henceforth, references to the right- and left-hand sides of the machine will assume that it is viewed from the loading end in the direction of platen movement. The head at the right at station No. 3 is the only vertically moving unit on the machine, and is seen in the view from the left-hand side, in Fig. 6. This head has a vertical slide, which carries an 8-in. diameter Galtona (Richard Lloyd, Ltd.) cutter with 16 inserted carbide-tipped blades. Driven at 76 r.p.m., this cutter operates on the outer face surrounding the driving pinion bore, at a feed of 0.126 in. per rev., and leaves about 0.010 in. of stock for a finishing operation. The horizontally-moving head at the left-hand side of the machine, seen in the foreground in Fig. 6, is equipped with a 4-bladed Galtona cutter for rough machining the inner pinion bore, B Fig. 1, about 0.060 in. on diameter being left for removal at subsequent operations.

Tools in the right- and left-hand heads at station 4 perform operations on the large and small pinion bores, respectively, and a view of this station, from the





Fig. 7. The left-hand head at station No. 4 is designed for rough- and finish-machining the face surrounding the bore B, Fig. 1, and chamfering the end of the bore, and has two hydraulically-operated facing slides

Fig. 8. Four V-section grooves are cut in the faces of the bearing cap pillars by tools in a horizontally-moving slide on the left-hand head at station No. 8. The slide is moved by the large hydraulic cylinder *U*



left-hand side of the machine, is given in Fig. 7. Here it may be noted that the movements of all the heads on the machine are controlled by the standard Alfling system. An inclined box *P*, one surface of which is formed of transparent plastics material, encloses a row of micro-switches connected to relays for controlling solenoid-operated valves in the hydraulic circuits. The plungers of these switches are depressed by adjustable dogs on a multi-grooved plate attached to the moving portion of the spindle head, so that, as the head advances, the switches are operated in succession. Another point of interest is that all the slideways are protected by concertina-type covers, also of transparent plastics material.

The right-hand head at station 4, at the far side of the machine in Fig. 7, has only one spindle, which is fitted with four single point tools for semi-finish boring and chamfering the outer ends of the two driving pinion bores *A* and *B*, Fig. 1, 0.015 to 0.020 in. being left on the diameters for removal at a finishing operation. A special facing unit, carried by the left-hand head at this position, incorporates a holder *R*, of cylindrical form. Within this holder there are two slides, each with provision for holding two tools, which can be moved at right angles to the spindle axis by means of a cam mechanism. This mechanism is operated by a hydraulic cylinder which is mounted co-axially with the spindle at the outer end. The ram of this cylinder is connected to the cam mechanism by a drawbar, and it extends into the sheet metal cover *S*. Adjustable stops, carried by the ram, serve to operate micro-switches when it reaches the limits of its travel in either direction, and the next movement in the sequence is thus initiated.

At the beginning of the cycle, the head is advanced, first rapidly and then at a slow traverse rate, up to a stop, and the facing tool-holders, which move in opposite directions, are then

brought into operation. One tool-holder carries a single tool, which takes a roughing cut across the left-hand face of the boss surrounding the bore *B*, Fig. 1. The other holder is equipped with two tools, one of which provides for finishing this face and is set slightly behind the roughing tool. Finally, the second tool in this holder cuts the chamfer at the left-hand end of the bore, and the head is retracted to avoid interference with the boring bar of the right-hand head, the tool-holders being automatically returned to their central positions. The facing spindle is driven at 270 r.p.m. and the tools are fed outwards at the rate of 0.0039 in. per rev. For plain boring operations, such as that performed by the right-hand head, cutting speeds of the order of 200 ft. per min. are employed, and the feed rate, in this instance, is 0.0059 in. per rev.

As indicated in Fig. 5, the next station (No. 5) provides for drilling the four holes in the pillars, which are later tapped for the reception of the bearing cap bolts, drilling eight holes in the pinion bore end face, and spot-facing the 14 holes previously drilled in the flange on the Ryder machine. Station No. 6 is equipped for chamfering the flange holes on the opposite side, also the pillar holes, and the eight holes surrounding the pinion bore, and at station No. 7, there are blow-out heads on both sides, which advance probes into the holes to ensure that they have been drilled to full depth, and clear them of swarf in readiness for tapping. A single spindle in the right-hand head at station No. 8 provides for drilling a hole of 0.495/0.505 in. diameter which is located adjacent to the outer pinion bore in the end face.



Fig. 9. At station No. 11, which is omitted from the lay-out in Fig. 5, the bearing caps are fitted, and the holding-down bolts are tightened to a pre-determined torque by means of a King Dick spanner

CHAMFER-SHAPING HEAD

The left-hand head at station No. 8, which is of unusual design, is employed for cutting V-shaped grooves in the faces K, Fig. 1, of the pillars which carries the bearing caps. Each groove centre line coincides with the bore when it is machined later in the sequence, and half of each groove is thus removed, leaving a chamfered edge on each side of the bore, as indicated in Fig. 1. A close-up view of the head in question, taken from the right-hand side of the machine, is given in Fig. 8. There is a horizontal slide T, which is guided in square-section ways and carries four carbide-tipped tools, shaped to an included angle of 90 deg. Each tool is employed to cut one of the grooves mentioned when the head has been fed to a fixed stop, and the large-diameter horizontal cylinder, partly seen at U, is energized.

The ram of this cylinder has a rounded end, and is not attached to the slide but merely pushes on its end surface so that it is moved past the face of the casting. At the end of the stroke of the large cylinder, the ram is retracted to the position shown and the head is withdrawn. Another, smaller cylinder W, mounted horizontally in a recess between the head casting and the slide, is then employed to return the slide to the right, ready for the next grooving operation. A head on the right at station No. 9, equipped with four spindles,

taps the holes in the bearing cap pillars $\frac{1}{2}$ in. by 11 U.N.C. 3B. The head at the left has 14 spindles which are employed to tap 2 holes $\frac{1}{2}$ in. by 13 U.N.C. 3B, and 12 holes $\frac{1}{4}$ in. by 14 U.N.C. 3B. Tapping is carried out at a cutting speed of about 15 ft. per min. under lead screw control. Station No. 10 has a head at the left-hand side only, which carries four probes for checking and blowing out the pillar holes in readiness for fitting the bearing caps.

Bearing caps are fitted at station No. 11, as shown in Fig. 9, the operation being carried out at the left-hand side of the machine. The caps are supplied in box pallets from another line, on which they are machined on the joint faces, drilled and spot-faced. A hole of about $\frac{1}{4}$ in. diameter is also drilled in each joint face, for the reception of a dowel pin with a hardened cone-shaped end. The point of the cone on each pin projects slightly above the surface of the joint face, and when the cap is fitted in position, and the holding-down bolts tightened, the pointed end is forced into the opposing face of the main casting. In this manner, a location is provided for each cap, so that it may be replaced in exactly the same position that it occupied during the final machining operations, after the differential assembly has been fitted.

Holding-down bolts for the caps are tightened with the aid of an Abingdon King Dick torque spanner, which is set to apply a torque of about 110 ft.-lb. to the $\frac{1}{2}$ -in. diameter bolts. The right-hand side of the machine at this station is idle, and indexing for the next cycle will not take place unless the fitter depresses a push-button to signal that the assembly of the bearing caps has been completed. Between stations No. 11 and 12 is installed the mechanism for turning the transfer bar to engage the ears with the platens. This mechanism comprises two horizontal hydraulic cylinders, one on each side of the machine, the cylinder on the right-hand side being seen in Fig. 10. The ram of each cylinder is connected to one of two swivelling brackets, hinged at a level below that of the transfer bar X, to the underside of which a long cylindrical projection is welded.

This projection is slightly longer than the total travel of the bar during the transfer motion, and it is engaged by jaws on both the brackets mentioned. At the start of the transfer cycle, the bar is in the position shown, and it is first moved to the left until each ear Y, is on the other side of the platen which it is to move. One of the transverse cylinders is then energized to turn the bar slightly, so that the ears are engaged with the platens, and the bar is then returned to the right, moving all the platens along, through the distance

between machine stations. Reference to the function of the second transverse cylinder will be made later, in connection with station No. 19 and 20. Station No. 12, at the right in Fig. 10, is idle, and is not shown in the sequence diagram, Fig. 5.

At station No. 13, the right-hand side of the machine is idle, and on the left-hand side there is a head with a single spindle, on which is mounted a large-diameter turning head. A view of this head, from the right-hand side of the machine, is given in Fig. 11, and it carries three tools of which two can here be seen. These tools are employed to machine the outside surfaces of the bearing caps, on which there are narrow cast projections, to a diameter of 13.435/13.440 in. Two of the tools share the rough-machining, and are set slightly in advance of the third tool which takes a light finishing cut. The spindle is driven at a speed of 56 r.p.m. to obtain the cutting speed of 200 ft. per min., mentioned previously, and the feed is 0.0079 in. per rev. A somewhat longer hydraulic cylinder and special valves are provided for this head, so that it may be withdrawn under manual control for a distance greater than is required for normal operation, for convenience in changing and adjusting the tools.

From Fig. 11, it may be seen that the remaining



Fig. 10. Between stations No. 11 and 12, this mechanism is installed for partially rotating the transfer bar to engage the ears Y with the platens before the bar is moved longitudinally for the indexing operation



Fig. 11. The outside surfaces of the bearing caps are turned by three tools in a head at the left-hand side of station No. 13, and at the next station the platen is turned through 90 deg.


platens on the machine have been turned through 90 deg., to enable operations to be performed on the differential bearing bores, and this turning is effected at the next station (No. 14). Here, the platen is raised on a table, by means of two vertical hydraulic cylinders within the machine base, to a level at which it clears the surrounding machine surfaces and the transfer bar. The table is slowly turned through 90 deg., in an anti-clockwise direction as viewed from above, by a horizontal cylinder operating through a rack and pinion, and is then lowered to return the platen to the transfer track. The next machining station (No. 15) has a head on each side, and each head is equipped with a large and a small diameter spindle.

The larger spindle on each head is fitted with a Galtona cutter having eight inserted carbide-tipped blades, and these cutters are employed for roughing the bearing bores to 4.64/4.65 in., about 0.080 in. being left on the diameter for removal at later operations. In the smaller spindle of the right-hand head is mounted a 4-bladed Galtona cutter which rough machines the bore Z, Fig. 1, cored in the flat wall of the casting, to a diameter of 2.37/2.38 in. A drill in the second spindle of the left-hand head produces a hole of 0.687/0.692 in. diameter in the opposite side of the casting, as indicated at E, Fig. 1. Both heads are fed at 0.060 in. per rev.

Similar spindle combinations are provided on the

heads at each side of the next station (No. 16) at which the bore Z, Fig. 1, is semi-finished and chamfered and the bore E is spot-faced and chamfered. Each of the two larger spindles at this station has three single-point tools for semi-finishing operations on the differential bearing bores. One of the three tools serves to machine the bore to 4.695/4.700 in., leaving about 0.025 in. on the diameter for finishing, a second tool enlarges the end of the bore which is to be threaded, to 4.730/4.735 in., and the third produces a slight counterbore at the outer end. The two bores Z and E, Fig. 1, are tapped at station No. 17, to 2½-in. by 16 U.S.F., and ¾-in. by 16 U.N.F. 3B, respectively, and the castings then reach station No. 18 at which the 4½-in. by 12 U.S.F. threads are milled in the bearing bores.

A close-up view of station No. 18 is given in Fig. 12, which shows the planetary type thread-milling heads fitted to both the right- and left-hand spindles. These heads are fed towards the casting, to advance the cutters into the bores, until the movements are arrested by fixed stops. The portion of each head carrying the spindle and cutter is then turned to feed the cutter into the work to the required depth, and the spindle housing is then rotated through one complete revolution to cut the threads. During this rotation, the cutter spindles are also cam-fed forward by a distance corresponding to one pitch of the thread. At the end of the milling operation the cutters are returned to the central position, and the heads are retracted. Each spindle is driven at a speed of 64 r.p.m. and the rotary feed is 0.094 in. per rev. of the cutter, the total cutting time being slightly more than 2 min.



FINE-BORING AND FACING OPERATIONS


The final operations on the casting, carried out at station No. 19, include fine-boring the differential bearing bores and the driving pinion bores, and facing the outer end of the boss surrounding the larger pinion bore. Station No. 19 can be seen in the background in Fig. 12, and another view, from the opposite side, is given in Fig. 13. The side heads at this station, for finishing the bearing bores, have single spindles, each carrying two single-point tools, and driven at 240 r.p.m., to give a cutting speed of about 300 ft. per min., with a feed of 0.0024 in. per rev. Operations on the pinion bores and face are performed by tools in a spindle carried on an overhead slide, the supporting structure for which can be seen at the top in Fig. 12. Guideways on this structure support a travelling carriage, as seen in Fig. 13, which is moved from the retracted position shown, on the far side of the transfer track, to a central position, for the fine-boring operation, by means of a horizontal hydraulic cylinder.

It is necessary to retract the carriage in order that platens, carrying finished components, can pass from station No. 19 to be turned round and unloaded at station No. 20, which is out of sight to the right in Fig. 13. When the carriage has been moved to the central position above the transfer track, ready for fine-boring, it is located and locked in position by means of dowels and clamps operated by the two hydraulic cylinders B, and two similar cylinders on the opposite side of the overhead structure. Guideways on the carriage support the boring and facing spindle, which is driven by two sets of three V-belts, from a

motor of 5 h.p., mounted at the far side of the carriage. The boring spindle of the head carries tools for finishing the large and small pinion bores to 5.187/5.188 and 2.834/2.835 in. diameter respectively.

Fig. 12. After the differential bearing cap bores have been roughed and semi-finished, the outer ends are threaded by planetary type milling heads at each side of the machine at station No. 18

Fig. 13. The driving pinion hubs are fine-bored in line, the outer end is faced, and the larger bore is chamfered by tools in this spindle head, which moved into position after the platen has been double-indexed to provide clearance



The facing slide for machining the end of the boss surrounding the large bore, and chamfering the outer end of the bore, is actuated in a similar manner to that described in connection with station No. 4, by means of a hydraulic cylinder, mounted coaxially with the spindle. This cylinder is indicated at C, and, as in the previous example, the ram is extended towards the rear and carries a plate D, with adjustable stops which operate micro-switches at the limits of travel of the facing slide. These switches operate solenoid valves which control the machine movements in the correct sequence. For the boring operation, the spindle is driven at 265 r.p.m. and the head is advanced at 0.0039 in. per rev., and for facing, the speed is reduced to 195 r.p.m. At the end of the facing cut, the tool slide is retracted, and the head is returned to the position shown, before the carriage is moved back to the far side of the overhead support, ready for the next indexing motion of the machine.

When this indexing motion takes place, the platen, with the completely machined casting, is moved to a position alongside the carriage and directly beneath the overhead structure, one of the locating dowels at this position being seen at F. The transfer bar, which has an ear G, on the opposite side to those on previous portions, is then returned to the right, and the second of the two cylinders mentioned in connection with Fig. 10 is actuated to turn the bar in the opposite direction to that employed for the normal transfer movement. This action raises the ear G, and another ear to its right, the other ears being simultaneously lowered. The bar is then moved longitudinally to the right, pushing the platen clear of the carriage and the overhead structure to the unloading station (not shown in Fig. 5).

A view of this station is given in Fig. 14, looking in the direction of travel of the platen, and it is equipped with a mechanism, of similar design to that employed at station No. 14, which turns

the platen so that it faces the same way as at the loading position. On the far side of the machine there is a head similar to that at the loading position, which can be brought forward by the operator responsible for unloading and inspect-



Fig. 14. In this view the platen at the left is at the unloading station, at which the clamps are released by a semi-automatic head. After the work has been removed, the platen is advanced into the elevating unit at the right

ing the castings, to loosen the clamping nuts. This operator then removes the casting from the platen and transfers it to the adjacent gauging station. At the next indexing motion of the machine, the unloaded platen is moved on to the platform of the elevating unit at the right in Fig. 14, on which it is raised to the level of the overhead return track.

The elevating and lowering units are of similar design, and each incorporates two substantial cylindrical columns, as seen at *H*, which provide guide-ways for rollers set in slots in the sides of the platform. For raising and lowering the platform, there are two double roller chains which pass over sprockets at the top and bottom, the lower sprockets being driven, through a reduction gear and a friction clutch, by a motor installed outside the cabinet housing. A slat-type conveyor extends for the entire length of the machine to remove swarf, which is pulled along a central square-section channel, and discharged, above floor level, into box pallets at the loading end of the machine. The complete cycle time for the operations described is 3.4 min., and the machine is normally tended by two operators and one setter.

INSPECTION FIXTURES

Castings which have been removed from the machine are de-burred manually, where necessary, and are stamped with identifying letters on the caps and pillars to assist in re-assembly at later stages. Inspection is then carried out, first with the aid of the equipment shown in Fig. 15, which

checks the relative positions of the two main bore axes, and their squareness to each other, also the positions of certain faces. The casting is placed on a datum surface, on which it rests on the end boss surrounding the main pinion bore, and a two-diameter spigot is raised by means of an air cylinder controlled by the two series-connected valves in the foreground. Steel bushes are inserted in the differential bearing bores, and through them is passed a test bar with cylindrical surfaces at each end.

These surfaces make contact with the ends of plungers which project vertically upwards from brackets on the fixture base, and the movements of the plungers are transmitted to the anvils of dial gauges, through lever mechanisms. A post on each side of the position occupied by the casting carries a swinging arm with a dial indicator, and the anvils of these instruments can be brought into contact with the outside surface of the main spigot, adjacent to the flange, to check its position relative to the pinion bores. The gauge *J*, lying on the front of the fixture, incorporates a dial indicator, and the opposite end is inserted, to a fixed distance, in a central bore in the stepped spigot. A plunger on the side of the gauge, connected to the dial indicator, then comes into contact with the inner face adjacent to the small pinion bore, the height of which, relative to the lower machined surface of the casting, is thus checked.

At the right is seen a bracket *K*, with channels which can be engaged with the central portion of the test bar, and when this bracket is placed in position, a pin at each end should enter one of the two holes *D*, Fig. 1, employed for the location of the casting on the transfer machine. From this fixture, which is normally used for percentage checking only, the castings are transferred to the air-operated gauging unit shown in Fig. 16, for measurement





Fig. 15. Inspection of the relative positions of the differential bearing and driving pinion bores is carried out with this receiver gauge which incorporate dial gauges

Fig. 16. A fixture supplied by Thomas Mercer, Ltd., is employed for checking the bores for diameter and ovality. Mechanical contacts are provided to avoid errors due to variations in surface finish in the bores



of the diameters of the driving pinion and differential bearing bores. Supplied by Thomas Mercer, Ltd., this unit incorporates four indicator dials, which are grouped on a single panel at the left for ease of reading, and graduated in widely-spaced 0.0001 in. divisions. In addition, the panel is provided with red and green lamps, one of which is illuminated to indicate to the operator that all the bores are within, or that one or more of the bores is outside, the dimensional limits which are specified.

In the fixture, the casting is loaded, initially, with the machined side of the main flange resting on the two flat support surfaces *L*, and is then pushed to the rear where it is finally located by means of two dowels, which are raised by means of the lever *M*, to enter the holes *D*, Fig. 1. Above the position now occupied by the casting, there is a measuring head which provides for checking the diameters of the two pinion bearing bores. Two more heads, one on each side of the casting, serve to check the two differential bearing bores, and each head is mounted on the ram of an air cylinder, whereby it is advanced into, and retracted from, the bore. The measuring heads are so mounted that they can float slightly to accommodate small amounts of misalignment, and incorporate mechanical contacts so that variations of surface finish in the bores do not affect the accuracy of the readings.

The air cylinders, on which the heads are carried, are controlled by the two series-connected valves at the front of the fixture. These valves must be operated, so that the inspector's hands are clear of the moving parts before the cylinders are energized. After the heads have been engaged with the respective bores, they may be turned by hand if a check for ovality is required. The photograph for Fig. 16 was taken before the fixture was installed in the factory, and the side gauging heads have since been fitted with simple sheet metal guards having L-shaped slots, through which handles secured to the heads project. With this

arrangement, the gauging heads can be turned through about 90 deg. only when they are engaged with the bores, and must be returned to their original position before they can be retracted.

From the gauging station, the castings are taken to a washing machine, and thence to the assembly line where the driving pinion and differential mechanism are fitted.

ALL-WEATHER FORK-LIFT TRUCK.—An all-weather fork-lift truck has been supplied by the Yale & Towne Manufacturing Co., Ltd., Wednesfield, Wolverhampton, to Metropolitan-Vickers Electrical Co., Ltd., for use both inside and outside their works. The truck, which is a series 51, rated at 8,000 lb. capacity and fitted with an adjustable jib attachment, has a totally-enclosed driving cab of sheet steel construction, complete weather protection being thus provided for the operator. There is a total of 25 sq. ft. of window space, glazed with Triplex safety glass, which ensures good all-round visibility.

The truck is employed for setting-up drop stamps in the forging section, where difficulty would be experienced in introducing a jib crane between the arms of a drop hammer, also in the maintenance department, where its manoeuvrability facilitates the movement of bulky parts through low doorways.

Outside the factory, the truck is employed, for example, for transporting large cylindrical oil conservator shells, weighing 30 cwt.

Typical Operations on Components for the Convair 880 Jet-propelled Air-liner

The Convair Division of the General Dynamics Corporation, San Diego, Calif., U.S.A., has spent 22 million dollars on tooling and other facilities in preparation for building the Convair 880 jet-propelled air-liner. Of this total, machine tools and associated equipment accounted for nearly 4 million dollars, and further expenditure under this heading is anticipated.

The Convair 880 is designed to serve cities of medium size, and is suitable for existing runways. It is stated that it can be operated profitably at ranges of 300 to 3,000 miles. Eight-eight passengers are accommodated in the de luxe-interior plane and 109 passengers in the tourist version. The aircraft is intended for altitudes up to 40,000 ft. and will have a maximum take-off weight of 178,500 lb. It is understood that the Convair 880 will be in service on important airlines by the spring of 1960.

Over 1,000,000 sq. ft. of factory space has been provided for production of the 880, and most of the new manufacturing equipment has been installed. Machine tools specially designed for economical operations on the 26,000 different structural parts (exclusive of systems) required

for each aircraft are a feature of the production lines. As far as possible, the new machine tools are automatically operated by means of tape and electronic controls.

One of the most spectacular machines is a duplex-carriage, 105-ft. long Onsrud spar mill of which a close-up view is shown in Fig. 1. It incorporates electro-hydraulic controls to enable good finish and accuracy to be obtained at high speeds. In this illustration, the machine is seen operating on the lower-keel longeron for the 880 aircraft, which weighs 1,700 lb. in the extruded form and only 310 lb. when finished. Modifications to the extrusion, for subsequent batches, will result in a reduction of weight, before milling, to 1,200 lb.

The keel is of constantly varying cross-section so that it is necessary to impart up-and-down and angular movements to the cutter-heads as each of the two carriages moves along the bed. One carriage is equipped with a horizontal and a vertical milling head, and the second has four horizontal heads. In Fig. 1, a milling head on the first carriage is seen in an approximately horizontal position, whereas in Fig. 2, it is tilted to a





Fig. 1. On this Onsrud spar mill, components up to 60 ft. long by 3 ft. wide can be machined. There are two carriages, one with a vertical and a horizontal head, and the other with four horizontal heads

Fig. 2. The horizontal heads on the spar milling machine can be tilted through angles up to 45 deg. in either direction



considerable angle. Milling cutters up to 16 in. diameter and up to 18 in. wide can be employed.

Selsyn tracer controls supplied by the General Electric Co. impart the required movements to the milling cutters as either carriage travels along the bed. The cam followers on the tracer units engage cams mounted along the front of the bed as seen in Fig. 3, and the required movements are thus imparted to the milling heads through an electro-hydraulic control system, the power for these movements being provided by torque motors. Speeds of 1,800 and 3,600 r.p.m. are available for the horizontal heads, and of 3,600 and 7,200 r.p.m. for the vertical head. The heads are driven by 100-h.p. motors. Parts up to 60 ft. long by 36 in. wide can be handled on this machine which is equipped with a chip conveyor.

SKIN MILLER WITH MAGNETIC TAPE CONTROL

The greatest importance is attached by Convair production engineers to the numerical control of machine tools for use in the aircraft industry. Their experience led to the installation of the large Giddings & Lewis skin miller shown in Fig. 4, which is completely controlled by a magnetic tape. The vertical and horizontal heads are operated in these planes, and at prescribed angles, by a Numericord control system.

This system is capable of operating the machine with two heads, and with continuous motion on five axes, in addition to performing 12 switch-

ing and auxiliary functions. The control cabinet, seen at the extreme right in Fig. 4, is provided with visible h.p. consumption meters, rate-of-feed indicators, and manual controls for setting-up purposes or for operating the machine when a tape is not being used.



Fig. 3. Vertical movements of all cutter-heads on the Onsrud machine, also lateral and tilting movements, are controlled by long cam-plates mounted at the front of the machine bed



Fig. 4. Large Giddings & Lewis skin miller which is completely controlled, from magnetic tapes, by the Numericord cabinet at the right

A typical application of the horizontal head is shown in Fig. 5, where integral ribs are being milled. The bed of the machine will accommodate work up to 30 ft. long by 10 ft. wide, which is sufficient for the panels of the swept-back wings of the 880 aircraft. The milling head motors deliver 50 h.p. at 1,800 r.p.m. and 100 h.p. at 3,600 r.p.m. Mist lubrication is supplied to the milling cutters during the operation.

VARIAX PROFILING MACHINE WITH NUMERICORD CONTROL SYSTEM

The Giddings & Lewis Variax profiling machine shown in the close-up view in Fig. 6 is also numerically controlled. Any part up to 168 in. long by 48 in. wide can be milled automatically along three axes without the necessity for using templates to guide the cutter. A Numericord unit provides 14 channels of instruction. It is capable of operating the cutter-head in the three axes of motion, and, in addition, performs 12 switching and auxiliary functions. Once the milling head has been lined up manually, the operator is only required to press a button to start the machine cycle. Operations that formerly required 10 hours are now performed in 70 min. with this numerically-controlled equipment.

An exceptionally versatile profiler, the Sundstrand profile milling machine, which is widely employed at the Convair works for both heavy and light operations, is shown in Fig. 7. Cuts are controlled in two dimensions by moving the stylus of a True-Trace hydraulic head along a template

at the front of the table. There is also a hydraulic valve on the column of the machine for quickly changing the height of the cutter with respect to the work for taking cuts at different levels, and it is therefore unnecessary to provide a stepped template. A small turret with a series of micrometer stops graduated to 0.001 in. facilitates setting the cutter to different heights.




Fig. 5. A typical operation is here being performed with the horizontal head of the skin miller, on a panel with a series of integral ribs machined from the solid

Fig. 6. A typical operation in progress on a magnetic tape-controlled Variax profiling machine



Cuts as deep as 2 in. have been taken on this machine with a cutter of 1½ in. diameter at high speed and feed rates. Speeds from 52 to 1,990 r.p.m. are available, and the feed is governed by manual manipulation of the tracer stylus. Standard end- and face-milling cutters are employed.

Routing has been substituted for profile milling on certain light-section structural members, one of which is seen on an Ekstrom-Carlson machine in Fig. 8. In this instance, the router is used for cutting elongated holes in one leg of a wing-bulkhead rail part, and for profiling along the edge of this leg. Notches of different depths are also routed in the leg that is seen upright in the illustration. These notches are, of course, cut with that leg of the structural member mounted hori-

zontally on the table of the machine. Templates clamped to the work guide the cutter.

The machine is equipped with a water-cooled motor that provides speeds of 7,200 and 14,400 r.p.m. Depth stops on the side of the head limit the down movements. Special fixtures are provided for the various components, and clamps attached to the front of the table apply pressure to the work both laterally and vertically. Other typical work handled by this machine includes light spars and stiffeners.

The Arrow profiling machine in Fig. 9 is equipped with a cutter-head that can be swivelled through 20 deg. in either direction from the vertical centre line, to enable "twists" to be machined. Straight movements of the cutter-




Fig. 7. A close-up view of a typical operation in progress on a Sundstrand profiling machine which is controlled by a True-Trace hydraulic head from a template at the front of the table




Fig. 8. An Ekstrom-Carlson routing machine is here being employed for producing elongated holes, contoured edges, and notches in a structural member for Convair 880 aircraft

head up and down and transversely are controlled by the True-Trace hydraulic head which the operator is guiding along a template in Fig. 8. Pivoting movements of the cutter-head are obtained by means of a second tracing valve unit with a roller, which is seen adjacent to the cutter-head. Spindle speeds from 37 to 3,000 r.p.m. are available.

The large fuselage belt frames required for the 880 transport aircraft necessitated the installation

of the 75-ton Cyril Bath radial draw-former shown in Fig. 10, which is believed to be the largest of its type in the world. Various other parts made from extrusions are handled on the same machine. The illustration shows an aluminium H section, which measures $3\frac{1}{8}$ by $4\frac{1}{2}$ in. and has cross sectional thicknesses up to $\frac{1}{2}$ in., being stretch-formed to an outside radius of approximately 6 ft.

One of the features of this machine is a yield and tension control. Signals imparted by a load cell on one pulling head are transmitted to an amplifier which gives readings for yield, tension, and elongation. After one piece has been formed to specification, duplication of settings on the instrument panel will ensure the production of subsequent pieces with the same characteristics.

This radial draw-former is also used for ironing T-sections to the required contours, and such an operation is shown in Fig. 11. The work is mounted on a form block of the re-





Fig. 9. An Arrow profiling machine on which the cutter head can be swivelled for taking angular cuts, in addition to being moved vertically and horizontally

Fig. 10. Cyril Bath radial draw-former of 75 tons capacity which is used for producing large fuselage belt frames and a variety of other parts



quired contour, and the traverse slide is moved over the work lengthwise, this slide being fitted with a suitable die for pressing the part against the form block. For all applications, the machine is hydraulically operated under electrical control.

Before parts are sent to the radial draw-former, they are thoroughly cleaned with Oakite in tanks, and heat-treated in the Despatch oven shown in Fig. 12. The oven has a work space 41 ft. long by 8 ft. wide by 8 ft. high, and is believed to be the largest of its type in use in the U.S. aircraft industry.

It is electrically heated and can be maintained at temperatures ranging from 400 to 1,300 deg. F. In conditioning the aluminium-alloy structures for the 880 transport aircraft, temperatures ranging from 860 to 920 deg. F. are normally employed. From 30 to 60 min. is required to bring parts up to the desired temperature. They are then soaked for 1 hour.

For heat-treatment, the work is loaded on the structural-steel rack seen in Fig. 12. Then, the

rack is pushed into the space beneath the oven and lifted by a hydraulic elevator into the oven tower. At the end of the heat-treating period, the rack, with its load of work, is quickly lowered into a quenching tank in a pit directly below the furnace. From the time that the oven doors are opened until the work is completely immersed, not more than 10 sec. must elapse. In practice, the operation has been carried out in $6\frac{1}{2}$ sec. The water in the quenching tank is held at a tempera-




Fig. 11. An aluminium-alloy T-shaped extrusion is here ironed to the required contour on the large radial draw-former




Fig. 12. This oven, used for the heat-treatment of aluminium-alloy structural members prior to radial draw-forming or ironing, is claimed to be the largest in the U.S. aircraft industry

ture of 65 deg. F., and parts remain in the tank for approximately 1 min.

It is essential to prevent aluminium sections

refrigerator is maintained at a temperature of -20 deg. F., and racks are provided along the walls, on which the sections are supported.

and sheets ageing between the heat-treating and drawing stages. For this reason, a refrigerator, more than 40 ft. long, has been installed. The workpieces are stored in this refrigerator as soon as they have been quenched. The re-


Frigolux Cold-light Illuminated Magnifier

Optical-Mechanical (Instruments), Ltd., 17, Station Road, Egham, Surrey, have been appointed sole selling agents in this country for the Frigolux illuminated magnifying unit shown in the accompanying illustration.

Illumination of specimens is provided by a circular "cold-light" tube incorporated in the swivelling lens head, which is carried at the right-hand end of the adjustably-mounted cross arm. The 3.5-in. diameter lens provides a magnification of 2x, but a supplementary prism monocular can also be accommodated, which, in conjunction with the standard unit, gives magnifications of 9 and 14x, at the same working distance. Power is supplied to the light source through a transformer at the opposite end of the cross arm which serves as a counterweight to the lens head. In place of the circular base shown, the magnifier can be supplied

with a clamp at the foot of the vertical post, and it can then be secured to a bench.

It is claimed that with the light source employed, illumination is dazzle free and is so evenly distributed that shadows are largely eliminated. No heat is radiated from the tube, and the daylight type of illumination provided, ensures viewing conditions which enable colours to be accurately distinguished.



Frigolux cold-light illuminated magnifier which incorporates an annular lamp

Lost Wax Investment Casting

Some Recent Developments by Trucast, Ltd.

The process of lost wax investment casting employed by Trucast, Ltd., is being operated under licence by a number of important firms in this country, including Rolls Royce, Ltd., The Fairey Aviation Co., Ltd., and Deloro Stellite, Ltd., also in France, Sweden, Spain, Switzerland, and Canada, and at the company's works at Farnham Royal Lodge, Bucks., certain developments and improvements to the process have been introduced in recent years. Attention has always been paid to increasing the overall size of refractory mould which is used, to allow a greater weight of metal to be poured at one time and thus increase the ratio of "useful" metal to that required for runner bars, for example. Such increases have been achieved by employing what is known as a "dual-gravity" refractory material, which, by providing increased strength, allows a larger mould to be handled.

In addition, in order to reduce the time required to produce the wax patterns, the company has developed a standard wax injection press which, when using a single-impression die, will produce the patterns at the average rate of 4 per min. A method of injection has been adopted whereby the natural high coefficient of contraction of the wax is, to a large degree, counteracted. Also, by the use of a new form of pre-coating material, the surface defects known as "slag spots," or "fusion," which frequently occur when casting chromium alloys of the martensitic type, also, to a lesser degree, with 18/8 stainless-steel, have been eliminated. Investigations have shown that these blemishes are caused by the fusion of the silica pre-coating, which is applied to the wax tree before investment, and the molten metal, and that they increase in number in proportion to the amount of time the metal, in its molten state, is in contact with the mould.

In some cases, these defects can be avoided, or reduced, by arranging for the mould to be cooled quickly, with the result that the metal solidifies rapidly. When thin sections are being cast, however, it is not always possible to follow this procedure, and the special pre-coating, which consists of a basic refractory material, is then employed. It is claimed that the use of this pre-coating eliminates "slag spots," and that the steels mentioned above can readily be cast without blemishes.

Great care must be taken during the pre-coating of the wax trees, also during the subsequent drying process, and a bank of air-tight drying cabinets has been built in which the temperature and humidity can be accurately controlled. These cabinets are installed so that they form a dividing wall between the pre-coating and investment departments, and a door is provided at each side of each cabinet, to enable the patterns to be loaded from one side and withdrawn from the other.

WAX INJECTION MACHINE

The latest type of wax injection machine, to which reference was made above, is shown in Fig. 1. This machine is used in conjunction with an electrically-heated holding tank with a capacity for 2½ cwt. of wax. A feature of this machine




Fig. 1. The wax pattern injection machine which has been developed by Trucast, Ltd., for producing wax patterns from a single-impression die at the average rate of four per min.




Fig. 2. The air-operated toggle mechanism for raising the lower die platen of the wax injection machine shown in Fig. 1

is that the wax is injected at the minimum temperature necessary to ensure plasticity, and, once in the mould, it solidifies quickly to a condition in which it may be handled without risk of damage or deformation. Moreover, by injecting the wax at the lowest possible temperature, shrinkage during cooling is reduced to the minimum. Accordingly, considerable attention has been paid to the means for maintaining the wax at the required temperature. The upper part of the machine houses the main injection cylinder, also four auxiliary holding cylinders, and is filled with water which is kept at a temperature of approximately 80 deg. C. by means of electric immersion heaters. Each holding cylinder is connected by a pipe to the injection cylinder, and contains a piston and rod coupled to a double-acting air cylinder. Wax is transferred from the main holding tank to the four auxiliary cylinders, which are open at the top and are fitted with removable covers. Individual controls are provided for each of the four double-acting air cylinders, and with this arrangement the wax in the holding cylinders can be transferred to the injection cylinder as required.

Handles seen projecting from the panels at the right and left of the machine in Fig. 1 serve for controlling the discharge of wax from the holding cylinders, and an interlocking mechanism is incorporated to ensure that wax is passed to the inject-

tion cylinder only when the latter is idle. On the centre panel, there are controls for raising and lowering the bottom platen, and injecting the wax. Dial-type instruments are provided to indicate the temperature of the wax, also the pressure of injection, and a red pilot light is incorporated which gives a warning when the injection cylinder requires replenishing.

The bottom platen of the machine, to which the lower die is clamped, is raised and lowered by means of a double-acting vertically-mounted air cylinder, which works in conjunction with three toggles. These toggles are equally-spaced around the air cylinder, and one is seen in the close-up view, Fig. 2. The lower arm is pivoted to the block A, which, in turn is attached to the fixed triangular plate B. This plate is located by the three ground vertical tie-bars of the machine, and serves also to support the air cylinder, which is just visible at C.

Each upper toggle arm, D, is pivoted to a block attached to the underside of the moving platen, and is extended past this pivot point to be connected by a plain link (as at E) to a bracket on the piston rod. As the latter rises, to elevate the lower platen, the toggles are brought to the dead centre positions to lock the dies in position, mechanically, irrespective of any variations in the air line pressure.




Fig. 3. Close-up view of the lower die platen of the Trucast wax injection machine, with the bottom half of a die clamped in position. The lever seen projecting from the front of the die operates an ejector for removing the wax pattern

The capstan-type adjusting nuts, seen below the bottom plate *B* in Fig. 2, provide for the initial setting of the bottom platen assembly, as a complete unit, to accommodate different die thicknesses. A close-up view of the working surface of the bottom platen, with the lower half of a die clamped in position, is shown in Fig. 3. The lever seen projecting towards the front operates an ejector for removing those patterns which remain in the bottom die after injection, and there is an automatic ejector, mounted coaxially with the injection nozzle in the upper platen, for patterns which remain in the upper die member.

In addition to maintaining the temperature of the wax as low as is consistent with plasticity, the machine injects the wax under a pressure of 1,000 lb. per sq. in. to ensure that the cavity is completely filled, and to assist in counteracting the high coefficient of contraction.

Depending on the size of the die cavity, which determines the volume of wax required, this machine will produce between 2 and 6 patterns per min., from a single-impression die. When the dies are opened, after the injection period, the pattern can be removed at once, and handled without risk of damage or deformation. This wax injection machine, which is known as the series 200, Mark 7, has been developed by the company for its own use, and that of its licensees, and the machine shown in Fig. 1 was photographed immediately before despatch to the Swedish firm of Nyby Bruk AG.

RADIO-FREQUENCY FURNACE

Also designed and built by the company for use by licensees is the furnace shown in Fig. 4. Radio-frequency heating is employed exclusively in the Trucast process in order to avoid the possibility of carbon pick-up. Consequently, the range of materials which can be used for investment casting is widened, and it is interesting to note, for example, that Swedish iron can be cast with total impurities of less than 0.1 per cent, and with a carbon content below 0.04 per cent. Another material for which r.f. heating is essential is a type of heat-treatable stainless steel known as Trubrite. This alloy, which has a maximum carbon content of 0.04 per cent, and contains Cr. 26; Ni. 5; Mo. 2; and Cu. 3 per cent, has a normal tensile strength of 60 tons per sq. in., and possesses corrosion-resisting properties superior to those of 18/8 stainless-steel.

As may be seen in Fig. 4, the crucible is trunnion-mounted, and the refractory mould is clamped in the inverted position to the top face. For pouring, the mould and crucible are rotated through




Fig. 4. The Trucast furnace, with a mould clamped in position ready for pouring. Radio-frequency heating is employed, to avoid the possibility of carbon pick-up

180 deg., as a complete unit and the molten metal is transferred, by gravity. At *F* in Fig. 4 is shown the inlet connection for a supply of air which is introduced to take the place of the metal, as it leaves the crucible, and impose a nominal pressure to ensure that the cavity is completely filled.

An electric motor and 2-speed reduction gear are used for inverting the crucible and mould, but this operation can also be carried out manually, as it is desirable, in some instances, to vary the speed of rotation slightly during the early stages of inversion. When pouring has been completed, the mould is unclamped from the furnace and removed to the cooling area.

STRONGER REFRACTORY MATERIALS

As was mentioned earlier, the weight of metal which can be poured at one time, and consequently the number of castings which can be produced as one tree, is determined to a great extent by the strength of the mould. The latter must possess sufficient strength to withstand the entry of the molten metal, also the handling necessary prior to the pouring, and the special refractory which has been developed enables moulds to be made with maximum dimensions of 11 by 8 by 17 in.,



capable of receiving 30 lb. of molten metal. This "dual-gravity" mould material consists of a mixture of coarse and fine grains. The coarse grains have a low, and the fine grains a high, specific gravity, and the two materials are mixed in such a proportion that during the vibrating process which follows the initial investment, no segregation occurs. As a result, the coarse and fine grains are distributed evenly throughout the mould, and, after firing, a strong refractory is obtained. Magnesite or sillimanite is used for the coarse, and zircon for the fine grains. The even texture of the moulding material can be seen in Fig. 5, which shows a

Fig. 5. This partially-opened mould shows the even texture of the "dual-gravity" refractory material, which, by providing increased strength, has enabled mould sizes to be increased

partially-opened refractory and one side of a tree of 72 turbine blades.

An indication of the manner in which the patterns are assembled to form a tree is afforded by the group of waxes for Rolls-Royce turbine blades shown in Fig. 6.

Each blade measures $7\frac{1}{4}$ in. overall, and by careful arrangement a total of 10 has been attached to the two horizontal runners. It may be noted that the aerofoil section of these blades is hollow, and the resultant envelope of metal varies in thickness between 0.050 and 0.080 in., these dimensions being held, on average, within ± 0.005 in. The tree of blades in Fig. 6 affords an example of the favourable proportion of "useful" metal to that required for runners, for example, obtainable by the use of the larger mould. Similarly, attention is drawn to the tree of 24 waxes shown in Fig. 7. These patterns, for a gyroscope component, measure approximately 2 in. diameter by 2 in. long. The wall thickness of the drum portion is 0.025 in., and whilst the limits called for are ± 0.005 in. it is stated that, in practice, this dimension is held within ± 0.003 in.

EXAMPLES OF INVESTMENT CASTINGS

One of the principal attractions of investment casting, from the economic point of view, is the possibility which it may afford for producing an integral assembly, as an alternative to the use of two or more separate machined components. Even where a casting replaces a single machined piece, however, a considerable number of operations can often be eliminated, and an example of such a conversion is shown in Fig. 8. At the left are seen the parts of a pawl assembly, of which right- and left-hand forms are required, in the fully-machined condition, when it comprised three separate pieces, namely the pawl *F*, the block *H*,





Fig. 6. A typical tree of wax patterns for turbine blades. These blades are approximately $7\frac{1}{4}$ in. long, and, by careful arrangement, a total of ten has been assembled in one tree. The aerofoil sections of these blades are hollow

Fig. 7. Wax patterns for a gyroscope component assembled as a tree. There are 24 of these waxes, each measuring approximately 2 in. diameter by 2 in. long, and the wall thickness of the drum portion is maintained to $0.025 \text{ in.} \pm 0.003 \text{ in.}$

and the spring anchor pin G. The part F was made from 1- by 2½- by 1½-in. section, bright drawn mild steel bar, which was annealed before machining. A total of 7 separate machining operations was required to produced this part, including horizontal milling (two separate machines), drilling (main bore and oil hole), oil grooving, profiling, surface grinding, and internal grinding. Two separate fitting operations were also involved, as well as cyanide hardening and straightening. In addition, the rectangular block and spring anchor pin were made as two separate items, and assembled to form a unit.

When the pawl is made by investment casting, as seen at the right of the figure, only two separate pieces are required. The material used is a cobalt-based alloy developed by the company, and known as Truhard 10, and no heat-treatment is necessary. Only four machining operations are carried out, namely, lapping the cast bore to $0.489/0.490 \text{ in.}$ diameter, to receive an expanding mandrel for location purposes; grinding the end faces to the specified dimension and removing the riser (both operations being performed on the same horizontal grinding machine); internally-grinding the bore to finished size; and grinding the tongue, remote from the hooked end, to finished width. Hand work is confined to stoning the radius on the tip of the hook to obtain a neater appearance.


It will be noted that with the original, machined,



design, lengthwise adjustment of the spring anchor pin was obtained by sliding the rectangular block in a machined groove in the pawl member. For the casting, the design was changed and the pin was made with a forked end which straddles the tongue cast on the boss. There is a cast slot in this tongue to provide the necessary adjustment, and no machining is required either for this slot or the anchor pin. It may also be noted that with the investment castings no tapped holes are needed, and the oil hole is cored and requires no machining.

Another advantage which was gained by making this assembly from investment castings was that the heavy section between the hook and the boss

Fig. 8. The three fully-machined steel parts of the pawl assembly at the left have been replaced by the two investment castings seen at the right. A considerable reduction in machining time has been achieved, coupled with the elimination of a heat-treatment operation






Fig. 10. The steel part at the left was machined from the solid. By employing an investment casting, as seen at the right, considerable economies in machining time have been achieved. It has also been possible to increase the strength of the part by providing a longitudinal rib

could be cored out, leaving an $\frac{1}{8}$ -in. thick rib at each side. It was found that by lightening the part in this manner, the balance, when in operation, was greatly improved. This pawl works continuously in conjunction with a cast iron ratchet wheel, and with the previous material the life of the hook was unsatisfactory owing to the wear which occurred. By using a cobalt-base alloy, the working life has been increased considerably.

The investment casting at the right in Fig. 9 has taken the place of the two machined items, at the left, which formed parts of a delivery chute and were assembled by soldering. Made from drawn brass of $\frac{1}{8}$ by $\frac{1}{2}$ by $1\frac{1}{2}$ in., the flange plate was milled to width on a horizontal machine. The semi-circular cut-out was produced on the same machine, and the part was then transferred to a vertical key-seater on which the two round-end slots were cut.

For the chute, half-hard brass sheet, measuring $\frac{1}{8}$ by $1\frac{1}{2}$ by $2\frac{1}{2}$ in., was employed. All burrs were removed and all corners radiused, by hand, and the two parts were then cleaned and soldered. Subsequently, the assembly was despatched for chromium plating by an outside contractor.

Made from an austenitic stainless-steel, the investment casting requires no plating, and has a considerably longer life than was obtained with the previous design, which was determined entirely

by the wear-resisting properties of the chromium plating. Immediately the latter exhibited signs of wear, the part had to be replaced. As an investment casting, the assembly requires only two machining operations, namely grinding the outside face of the flange square with the chute and removing the flash, both operations being carried out on a surface grinding machine. It will be noted that when this assembly was redesigned for investment casting, the opportunity was taken to provide a strengthening rib between the underside of the chute and the backplate, a feature which would have been difficult and expensive to incorporate in the previous assembly. The round boss in the centre of the rib is a casting runner, which was provided to ensure soundness of metal on the longitudinal centre line of the chute. This runner is trimmed back flush with the edge of the rib prior to the grinding operations. Finally, the




Fig. 9. A delivery chute was formerly made from the chromium-plated brass pressing and the brass plate seen at the left, the two pieces being soldered together. The assembly is now made as an investment casting from austenitic stainless-steel, as seen at the right

Fig. 11. With the exception of a change in cross-section to reduce the weight, this investment casting is identical in design to that produced hitherto by machining from solid $\frac{1}{8}$ -in. thick gauge plate


part is straightened, if required, and the burrs are removed by hand.

Reductions in machining time were obtained by producing the workpiece at the left in Fig. 10 as a casting, the latter being shown at the right. Hitherto, this part was machined from the solid, in steel, and required a large number of different set-ups. The overall dimensions are $5\frac{1}{4}$ in. long by $1\frac{1}{8}$ in. wide by $\frac{3}{8}$ in. deep, and the centre section between the two $\frac{1}{8}$ -in. thick end plates was machined away to leave an $\frac{1}{8}$ -in. thick connecting plate. An end-milling operation was required to produce the two $\frac{1}{8}$ -in. wide by $\frac{1}{8}$ -in. deep slots on either side of the central raised portion, and semi-circular clearances were necessary adjacent to the latter to allow the cutter to run out.

The advantages which were gained by producing the part as a casting are obvious, and a strengthening rib was again included, in this case to improve the rigidity of the $\frac{1}{8}$ -in. thick connecting plate. All hand operations connected with the removal of sharp corners and burrs have been eliminated, and the only machining required is the facing of the end plates and the line boring of the three holes. It may be noted that the part identification number is also cast.

The pawl finger shown in Fig. 11 is another good example of a conversion from fully-machined steel to investment casting. Hitherto, this part was machined from the solid, from $\frac{1}{8}$ -by 2- by 4-in. gauge plate, and involved lengthy horizontal milling operations. After milling, the burrs were removed by hand, the $\frac{1}{8}$ -in. diameter hole was drilled and reamed, and the profile was filed to shape with the aid of a template.

A cyanide hardening operation followed, after which the part was straightened and cleaned and the hole was finish lapped. Finally, the overall width was brought to the required size by a surface grinding operation. As an investment casting, the cross-section was changed to a T-shape, and the part is cast from Truhard 10 cobalt-based alloy. After an initial straightening operation, the width is finished ground as hitherto, and the excess metal on the bottom edge is removed on the same machine. Next, the top edge of the hook is stoned, also the disc-like portion at the tail of the component. Finally, the $\frac{1}{8}$ -in. diameter hole



is internally ground. No heat-treatment is required.

When in use, this part performs 900 oscillations per min., and as a result of the change in section mentioned, the cast form is lighter than the fully-machined finger. In addition, the material now used has better wear-resisting properties than the heat-treated gauge plate. This characteristic is of considerable importance, because the component is located in a somewhat inaccessible position on the machine.

Grateful acknowledgement is made to the Molins Machine Co., Ltd., for permission to publish in this article photographs and details of the various parts seen in Fig. 8 to 11, inclusive.

PRODUCING WAX INJECTION DIES FROM STRICKLED PLASTER MOULDS

Although the lost wax investment casting technique is extremely effective for producing accurate castings of difficult three-dimensional forms in general, and of turbine blades in particular, a considerable amount of time and money may be expended in the production of the accurate master model from which the wax injection die is made. The most difficult shape to reproduce on the master model of a turbine blade is usually the aerofoil portion. This portion, however, generally consists of a form which can be generated by a number of straight lines drawn between two or more templates, which represent the various sections of the required blade. Advantage has been taken of this fact by Trucast, who have developed a method of producing plaster half-moulds for casting wax injection dies, in which the aerofoil section of the blade is formed by strickling the plaster in conjunction with suitable templates. With this process, the necessity of producing a master model




Fig. 12. Typical hard plaster mould for producing one half of a wax injection die. Brass models are used as patterns for the root fixing and tip portions, and the blade portion is produced by a strickle board in conjunction with the templates *L* and *M*

of the part required is completely eliminated.

A mould for a 2-section blade is shown in Fig. 12, where the tip and root templates are indicated at *L* and *M* respectively. In conjunction with these templates, a strickle board has been used to produce the concave side of the aerofoil section. A similar procedure is employed to produce the mating half-mould, which contains the convex side of the blade, great care being taken to provide accurate locations so that the half castings will match on assembly. The mould casing is of built-up construction in steel, and brass patterns of the root fixing and tip portions are located in the plaster, in the correct relationship to the aerofoil section, by the additional templates seen to the left and right of the templates *L* and *M*, respectively.

The templates are filed to shape in position in

a special shadow-type projector, designed and built by the company, with which are used accurate line drawings of the aerofoil sections, supplied by the customer. Depending on the size of the turbine blade, these outlines are drawn either 10 or 20 × full size. The bottom face of each template has a locating shoulder which abuts a similar lengthwise projection machined in the floor of the mould box, thereby ensuring that all the templates are located accurately in the transverse direction. Spacing bars are used to set the templates at the required centres, and the complete pack is then locked together by clamping screws provided in the end faces of the mould box.

When the plaster moulds have set, a bismuth/tin alloy casting is made from each, under pressure, and these castings are subsequently joined to produce a complete wax injection die. It is stated that with this procedure, a wax injection die for a turbine blade of average complexity can be produced in 60 to 75 man/hours, whereas more time than this is frequently required to produce a master only with the conventional methods of manufacture.

"Rapid" Deep-field Circular Lifting Magnet

The circular lifting magnet shown in the accompanying figure has been developed by Rapid Magnetic Machines, Ltd., Lombard Street, Birmingham, 12, and is intended primarily for applications where space is limited, as in the loading and unloading of railway wagons, also in instances where the load to be lifted has a limited response to magnetic induction. This magnet has a deep field, and it is stated that, depending on the nature of the load, it is capable of lifting a weight up to 100 per cent greater than is possible with a conventional electro-magnet of equivalent diameter.

Of 46-in. diameter, the magnet here shown is employed for slag handling, and is capable of lift-

ing masses of iron-bearing slag up to 3 tons in weight, or "skull cracker" balls up to a maximum of 9 tons. It can be used in all applications where conventional magnets have been hitherto employed.



"Rapid" 46-in. diameter deep-field circular lifting magnet

Andantex Speed Reduction Pulleys

The sole licensees for the manufacture and distribution of Andantex speed reduction pulleys in the United Kingdom and Commonwealth countries are Furnival & Co., Ltd., Reddish, Stockport. A cut-away view of one of the pulleys, connected by V-belts to a driving motor, is shown in the figure.

Of compact design, the pulleys are intended for direct mounting on shafts, and speed reduction is obtained by built-in epicyclic gearing. They are available in 16 sizes for transmitting up to 80 h.p., and various arrangements of epicyclic gears can be incorporated to give 21 different speed reduction ratios, ranging from 2.79 to 1 up to 273 to 1, when the pulley and the driven shaft are rotated in the same direction. Reduction ratios from 1.79 to 1 up to 272 to 1 can be provided when the pulley and shaft are driven in opposite directions.


A central cavity in the pulley forms an oil bath and houses the helical reduction gears, which are made from nickel-chrome steel, hardened and precision profile ground. There are two sun gears, one of which is fixed to the hollow driving shaft, the latter being mounted in needle roller bearings. The second sun gear is fastened to a sleeve which

surrounds the driving shaft, and is normally prevented from rotating by a torque arm. Drive between the sun gears is transmitted by either two or three pairs of planet gears secured to ball-bearing mounted shafts by a patented keying process which ensures uniform distribution of load.

During assembly of the unit, the planet gears are passed over the shafts so that they can mesh freely with the sun gears. The shafts are located, and pre-load is applied to the planet gears by adaptors inserted in the bores in the end-flanges of the pulley, which normally house the bearings. The assembly, which forms, in effect, a mould, is now pre-heated, and keyways provided in the planet gears and shafts are filled with nylon, in liquid form, by a specially-designed injection press. After the nylon has solidified, the adaptors are removed from the pulley, and the bearings are fitted. When the unit is in operation, the slight inherent elasticity of the nylon "keys" ensures that uniform contact pressure is applied between the teeth of the sun and planet gears.

The torque arm is fitted with leaf springs which serve as a safety device and will bend or break when a torque of two to three times that for the rated capacity of the pulley is applied. Release of the sleeve carrying the normally fixed sun gear, as a result of breakage of the leaf spring, automatically disengages the drive to the shaft. Alternatively, a torque arm fitted with a coil spring can be provided. This unit incorporates a pawl which operates a switch to stop the driving motor when a pre-determined torque, up to a maximum of 120 per cent of the nominal rated capacity for the pulley, is transmitted. In the event of failure of these safety devices, shearing of the nylon keys will take place without damage to the gearing when a load of four to five times that for the rated capacity for the pulley is applied.

Other attachments, which are available for mounting on the side of the pulley to form compact assemblies, include mechanical and electromagnetic clutches, and a 2-speed drive unit.



Cut-away view of an Andantex speed reduction pulley for a V-belt drive

STOCKS OF PIG-IRON at steel works, steel foundries, and blast furnaces at the end of July amounted to 1,144,000 tons, as compared with 1,039,000 tons at the end of 1957. Stocks of scrap at steel works and foundries at the end of June totalled 1,175,000 tons, as against 1,207,000 tons at the end of 1957.

New B.M.C. Body Painting Plant

Expansion now taking place within the British Motor Corporation will provide for an increase in production capacity of 30 per cent during the next 12 months. These latest developments will cost £18 million, which is additional to the £22 million that has already been invested in new factories and equipment during the past three years. More than 500,000 B.M.C. vehicles of all types were produced in 1957/58, which is stated to be the highest figure yet achieved by any British or European manufacturer, and export deliveries were 16 per cent greater than in the previous year. It is estimated that nearly 45 per cent of the cars sold in Great Britain were the products of the British Motor Corporation.

An important development at the Cowley works of Morris Motors, Ltd., is a new body painting plant which has been built at a cost of £3 million, and is considered to be one of the most efficiently planned units of its kind yet put into production. The new building has a length of 1,400 ft. and it houses two independent production lines arranged side by side, each of which is capable of handling 26 bodies per hour. Alongside these two lines is a Rotodip conveyerized installation in which the "white" body shells first receive the Bonderizing anti-rust and corrosion preventative treatment. This Rotodip installation, which is just

being brought into operation, will handle 26 bodies per hour, and augments the existing plant at the Cowley works. It has been built by the Carrier Engineering Co., Ltd., and incorporates automatic loading arrangements and various design improvements resulting from the extensive experience of B.M.C. in operating this type of equipment. The Carrier Engineering Co., Ltd., have also been responsible for the construction of an important part of the new paint lines. The layout of the latter, with which this article is principally concerned, is shown in Fig. 2. At the delivery end of the lines, to the right, are provided facilities for carrying out certain finishing operations and for despatching the painted bodies, also for receiving and storing white bodies that are to be treated in the new Rotodip installation.

To conserve space, each paint line is arranged to turn back on itself, and the carrier and the oil-fired stoving ovens are located above the lines on mezzanine floors, as indicated in the layout. Fig. 1 is a view of one of the lines looking towards the starting end, and the U-bend of the conveyor, seen in the foreground of the latter illustration, is indicated at X on the drawing, Fig. 2.

The bodies progress along the line mounted on wheeled trolleys of fabricated steel, which are returned from the finishing to the starting end by




Fig. 1. View of one of the paint lines in the new building




Fig. 2. A diagrammatic layout of the new painting lines at the Cowley works of Morris Motors, Ltd.

way of a train conveyor in an underground passage. A trolley from which a finished body has been removed is seen in Fig. 3, moving down the incline into the passage on its way back to the starting end. One design of trolley serves for all types of bodies handled in the plant, the only adjustment required being for working height. It is the company's intention to provide a cleaning station in the tunnel, and since the trolleys pass through several stoving ovens during the cycle, means will be incorporated for automatically lubricating the wheel bearings.

The bodies delivered from the new and the existing Rotodip installations are loaded by hoist and special sling on to the trolleys, which are then wheeled along guide rails

into engagement with the single-chain floor conveyor of the paint line. After preliminary operations, which include cleaning and the application of an anti-drum compound, the body passes through an infrared heated drying tunnel and a cooling tunnel, into the first section of the filler spray booth. Here, a certain amount of hand spraying is carried out, and filler coating is then completed automatically in the second section by means of U.S.-designed Schweitzer equipment, which is now being built in this country by the Carrier Engineering Co., Ltd.

A view from the entry end of a similar Stoving booth, in this instance for finish painting, is given in Fig. 4, the bodies seen here being for the Austin-Healey Sprite.

Spraying is performed by a total of six guns arranged in two groups of three, each comprising right- and left-hand vertically-traversing guns, and a gantry-mounted gun which moves horizontally above the line. The guns are carried on cam-actuated, pivoted arms whereby they are caused to follow the general contour of the body during the traversing motion. Starting and stopping of the gun traverse and paint flow, as the body enters and leaves the booth, is controlled by photo-electric cell units and light beams.

Stoving of the filler coat is carried out at a temperature of 320 deg. F., and the body is subsequently rubbed down in preparation for applying the sealer, which is sprayed on by hand guns and then stoved



Fig. 3. The trolleys which carry the bodies return to the starting end of the line by way of an underground chain conveyor, as here shown

at a temperature of 300 deg. F. Following a dry scuffing operation, the finishing coat is applied automatically in the booth seen in Fig. 4, to which reference has already been made, and the body is next stoved at a temperature of 275 deg. F. With the latest synthetic finishes that are being employed, no polishing is required after spraying and stoving, and a high degree of durability is provided. In connection with the rubbing down operations, which play an important part in obtaining a high standard of finish, the work is considerably facilitated by the provision of water troughs which are automatically filled, and are heated during cold weather. Where a duo-tone finish is required, the body is suitably masked and the second colour is applied by hand spray guns in a separate booth, as indicated on the layout drawing. This booth is also used for rectifying any bodies which do not conform to the very high standard that is laid down by the inspection department. The finished bodies are unloaded by hoist and special sling from the trolleys, and the latter are pushed along guide rails to the return conveyor seen in Fig. 3.

WATER WASH SYSTEM

All the spray booths are of the water-wash type, and extending transversely across the two paint lines, in a basement, are two 50,000 gal. sludge tanks, one of which serves the filler and sealer spray booths, and the other the finishing booths. A view of one of these tanks is given in Fig. 5. Clean air is circulated through the booth by way

of dispersive filters in the roof, and overspray is drawn by the air flow into a water curtain beneath the grid floor seen in Fig. 4. Water and sludge from the various booths flows to the underground tank in a cascade as seen on the left in Fig. 5, and it is recirculated by 12 submersible, motor-driven pumps arranged at the opposite side (to the right in the figure). Additives in the water cause the sludge to float on the surface, and it is skimmed off every day, by manual means, from an electrically-driven trolley that runs on rails extending the length of the tank. The sludge is collected in a detachable skip on the trolley, which is then lifted by hoist to ground level so that it can be towed away for disposal of the contents.




Fig. 4. One of the Schweitzer automatic spray booths for applying the synthetic finishing coat

Fig. 5. De-sludging of the water from the spray booths is carried out in two underground tanks each having a capacity of 50,000 gal.



Submerged water jet pipes, traversed mechanically, prevent the inlet filters of the pumps becoming clogged with sludge, and water is delivered to the floor of the booth, to form a curtain, through downwardly-projecting jet pipes in compartments in the booth sides. The exhaust air passes upwards through these water jets for cleaning purposes, and is then discharged through drying louvres to atmosphere.

PAINT MIXING AND DISTRIBUTION

Primer and sealer paint is supplied by pipe lines to the spray booths of the two production lines from a mixing room in the basement, and there is a similar but larger installation, housed on the upper floor of a 2-storey building, separate from the main shop, for supplying the synthetic finishing paint. A view of the latter plant is given in

Fig. 6. Here are installed 26 pairs of mixing pans which enable 26 different-coloured paints to be pumped direct to plug-in supply points in the booths. In the pans, the paint is continuously stirred by paddles, and while one pan of a pair is in use, paint of the same colour is being prepared in the other, so that continuous operation can be maintained.

Thinners is fed to the pans in controlled quantities by way of Wayne flowmeters from an outside storage tank, and each pan holds 100 gal. of paint. About 3,000 gal. of paint are used per week and it is delivered by the suppliers in 40-gal. drums which are stored in specially-designed racks on the ground floor. From the racks, the drums are delivered to the mixing pans by hoist and runway. The building is air conditioned, and incorporates a laboratory from which the operating conditions are closely controlled.

When the colour is to be changed in the spray booth, it is only necessary to flush-out the guns and plug in the pipe connection to the selected paint delivery point. This operation can be performed in 23 sec., and to enable it to be carried out while



Fig. 6. View of the mixing room where synthetic finishing paints of 26 different colours are handled




Fig. 7. Centralized electrical control station for the two body painting lines

the bodies are progressing along the line, a double chain conveyor is provided for the finishing booths. The trolley wheels rest on the chain links, as may be seen in Fig. 4, and it is thus possible for the operator to push an incoming body back along the moving chains. In consequence, the change-over can be made before the body interrupts the photo-cell light beams which start the automatic spray guns. The conveyor reverts to single track to carry the trolleys through the stoving oven.

Complete electrical control of the two paint lines is carried out from the centralized station shown in Fig. 7. Here, flow-line diagrams and warning lights on a panel indicate the stopping of any part of the equipment and enable faults to be rapidly located and rectified. Heenan & Froude electromagnetic transmission units are incorporated in the main conveyor drives, which enable the speed to be closely controlled. Particular attention is drawn to the excellent working conditions and cleanliness provided by the layout of the new plant. An extensive space heating system is installed, and the walls of the building are asbestos lined to facilitate temperature control. A high standard of fluorescent lighting is provided throughout. Safety in the paint mixing rooms is ensured by the provision of fire-proof doors and carbon dioxide sprays which are brought into operation by thermostatic control.

In connection with B.M.C. expansion, reference may also be made to a completely new paint shop which is to be built at the Longbridge works of the Austin Motor Co. and to an important exten-

sion of the car assembly building at this plant. The production of replacement engines and gearboxes for B.M.C. cars is now centralized at the original Riley works, Durbar Avenue, Foleshill, Coventry, under the control of Morris Motors, Ltd., Engines Branch, Courthouse Green, Coventry. The plant, which includes five assembly lines transferred from the Austin and Morris

factories, is capable of handling 4,000 engines per week by flow-line methods. All used engines and gearboxes received into the factory are completely stripped and the parts are cleaned and thoroughly inspected before they are delivered into stores, or passed forward for re-machining. On the assembly lines, the methods employed for building and testing conform to those for new engines and gearboxes, and units are periodically dismantled and checked by the inspection department to ensure that the high quality specified is being maintained. It is stated that replacement units can be supplied for most of the Austin and Nuffield vehicles on the roads today.

NEW LEAD ALLOY FOR CHROMIUM PLATING TANK LININGS—British Lead Mills, Ltd., Byron House, 7-9, St. James's Street, London, S.W.1, a member company of the Firth Cleveland Group, announce that, following a "small but increasing number of inexplicable failures in chromium plating tank linings", they have introduced a new alloy for this purpose with the registered trade name Antatac R.1. It is stated that in connection with this development more than 200 different alloys were made up. The most promising of these alloys were subjected to rigorous tests, during which accepted rules for the protection of linings were deliberately broken. Antatac R.1 is now available in the form of sheet for linings, pipe for heating and cooling coils, and anodes. It is being employed in the new plating plant of Vauxhall Motors, Ltd., at Luton.

New Production Equipment


Craven 30-ft. Vertical Boring and Turning Mill

Craven Brothers (Manchester), Ltd., Reddish, Stockport, have recently built the 30-ft. vertical boring and turning mill, here shown, for the Australian State Dockyard, Newcastle, New South Wales. In order to handle the general run of workpieces, extending up to 15 ft. diameter, also to cater for occasional workpieces of 30 ft. maximum diameter, the design is based on a 25-ft. fixed-column mill, with a 22-ft. diameter table, but the two columns are supported on bed wings, and the cross-slide and top beam have been extended to accommodate a maximum diameter of 30 ft. 3 in.

Drive is taken from an 80-h.p. variable-speed reversing motor, through V-belts and a 3-speed gearbox, and a table speed range of 0.25 to 7.5 r.p.m. is provided. Two steel pinions are employed to transmit the final drive to a large-diameter, single-helical steel gear-ring, secured to the underside of

the table. The two pinions are located at the rear of the machine, on radii 90 deg. apart, and are mounted on vertical shafts in the bed. These shafts are driven from the main gearbox through a central distribution box, at the rear of the bed, and spiral bevel gears. Provision is made for setting the pinions so that the total driving load is equally distributed between them. Built in three sections, securely jointed together, the bed is provided with special levelling screws and plates. The table is of similar construction and has eight pairs of T-slots for the attachment of loose jaws. A central cast-iron spindle, of hollow conical form, is secured to the table, and runs in phosphor-bronze bearings which can readily be adjusted vertically to control the running clearance.

The vertical load of the table and workpiece is supported by two flat, concentric tracks, with phosphor-bronze bearing pads, mounted on top of the bed. Both the spindle and tracks are housed in oil baths, and additional pressure oil lubrication is



Craven 30-ft. vertical boring and turning mill for Australia

provided direct to the various bearing faces by two independently-driven pump units with separate oil supply reservoirs.

Electrical interlocks ensure that table cannot be rotated unless the oil is circulating, and pressure gauges and filters are included in the various oil circuits. A coloured light indicates that the lubricating system is working, and if any failure occurs in the pump motors or oil supply system, the main drive motor is stopped automatically. The oil temperatures at eight different positions in the tracks and spindle bearings are indicated successively by a dial on the control desk. If the oil temperature at any position exceeds a predetermined value, an alarm bell rings and warning lights on the control desk are illuminated.

Each cross-slide saddle has a balanced octagonal-section ram, fitted with a forged-steel tool-holder, which is adjusted vertically by means of a central screw. The ram can be swivelled through an angle of 30 deg. on either side of the vertical position, and has a travel of 5 ft. 6 in. Hand adjustment of the ram vertically, or its saddle horizontally, is effected by separate handwheels at the end of the cross-slide, or by a single handwheel and lever-operated selection clutch on the front of the saddle.

Separate gearboxes at the ends of the cross-slide are provided for the feed and rapid power traverse motions for the two saddles, and the 12 rates of horizontal and vertical feed range from 0.007 to 0.376 in. per rev. of the table. Drive to each feed box is taken from a separate motor, which is also used for rapid traverse, and feed changes are effected by levers on the gearboxes.

When the motors are used to power the feed motion, they receive their electrical supply from a generator coupled to the output shaft of the main drive gearbox. In consequence, variations in the table speed cause modifications in the output voltage from the transmitter and corresponding variations in the speed of the feed motors. By this arrangement, a constant rate of feed per revolution is maintained, regardless of any change that may occur in the speed of the table. It is also possible to accelerate one feed motor from rest while the other feed motor is in operation. When the motors are used for the rapid power traverse they are automatically connected to the fixed-voltage A.C. mains supply and run at a constant speed.

A 35 h.p. constant-speed motor on the top tie beam powers the elevating mechanism of the cross-slide, and the latter can be locked to the columns by separate motor-operated clamping units. An electrical interlock ensures that the main motor is not started until the cross-slide is locked. The electrical equipment is controlled from a desk-type panel, which includes a tachometer for indi-

cating the table speeds, and an ammeter. Controls for the main motor and the appropriate feed motor are also incorporated in each saddle, and in two push-button stations, suspended from arms that are pivotally mounted on the tops of the main machine columns.

The variable-speed main drive motor has a three-to-one speed ratio and operates from 220-volt D.C. supply, derived from a constant-speed motor-generator set, powered by the normal A.C. workshop supply mains.

Birfield-Somua Type ZIB Milling Machine

The Somua ZIB milling machine shown in the accompanying Fig. 1 and 2 is now being built in this country by Birfield Tools, Ltd., Bodmin Road, Coventry, under licence from the French firm Saviem L.R.S.

This milling machine incorporates patented design features which are claimed to afford important advantages, in respect of rigidity, as compared with a conventional knee-type machine, and it is stated that more than 3,000 have been built since it was introduced in 1954. Referring to the diagram, Fig. 3, the 47½-by 11½-in. table A moves longitudinally in long guideways in a bridge casting B, which, in turn, is bolted to the machine base, and in this manner a very rigid support is provided.

Below the table guideways in the bridge, which has extensions at the rear, there are transverse dove-




Fig. 1. Birfield-Somua type ZIB milling machine set-up for horizontal milling




Fig. 2. Birfield-Somua milling machine fitted with a universal swivelling spindle head

tail ways C, for the knee D, the latter being fully supported at all positions of its movement. Vertical ways at the rear of the knee accommodate a box-section spindle column E, which houses the gearbox, the latter being driven by a flange-mounted 3-h.p. motor.

A longitudinal travel of 28 in., a cross traverse of 9½ in., and a vertical hand adjustment of 15½ in. are provided. There are nine rates of power feed from ½ to 20 in. per min., and fast traverse at the rate of 80 in. per min., longitudinally and transversely, in addition to hand adjustments by conveniently-placed wheels. The feed and rapid traverse motions are driven by a ½-h.p. motor, which, together with the gearbox, is housed in the left-hand end of the bridge casting. Automatic trip dogs, stated to operate to an accuracy of 0.0004 to 0.0016 in. according to the rate of feed, are fitted, and a backlash eliminator can be incorporated, to enable climb milling to be performed.

Twelve speeds, from 50 to 2,500 r.p.m., in forward and reverse directions, are available for the horizontal

spindle, and a heavy-duty vertical spindle head, with speeds from 40 to 2,000 r.p.m. can be fitted. In addition, there is available an inclinable vertical spindle head, a slotting head and a universal swivelling head, the latter being seen fitted to the machine in Fig. 2. Provision is made for the use of an overarm brace when the horizontal spindle is in use. For production applications, the machine can be equipped for a wide variety of automatic cycles, including starting and stopping of the spindle, and combinations of longitudinal and transverse table movements.

A coolant pump and tank are incorporated in the base casting, together with a chip tray, which can be withdrawn from the front. The machine is also available as the type Z1B-ALU, with feed rates ranging from 24 to 80 in. per min., and a rapid traverse of 120 in. per min., for machining light alloys and plastics.

The Somua Z3 milling machine which is also available is of the same general design. Weighing 2 tons 3 cwt., it has a 63- by 14½-in. table, and a 10-h.p. spindle-drive motor.

In addition, there is a Somua Z44 duplex, bed-type production milling machine, which has a 78- by 16½-in. table and is hydraulically operated.




Fig. 3. Diagram showing the construction of the Somua type Z milling machine

Asquith Horizontal-spindle Milling Machine for Facing the Ends of Girders

A horizontal-spindle, floor-type milling machine recently built by William Asquith, Ltd., Halifax, for facing the ends of fabricated steel girders, is here shown installed in the works of Dawneys, Ltd., Welwyn Garden City, Herts. The box-section girders, which are of considerable length, are supported by cross rails attached to floor-mounted rails provided by Dawneys, Ltd.

The facing operation is performed by a Prolite Futur-Mill (Protolite, Ltd.) face milling cutter fitted with octagonal tungsten carbide blades. This cutter is held in the 5 $\frac{1}{4}$ -in. diameter spindle nose by a drawbolt. Drive to the spindle is taken by V-belts from a 20-h.p. motor, and interrupted cutting, also the removal of weld scale, can be undertaken. Spindle speeds of 655, 760 and 870 r.p.m. are obtained by interchangeable pulleys, and the motor can be moved on the spindle slide by screws for adjusting the tension of the V-belts. The spindle quill can be moved axially through a distance of 3 in., by means of a crank, and a micrometer dial is provided to facilitate setting the depth of cut. Upon completion of the setting operation, the spindle quill is secured by a clamp.

The substantial spindle slide is counterbalanced by a weight housed in the box-section, internally-

ribbed, column, and has a travel of 6 ft. on broad guideways. Taper gibs and keep strips, also wipers for the column ways, are incorporated in the slide. The column base has a horizontal travel of 10 ft. on the bedways, and telescopic guards are fitted to prevent the ingress of swarf to the guiding surfaces. The bedways are automatically lubricated by a motor-driven pump, which has provision for adjusting the rate of delivery of the oil. Horizontal and vertical traverses are derived from separate 3-h.p. 2-speed motors, through rotating nuts and fixed screws, which are held in tension when the column base and the spindle slide are being traversed in either direction. Feeds of 30 and 60 in. per min. are usually employed for both the column base and spindle slide, but interchangeable pairs of pulleys are supplied which enable rates of 40 and 80 in. per min. to be obtained.

The various motions of the machine are controlled by push-buttons mounted on a swivel pendant unit, and an injection braking system is provided for the spindle drive and feed motors so that they can be "inched" to facilitate setting. A wattmeter is fitted to indicate the load on the spindle drive motor when cutting is actually in progress.


Weighing approximately 9 $\frac{1}{2}$ tons, the machine occupies a floor space of 20 ft. 6 in. by 5 ft., and has an overall height of 13 ft. 9 in. Machines built by William Asquith, Ltd., are sold by Drummond-Asquith (Sales), Ltd., King Edward House, New Street, Birmingham, 2.

New Small Wheel Attachment for the Wickman Optical Profile Grinder


In the figure is shown a high-speed spindle attachment recently introduced by Wickman, Ltd., Tile Hill, Coventry, for use with their optical profile grinder.

Available with different driving motors for operation on single-phase supplies of 110 and 220 volts, this attachment provides a spindle speed of 35,000 r.p.m., under load, and takes wheels from $\frac{1}{4}$ to $\frac{3}{4}$ in. diameter, with $\frac{1}{8}$ -in. diameter shanks. It is intended for profile grinding, for example, small punches for press tools and core pins for pre-forming tungsten carbide drawing dies, on which small run-out radii are required. By dressing the wheel to a predetermined diameter, the run-out radius on a core pin, which is reproduced on the entry side of the drawing die during the subsequent forming operation, can be accurately ground simultaneously with the profile grinding of the pin.

The attachment can be readily mounted in place



Asquith horizontal-spindle, floor-type milling machine for facing operations on the ends of fabricated steel girders



Close-up view of the Wickman optical profile grinder here shown fitted with the new small wheel attachment

of the standard spindle unit, and there is a special tube for connection to the dust collecting system provided on the machine. When the attachment is mounted on the machine, as shown, the grinding wheel occupies the same position in relation to the work as the larger diameter wheel usually employed.

Seneca Falls Precision Boring Machine


The type NP precision production boring machine, here shown, has been added to the range built by the Seneca Falls Machine Co., Seneca Falls, N.Y., U.S.A. Available with single or twin spindles, of the company's own design, the arrangement of the headstock bridge is such that other makes of standardized boring spindles can be fitted, if required. When the company's spindles are employed, a choice of three different designs is available, with maximum spindle speeds of 2,500, 5,000, and 10,000 r.p.m.

On a 2-spindle machine, the spindles can be driven by a single motor, or by separate 3-h.p. motors, where different speeds are required. For either system, the drive is transmitted by V-belts, and the spindles run in high-precision pre-loaded ball bearings.

The table has a maximum traverse of 5 in., and is carried on vee and flat slideways, which are completely covered at all times. A drum-type cam is employed to traverse the table to ensure a

positive feed motion and a high surface finish on the workpiece. A patented quick-change mechanism is incorporated for varying the length of the table stroke, and the rapid traverse and feed cycles, within the range quoted, without changing the cam. It is stated that, with this mechanism, the average time required to make an alteration is less than 30 min. The table measures 9% by 19 in., and has a rapid traverse rate of 370 in. per min., the range of boring feeds varying from 0.0005 to 0.054 in. per min.

Boring can be carried out either with the work mounted on the spindles and the tools on the table, or, when it is impracticable to rotate the part, by the reverse procedure. Standard cross-slides, arranged for both hand or



Seneca Falls precision production boring machine

power-operation, are also available. It is stated that boring can be carried out to limits of accuracy that are well within those specified by the aircraft, instrument, and motor car industries.

Gaston E. Marbaix, Ltd., Devonshire House, Vicarage Crescent, Battersea, London, S.W.11, are the agents in this country for the Seneca Falls Machine Co.

Genelin Plate Bending Rolls

John S. Young & Co., Ltd., Maryville Avenue, Giffnock, Glasgow, are the sole agents for the recently-introduced Genelin plate bending rolls shown in the figure. The subject of a patent application, the machine has a capacity for bending mild steel plates from 39 in. wide by $\frac{1}{4}$ in. thick, up to 12 in. wide by $\frac{1}{2}$ in. thick, for example. It incorporates 4-in. diameter lower bending rolls, and a 4 $\frac{1}{4}$ -in. diameter top roll, all of which run in spherical roller bearings.

The entire drive unit is housed in the base, and the shape of the side members of the fabricated steel frame is such that the rolls are positioned at the rear of the centre line, and with this arrangement access to the work can readily be obtained from either side.

The distance from the centre line of the lower rolls to the shop floor is 37 $\frac{1}{2}$ in., and to the top surface of the base, 22 $\frac{1}{2}$ in.

Adjustment of the top roll is made by separate screws at both ends, and scales and pointers are fitted to facilitate setting for parallelism. The bearing housing at either end of the top roll can



Genelin plate bending rolls


be readily swung clear to permit of unloading closed rings and cylinders.

Drive is taken from a 5-h.p. motor, directly coupled to a 3 $\frac{1}{2}$ -h.p. Churchill-Sturm hydraulic unit, thence to the lower rolls by a duplex roller chain and gears. Reversible, steplessly-variable work speeds, ranging from 0 to 100 ft. per min., are thus provided, adjustment being made by levers at both ends of the frame. The lower rolls and their bearings and driving gears can be readily removed from the frame as a single unit.

The machine weighs 19 cwt., and occupies a floor space of 56 $\frac{1}{2}$ by 26 $\frac{1}{2}$ in.

Burgmaster Turret Drilling Machine with Automatic Indexing

To meet the need for a sensitive machine for use in the production of small delicate parts to close limits of accuracy, the bench-type turret drill shown has been developed by the Burgmaster Corporation, Small Tool Division of Burg Tool Manufacturing Co., Gardena, California, U.S.A. The automatically-indexing turret enables a variety of operations such as drilling, tapping, reaming, counterboring and spot facing to be carried out at one set-up.



Burgmaster turret drilling machine with automatic indexing

Drive to the spindle is transmitted by 2-step pulleys and a belt, and there are 12 spindle speeds, comprising a high range from 650 to 6,200 r.p.m., and a medium range from 350 to 3,300 r.p.m. The overall dimensions of the machine are 24 in. high by 17 in. wide by 20 in. deep, and the working surface of the table measures 8 by 12 in. A maximum distance of 7 $\frac{1}{4}$ in. is obtainable between the end of the chuck and the table, and the spindle has a maximum traverse of 2 $\frac{1}{2}$ in. The distance from the centre of the chuck to the column is 5 $\frac{1}{4}$ in.

A number of accessories is available for use with this machine, including drill chucks, tapping heads, spindle extensions, a sub-plate, and a cabinet-type mounting complete with a coolant pump.

Verson 1,000-ton Press Brake

The large hydraulic press brake shown in the accompanying figure has been built by the Verson All-steel Press Co., Chicago, Ill., U.S.A., for Hall,



Verson 1,000-ton press brake

Longmore & Co., Ltd., Transvaal, South Africa, and will be employed primarily for the fabrication of steel pipe up to 36 in. diameter by 30 ft. long, for pipeline installations. Of "A"-frame construc-

tion, the press is rated at 1,000 tons, measures 31 ft. between the housings, and is stated to be the largest machine of this type yet built.


Advance and pressing speeds of 41½ in. per min., and a return speed of 124½ in. per min., are provided, and the press has a ram stroke of 34 in. It was supplied complete with the necessary tooling, which was built by the company, and an automatic levelling control is incorporated. The machine weighs approximately 200 (short) tons, and occupies a floor space of 7 ft. 10 in. by 39 ft. 4 in.

Paul Granby & Co., Ltd., 39 Victoria Street, London, S.W.1, are the sole selling agents in this country for Verson machines.

Crowthorn Heavy-duty Lathe for Facing Crankcases

Crowthorn Engineering Co., Ltd., Atlas Works, Reddish, Stockport, have recently supplied the 31-in. swing, heavy-duty lathe shown in the illustration, for facing, simultaneously, both ends of crankcases for Kelvin marine engines.

Two saddles are mounted on the 24-in. wide bed, and are fitted with top slides of opposite hands, which carry 4-way toolposts. The right-hand assembly carries a bracket for supporting the outer end of a mandrel. Workpieces of 21½ in. maximum diameter can be swung over the saddle covers. Twelve spindle speeds, ranging from 7 to 300 r.p.m., are obtainable, the drive to the headstock being taken




Crowthorn 31-in. swing, heavy-duty lathe for facing both ends of crankcases for Kelvin marine engines

from a 20-h.p. motor. The spindle is bored $\frac{4}{16}$ -in. diameter and is mounted in Timken precision taper roller bearings.

The lathe occupies a floor space of 16 ft. 3 in. by 5 ft. 6 in., and weighs approximately $8\frac{1}{2}$ tons.

Rotaform Grinding Fixture

The Rotaform fixture shown in the accompanying illustration has recently been introduced by



Rotaform grinding fixture for punches

Lennie & Thorn, Ltd., Western Road, Bracknell, Berks. The subject of patent application, the fixture is primarily designed to facilitate the grinding of formed press-tool punches from cylindrical blanks, although it can also be employed for light machining operations on copper, for example, as required for the production of electrodes for spark machining. In addition, finished components can be set up in the fixture for inspection.

Interchangeable collets for gripping punch shanks from $\frac{1}{8}$ to $\frac{1}{2}$ in. diameter can be supplied for mounting in the compound workhead, the main and auxiliary slides of which may be moved through distances of $\frac{1}{2}$ and $\frac{3}{4}$ in., respectively, and locked. Setting is carried out with slip gauges, and accuracy of 0.0002 in. is claimed. The punch can thus be adjusted radially, in two directions at right angles, in relation to the axis of the spindle that passes through the body of the fixture. Of hardened steel,


the spindle can be smoothly rotated through a full turn by means of substantial knob at the rear end, and it can be set for angle, within 5 min. of arc, by reference to a large-diameter vernier scale. Adjustable stops permit the angular movement to be restricted for grinding arcs of different lengths. A wheel dressing attachment is available, and enables radii from $1\frac{1}{4}$ in. convex to $1\frac{1}{2}$ in. concave to be generated on surface grinding wheels.

With the combination of rotary movement and radial adjustments described, a wide variety of symmetrical and irregularly-shaped sections can be quickly and accurately produced on a surface grinding machine, in the required relationship to the shank of the punch, without re-setting the work in the collet.

Bronx 5-roll Plate Levelling Machine

Bronx Engineering Co., Ltd., Lye, near Stourbridge, have recently built the 5-roll plate levelling machine shown in the figure. It has upper and lower rolls of $12\frac{1}{2}$ in. diameter, and will handle mild steel plates up to 8 ft. wide by $\frac{3}{4}$ in. thick at a speed of 16 ft. per min.

Drive to the lower rolls is taken from a 50-h.p. reversing motor through a worm gear box and totally-enclosed reduction gearing. The upper rolls can be adjusted simultaneously, by hand, or by a $7\frac{1}{2}$ -h.p. reversing motor. Separate handwheels are provided for independent adjustment of the outer rolls, and roll setting is facilitated by large-diameter dial indicators, mounted on one of the substantial fabricated steel columns.



Bronx 5-roll Plate Levelling Machine

Open Days at the A.I.D. Laboratories

With the collaboration of the Inspectorate of Electrical and Mechanical Equipment, and the Chemical Inspectorate, the Aeronautical Inspection Directorate held Open Days at the Harefield Laboratories, for the first time, on October 8 and 9. The laboratories of the A.I.D. were founded in 1914, and originally occupied a small building at Farnborough. One year later, additional laboratories were opened at Sheffield and London, specifically for the testing of metallic and non-metallic materials. As the work of the Directorate widened to cover the fields of gauge and electrical equipment testing, it was decided to centralize the separate laboratories. Accordingly, in 1919, activities were transferred to Kidbrooke, where they remained until 1936, when the work of the organization was expanded still further, to include metrology, metallurgy, and radiology. This expansion necessitated a move to premises at the Royal Airship Works, Cardington, where the Directorate remained until the present modern laboratories at Harefield were ready for occupation in 1940.

The work of the A.I.D. at Harefield is divided into six sections, concerned with metallurgy, metrology, non-destructive testing, guided weapons, textiles, and apprentice training. In addition, there are physics and radio sections of the

I.E.M.E., and a section of the Chemical Inspectorate. The functions of the establishment are three-fold, namely, to ensure the maintenance of the high quality of supplies by the application of precision measuring equipment and the development of new inspection techniques; to collaborate with industry on methods for precision testing, the investigation of failures, and the improvement of inspection techniques in general; and to act as a training centre for A.I.D. staff by providing regular courses of instruction. Considerable importance is attached to the degree of collaboration which can be achieved with industry, and whilst, on average, 200 representatives from firms visit the laboratories annually to discuss specific problems, it is felt that this figure could be usefully increased, and it is hoped that the inauguration of Open Days will indirectly assist in the attainment of this objective.

WALL THICKNESS MEASUREMENT

An example of the work of the metrology department in connection with the development of new measuring techniques is afforded by the wall thickness measuring equipment shown in Fig. 1 and 2. Although the equipment is here shown set up for

measuring the wall thickness of a fairly large diameter copper tube, the original problem was to develop a means of taking such measurements on a component which had a fairly small non-circular bore extending through its entire length of 27 ft. The equipment comprises a channel-section steel beam on which is mounted, at one end, a standard alignment telescope and an optical micrometer, as indicated at A. Immediately in front of the telescope, there is a swivel mounting B for one end of a 1½-in. diameter copper tube, the other end of which serves to hold the




Fig. 1. Equipment developed by the Metrology Department of the A.I.D. laboratories at Harefield for measuring the wall thickness of hollow components with circular or non-circular cross sections




Fig. 2. Close-up view of the stylus head of the wall-thickness measuring equipment seen in Fig. 1. The stylus is a standard ball bearing with the outer race ground to a spherical form

"stylus" and a target graticule. The stylus is actually a standard ball bearing, the outer race of which has been spherically-ground to provide for point contact with the surface of the workpiece being measured. A close-up view of the stylus and its carrier tube is shown in Fig. 2, where the ground cylindrical anvil which serves as the fixed measuring datum can be seen at C. The centre line of this anvil is arranged exactly beneath the centre of the ball bearing sphere. A light source is provided to illuminate the target in the stylus head, power for this lamp being supplied by way of the cable at the left.

To measure a workpiece, the optical micrometer is first set to zero with the stylus head resting on a stack of slip gauges equivalent to the nominal wall thickness of the part, in the manner shown in Fig. 2, where the slip gauge is indicated at D. Next, the slip gauge is removed, the stylus head is raised, and the component is placed in position, with the outer end resting on a pair of free-running rollers and the opposite end in con-

tact with the anvil C. The stylus is then lowered into contact with the bore of the part, and any variation in wall-thickness of the latter from the nominal has the effect of raising or lowering the stylus from the datum position. Since the target graticule is integral and coaxial with the stylus head, its horizontal hair line is displaced above or below the zero mark of the alignment telescope, and the amount of such movement can be read directly by the inspector with the aid of the optical micrometer.

A series of readings can be taken along the workpiece by moving it lengthwise towards the telescope, and when the outer end has passed beyond the free-running rollers, the leading end is supported on the ground bar indicated at E, Fig. 1.

Immediately behind the stylus head, there is a U-shaped pivoted bracket, seen at F in Fig. 2, which has a free-running roller mounted at the end of each leg. To avoid a rubbing contact between the stylus and the workpiece each time the latter is traversed forward for a fresh reading, this bracket can be pulled into the vertical position by means of a thin-gauge wire attached to the top. As a result the rollers make contact with the workpiece and the stylus head is lifted clear. When readings have been taken along the entire length of the work, the latter can be rotated through any required angle, and the procedure repeated.




Fig. 3. A small dividing head which has been designed and built by the A.I.D. for checking the angular errors of electrical synchros for aircraft and guided missiles

DIVIDING HEAD FOR TESTING SYNCHROS

With the increasing use of synchros for transmitting information regarding the angular positions of components in aircraft and missiles, means have had to be found for checking the angular errors which are inherent in the synchro itself, that is, the amounts by which the rotor shaft positions differ from the true electrical positions. For this purpose, the A.I.D. has designed and built the small dividing head shown in Fig. 3, with which the body portion of the synchro can be set to the required angle, relative to the datum, within 15 sec. of arc, and any positional error of the rotor shaft measured directly by micrometer.

The body portion of the synchro is held in the freely-rotating member G, so that the rotor shaft projects, as at H. At the lower end of the member G there is an annular track which contains 72 closely-packed $\frac{1}{8}$ -in. diameter rollers. These rollers serve, in effect, as index notches, and the peripheries of any two can be engaged by a ball-ended plunger which is attached to an arcuate adjustable slide on the base of the instrument. When a synchro is received from the maker, it has a small line marked on the end face of the rotor and a similar line on the body portion, and when these two lines are coincident the mechanical and electrical positions of the unit are approximately at zero. With the synchro aligned in this manner, the arm K is clamped to the rotor shaft, and its outer end is introduced between the anvil of the micrometer L and the spring-loaded plunger M, the micrometer being set to zero or some convenient figure.

Current is now supplied to the windings of the synchro, and the arcuate slide carrying the indexing stylus is adjusted to rotate the member G until a null reading is obtained on an associated instrument. The arm K is, of course, held stationary during this movement by the micrometer and the plunger M, with the result that the body of the synchro and the rotor shaft are now truly aligned. Next, the member G is indexed through 5 deg., the distance between the centres of two rollers. The anvil of the micrometer is then retracted, and the plunger M rotates the arm K, and, consequently, the rotor of the synchro, while the body portion of the latter remains stationary. This adjustment is continued until a null reading is again obtained on the associated electrical instrument. The difference in the micrometer readings is noted, and since the length of the arm K is such that 0.001 in. movement of the micrometer anvil represents 1 min. of arc, this linear adjustment can readily be converted into angular movement. The maximum error of angular position specified for

these synchro units is approximately 4 min. of arc.

A branch of the Ministry of Supply student apprentice training scheme has been in operation at Harefield since 1953, the annual intake of 10 students being recruited through the Civil Service Commission. The training occupies five years, and starts with two years' instruction in the workshops. Laboratory training is given in the third and fourth years, and the fifth year is spent at an aircraft firm, to gain industrial and production experience. A small display of some of the tools and equipment made by the students during the course of their training was on view during the Open Days.

Coming Events

NORTH EAST COAST INSTITUTION OF ENGINEERS AND SHIPBUILDERS. October 31, at 6.15 p.m., in the Lecture Theatre of the Literary and Philosophical Society, Newcastle-upon-Tyne; Andrew Laing Lecture on "Nuclear Power for the Propulsion of Commercial Shipping," by Sir John Cockcroft, O.M., K.C.B., C.B.E., F.R.S.

THE INSTITUTE OF METAL FINISHING. *Sheffield and North-East Branch.* October 31, at 7 p.m., at the Grand Hotel (Fitzwilliam Room), Sheffield; lecture on "Recent Developments in Polishing Techniques," by J. H. Bryan.

INCORPORATED PLANT ENGINEERS. *South Wales Branch.* October 28, at 7.30 p.m., at the South Wales Engineers' Institute, Park Place, Cardiff; lecture on "The Clean Air Act and Effluents," by A. S. Minton. *Birmingham Branch.* October 31, at 7.30 p.m., at the Imperial Hotel, Temple Street, Birmingham; lecture on "The Clean Air Act."

INSTITUTION OF ELECTRICAL ENGINEERS. *Southern Centre.* October 31, at 6.30 p.m., at the South Dorset Technical College, Weymouth; paper on "Three Weeks in the U.S.S.R.," by Sir Josiah Eccles, D.Sc. *London Measurement and Control Section.* October 28, at 5.30 p.m., at the Institution, Savoy Place, W.C.2; discussion on "Electronic Control of Machine Tools," opened by D. T. N. Williamson.

INSTITUTION OF PRODUCTION ENGINEERS. *Manchester Section.* October 27, at 7.15 p.m., at the Manchester College of Science and Technology, Sackville Street, Manchester; lecture on "Zeta," by J. Blears, B.Sc.

INSTITUTION OF MECHANICAL ENGINEERS. October 31, at 6 p.m., at the Institution, 1 Birdcage Walk, London, S.W.1; papers on "Estimation of Upper Bound Loads for Extrusion and Coining Operations," by W. Johnson, and "Theoretical Analysis of the Bending of Wide Plates of an Aluminium Alloy in the Plastic Range," by J. M. Alexander. *London Lubrication Group.* October 29, at 6 p.m., at the Institution, 1 Birdcage Walk, S.W.1; discussion on "Can Automotive-type Bearings be Applied More Generally in Engineering?" *Yorkshire Branch.* October 27, at 7 p.m., at the Institute of Technology, Bradford; paper on "Turning with Ceramic and Sintered Oxide Tools," by R. C. Brewer.

Churchill Gear Machines Link-line for Cluster Gears

Churchill Gear Machines, Ltd., recently demonstrated, at their Blaydon, Co. Durham, works, a 175-ft. long fully-automatic machine line for producing gearbox layshaft cluster gears, which is stated to be the most advanced unit of its type yet produced in Europe. Destined for the British Motor Corporation, this line represents a notable achievement by the company, who have already built in-line arrangements of Rigidhobbers incorporating fully-automatic loading equipment, as described in *MACHINERY*, 90/269—1/2/57.

A view from the starting end of the line is given in Fig. 1. Operations on the turned cluster-gear blanks start with hobbing the fourth-, third-, and first-speed gears on a line of five Churchill Mk.IV Rigidhobbers, and after the work has been washed and gauged, the second-speed gear is cut on three Fellows-England type 7125A gear shapers built by Alfred Herbert, Ltd. Washing and gauging follows, and the parts then pass to three Churchill-built machines which chamfer the teeth of the second-, third-, and fourth-speed gears. Two





Fig. 1. View from the starting end of the Churchill fully-automatic machine line for producing gearbox cluster gears

machines, also built by the company, perform a rounding operation on the teeth of the first-speed gear at the next stage, after which the work passes through brushing and washing units to a line of

four Churchill Red Ring G.C.U. gear shaving machines, which finish all the teeth. The loading and unloading equipment installed between two of these machines is shown in Fig. 2. After shaving, the cluster gears are thoroughly washed in preparation for gauging the teeth, and finally the outside diameters of the teeth of the three

Fig. 2. Work-handling equipment between two of the Churchill Red Ring gear shaving machines

helical gears on the cluster are plunge-ground on a Newall LA machine. These ground diameters provide locations during the subsequent heat treatment operation.

In all, there are 26 units in the line, and although six different types of machine tools are employed, together with washing and gauging stations, the

automatic work handling throughout the line is achieved by the use of only two types of automatic loader, and two types of conveyor for the transport of the components from one machine to another.

Further details of this noteworthy installation will be published shortly in **MACHINERY**.

Grinding Machine Demonstration

Examples of grinding machines built by the German firms Wotan, Elb, and Schmaltz, for whom Soag Machine Tools, Ltd., Juxon Street, Lambeth, London, S.E.11, are selling agents in this country, were demonstrated recently at the company's showroom at Hester Road, Battersea, London, S.W.11.


A Wotan type RJ 134/8G hydraulic internal grinder, which was shown in operation, will swing a maximum diameter of 24 in., and has a capacity for grinding bores up to 20 in. diameter to a maximum depth of 20 in. The table which carries the wheel-head has a maximum travel of 32 in., and the steplessly-variable traversing speeds available range up to 26 ft. per min. Cross feed is applied to the wheel-head hydraulically at the left-hand end of the table travel, and shortly before the required bore size is reached, there is an automatic change to finishing feed steps of 0.0001 in.

on diameter. The work-head can be swivelled for grinding tapers up to 50 deg., and has a cross adjustment of 12 in. to the rear and 6 in. to the front of the normal position. This arrangement enables the work to be rapidly re-set when a stepped bore is being ground. Face and external grinding, in addition to parallel and taper bore grinding, can be carried out at a single setting of the work, without the need for special equipment. If required, however, a face grinding attachment may be mounted on the work-head. A full description of the machine was published in **MACHINERY**, 88/1134—22/6/56.

Wotan internal grinders are of unit construction, and can be supplied in different forms for handling a variety of workpieces. A good example of the type of machine which can be provided for a particular requirement was afforded by a type RJ 134/13L internal grinder for handling long workpieces such as headstock spindles for lathes. On this machine the parallel and taper bore, and the face and external diameter at the flanged nose end of the spindle, can be ground at a single setting of the work.

The machine is of basically similar design to the type RJ 134/8G, but the work-head is mounted on a swivel table, which, in turn, is carried by a bed extension piece, supported at the left-hand end by a column. Bores can be ground for a maximum depth of 32 in., and distances up to 110 in. are obtainable between the nose ends of the work and grinding spindles.

The range of Elb hydraulic surface grinders was represented by the type SW 6VA 24- by 12-in. machine, and the type SW 10VA, shown in the figure, which has a grinding capacity of 40 by 12 in. A maximum distance of 21½ in. is obtainable between the spindle axis and the work table. This range, it may be noted, has recently been extended to include four new



Elb type SW 10 VA hydraulic surface grinder recently demonstrated in the showroom of Soag Machine Tools, Ltd.

sizes with grinding capacities from 24 by 20 in. to 79 by 30 in.

In an article published in *MACHINERY*, 91/1031—1/11/57, in connection with the Hanover Exhibition, reference was made to the principal design features of the Elb machines, and the wide range of equipment which can be supplied. These items include the Forster automatic electronic sizing equipment (which was fitted to the type SW 10VA machine shown at the demonstration), an optical projector for profile grinding, a closed-circuit television system for use when grinding radio-active materials, for instance, a stylus-controlled copy-grinding unit, a wheel-head for slideway grinding, and wheel crushing attachments for mounting on the wheel-head and the work table.

It may be recalled that on the Elb machines the table traverses in the longitudinal direction only, and cross feed is applied to the wheel-head column, which moves on guideways at the rear of the bed. The wheel spindle runs in plain, paraffin-lubricated, bearings, and is usually driven direct, at speeds of 1,400 and 2,800 r.p.m., by a 2-h.p. pole changing motor. Built-in reduction gearing can be brought into use to provide the necessary slow spindle speed for wheel crushing. If required, a Ward-Leonard drive system can be supplied, to give steplessly-variable spindle speeds.

The Schmaltz rotary table surface grinder, which was shown in operation, is available in four sizes with tables of 15%, 19%, 23%, and 27½ in. diameter. Workpieces up to 4½ in. thick can be ground on the two smaller machines, and up to 6½ in. thick on the larger sizes, and the table speeds can be varied steplessly from 22 to 28 r.p.m., and from 12 to 60 r.p.m. Vertical feed can be applied to the table either by hand or automatically. The ram-type wheel-head is traversed on guideways at the top of the column, at a maximum speed of 10 ft. per min., and can be tilted through angles up to 2 deg., in each direction.

New Mond Nickel Films

In the year 1932, news was first received from Japan of the discovery of a new series of permanent magnet alloys in which the principal elements were nickel, iron, and aluminium. These materials were reported to possess properties far in advance of those obtainable with the cobalt steels, which, up to that date, were the best permanent-magnet materials available. Subsequent development work was carried out in various countries, including Britain and the U.S.A., and further improvements, resulting from the inclusion of cobalt, led to the

introduction of the class of alloys generally known as Alnico. It was then discovered, in 1938, that still better properties could be obtained by allowing the material to cool from a high temperature in a magnetic field. This discovery led to the production of Alcomax and Hycomax alloys, and further advances have since resulted from the use of niobium, and the adoption of casting techniques whereby columnar crystals, orientated in the preferred axis of magnetization, are obtained.

The magnetic properties of the nickel-iron alloys, and particularly stability and strength, are the subject of a new colour film, with a running time of 21 min., which has been produced by the Mond Nickel Co., Ltd., Thames House, Millbank, London, S.W.1, and is entitled "Nickel Alloy Permanent Magnets."

First, the well-known properties of magnets are reviewed, and the striking increase in the power of the newer magnet materials is explained. The high stability of magnets containing nickel is demonstrated by tests in which an Alcomax magnet is subjected to extreme conditions of heat, cold, and vibration. Subsequent sections are concerned with the manufacture of magnets; some industrial applications, for example, in chucks for lathes and grinders; and the use of magnets in an automatic train control system, in magnetron oscillators for aircraft radar equipment, and in the rotors of electric speedometers.

"Spheroidal Graphite Cast Iron" is the title of another recently-issued Mond Nickel colour film. This film represents a revision of the first on the subject, which was introduced by the company some five years ago, and it runs for 28 min.

Opening with a brief reference to the advantages and limitations of the ordinary flake graphite and malleable cast irons, the film then shows how, with the transformation of the graphite from flake to spheroidal form, iron can be caused to assume some of the properties of steel yet still retain its castability. The ductility of the material in the annealed state is demonstrated by tests, and attention is also drawn to the good machining qualities, and the extent of the field of applications.

Both films are obtainable free of charge, on loan, in the 16-mm. size, on application to the publicity department of the Mond Nickel Co., Ltd.

STEEL PRODUCTION in the U.S.A. during the first seven months of this year averaged 5,628,000 tons per month, as compared with 8,387,000 tons for the full year 1957. For Western Germany the corresponding figures were 1,933,000 (eight-month average) and 2,010,000, and for the U.K., 1,663,000 (eight months) and 1,808,000 tons.

News of the Industry

Glasgow and District

HUGH SMITH & Co. (POSSIL), LTD., Glasgow, are making good progress with their building extension programme, and we noted that the steel framework has now been erected for the third and final stage. Orders are in hand for a variety of work, including plate bending rolls, plate edge planing machines, hydraulic beam bending machines, combined flanging presses and bending rolls, gap-type flanging presses and cold frame bending machines, in a wide range of sizes, for both the home and Continental markets. Outstanding among equipment recently ordered are a 45-ft. by 2-in. plate edge planer equipped with rotary shears for $\frac{3}{4}$ in. thick plates, for the Rotterdam Dry Dock Co., Ltd., Holland; two 2,000-ton combined flanging presses and bending rolls for plates up to 42 ft. 6 in. long, one for Swan, Hunter & Wigham Richardson, Ltd., Wallsend, and the other for a Danish shipyard; and a cold frame bending machine for a Sunderland shipyard, for dealing with welded-type ships' frames.

A. P. NEWALL & Co., LTD., Glasgow, are engaged in the production of their various types of high-stress- and high-temperature-resisting steel bolts, screws, studs and nuts, also high-tensile steel structural bolts. It is claimed that uniform loading can be achieved in structural engineering work by the use of Newall Torshear structural bolts in conjunction with a specially-designed pneumatic spanner, made by North Bar Tool Co., Ltd., Banbury, Oxon.

JOHN S. YOUNG & Co., LTD., Giffnock, Glasgow, report a reasonably good demand for the various machine tools and cutting tools, including Stag Major tools, for which they are selling agents. This firm was the main contractor for the equipment recently required for the Reid-Kerr trade college in Paisley, and is the sole agent for the new Genelin hydraulically-driven bending rolls to which we hope to make further reference shortly. The new fabrication shop, where parts stillages, industrial trucks, and mechanical handling equipment are being produced, is now in full use, and extensions are contemplated.

W. CROCKATT & SONS, LTD., Glasgow, are doing a steady business in all types of gear-cutting, and the latest additions to plant in the department are a Sunderland No. 16 spur and spiral gear planing

machine with double-helical attachment and a Zuffenhausen MS12 worm milling machine. Other activities at these works include the production of electric salinometers, valve reseaters, feed water filters, and floor polishing equipment.

CROW, HAMILTON & Co., LTD., Glasgow, are mainly employed on orders for bar and tube reeling and straightening machines of various capacities, and on special-purpose machinery. Locomotive boiler-tube de-scaling machines are also produced at these works, some of which have been supplied to India.

DEMPSTER, MOORE & Co., LTD., Bonnybridge, are steadily occupied with the production of standard machine tools mainly required for installation on board ship. These machines include lathes from 7½- to 9½-in. centres, on beds up to 12 ft. long, vertical drilling machines of 1½ in. diameter capacity, and 12- and 14-in. double-wheel tool grinding machines. We noted a special horizontal roll drilling machine in hand, equipped with two saddles, to which we hope to make further reference at a later date.

THE REID GEAR Co., LTD., Linwood, Paisley, have various sizes of spur, bevel, worm and double-helical gears in progress, some of which are required for colliery, haulage and conveyor work. Among other destinations for the firm's gearing may be mentioned the Scottish hydro-electric schemes, turbine and pumping plants, steelworks, and machine tool works. In addition, activities include the production of both standard and special gearboxes. We may note that some capacity is available in the gear grinding department.

THOMAS WHITE & SONS, LTD., Paisley, have a variety of both standard and special woodworking machinery in course of production for home and overseas customers. Steady employment is maintained in the department producing jigs, fixtures, press tools and gauges, and special multi-point gauging equipment. Other work in hand includes shear blade surface grinding machines, which were formerly built by Luke & Spencer, Ltd., Broadheath, Manchester, and were described in MACHINERY, 93/383—13/8/58.

C. & G. OLDFIELD, LTD., 15 Abercorn Street, Paisley, are experiencing a steady demand for the products of the various machine tool makers they represent. A good selection of new and used

machine tools and presses is available for inspection on the premises, which formerly housed an electricity sub-power station. The overhead electric travelling cranes have been retained to facilitate handling the machinery.

ABBOT ENGINEERING CO., LTD., Paisley, report that orders for spur, bevel, worm and double-helical gear-cutting are maintained at about the recent level. A good proportion of the firm's output is destined for local crane-builders and other industrial undertakings.

A. & W. SMITH & CO., LTD., Glasgow, sugar factory and refinery engineers, whose milling machinery has been supplied to all parts of the world, are at present extending their works and augmenting plant, and new office accommodation has recently been occupied. The firm's subsidiaries, R. G. Ross & Son, Ltd., and Foundry Plant Machinery, Ltd., are occupied, respectively, with the production of electro-pneumatic, steam and compressed air forging hammers of various capacities, and sand-slinging equipment for foundry use.

B. ARTHUR HEMS, LTD., Glasgow, inform us that business in machine tools and small tools during recent weeks has shown signs of expansion. Extension

sive stocks of a wide range of small tools are maintained, to ensure prompt service.

R. & J. DICK, LTD., Glasgow, are experiencing a steady flow of orders, on both home and export account, for flat and V-type belts. Among the regular lines we may note Balata belts, Dixylon Suplex plastics transmission belts, Dickrope Plus V-belts, and link V-beltting.

H. B.

Ultrasonic Welding

(Continued from page 919)

sheet as employed in the fabrication of strainers. The material has a pattern of 0.006-in. diameter holes, and in preparation for welding, the holes in two pieces are lined up by means of fine wires. In the weld area, a good bond is obtained in the material between the holes, and the latter remain unobstructed.

An aluminium heat exchanger incorporates a flat, 0.072-in. thick sheet, and a corrugated sheet of 0.006-in. thick material. The two are joined by continuous ultrasonic welds at the bottoms of the corrugations, and it is stated that, in these conditions, welding speeds up to 25 ft. per min. are possible. Ultrasonic welding has also proved effective for the fabrication of "waffle-type" sandwich structures, because it enables the "waffle" filler to be bonded to inner and outer skins with weld spots of fairly large area.

It will be evident, therefore, that welding by high frequency vibration already represents a useful addition to the available joining processes, and it is likely to find increasing application as the equipment is further developed.

Industrial Notes

DEMONSTRATIONS OF LAPPING will be given at an exhibition to be held at the Hounslow plant, Lawrence Estate, Green Lane, Hounslow, of Payne Products International, Ltd., from November 10 to 21. The operations will be carried out on Lapmaster machines, and prospective visitors are invited to send specimen components to the company, in advance, so that they may see them lapped during the course of the exhibition. Various accessories are also to be shown, such as Lapmaster monochromatic lights for checking flatness; optical flats, from 1 to 12 in. diameter; polishing plates; hand lapping plates and pastes; and polishing stands.

Obituary

MR. C. A. PRINCE, production director of British Vapour Blast, Ltd., Rose Hill, Coalbrookdale, Nr. Ironbridge, Salop., and of Intermetric Processes, Ltd., died suddenly on October 12.

The Price of a Subscription to MACHINERY is 52 Shillings per annum, post free, to any part of the world.

Subscribers are not bound for any definite period of subscription. We send MACHINERY, post free, each week until told to stop. Subscribers can pay yearly, half-yearly, or quarterly, pro rata. (Cash with order)

To MACHINERY, National House, 21 West Street, Brighton 1.

Please send me/us MACHINERY every week until I/we tell you to stop, for which I/we enclose remittance of 52 Shillings per annum or pro rata

Name

Address

* Position

* Firm

* For our mailing records only.

22/10/58

Machine Tool Demonstration

A demonstration of the latest machine tools produced by Churchill-Redman, Ltd., was recently staged at their West End Works, Halifax. Two of the new P.5 automatic multi-tool and profile turning lathes (see MACHINERY, 92/5/70—7/3/58) were shown, machining a bevel pinion shaft in two operations, the first of which was completed in a cycle time of 96 sec., and the second in 45 sec. We hope to publish more details of these turning operations in the near future.

Machine Tool Share Market

Stock markets were firm and generally cheerful during the period under review, and conditions in nearly all sections were very active.

British Funds were well supported and other high-grade fixed interest stocks also received attention at steadily improving levels.

The commercial and industrial sections became buoyant, and finished on a strong note, with higher prices over a wide range of securities, as a result of sustained investment and speculative demand.

Among machine tool issues, Asquith Machine Tool

Other machines demonstrated included a Fay 8-in. swing multi-tool lathe with hydraulic profiling equipment; a 12- by 20-in. semi-automatic hydraulic profiling lathe; centre lathes of 15-, 22-, and 28-in. swing, the latter provided with hydraulic copying equipment; a 28-in. swing surfacing and boring lathe with hexagon turret mounted on the saddle; and 18- and 24-in. stroke heavy-duty shaping machines, the former equipped with a swivelling work table.

Examples of power-operated chucks and hydraulic units were also on view.

advanced 3d. to 21s. 6d.; British Oxygen, 3s. to 43s.; Chas. Churchill, 1½d. to 5s. 1½d.; John Harper, 1½d. to 15s. 9d.; Churchill Machine Tool, 9d. to 18s. 1½d.; Geo. Cohen, 6d. to 11s.; Sheffield Twist Drill, 6d. to 12s. 9d.; Alfred Herbert, 7½d. to 36s. 3d.; Kayser Ellison, 1s. 6d. to 46s. 6d.; John Shaw & Sons (Wolverhampton), 4½d. to 14s. 1½d.; and Thos. W. Ward, 1s. to 85s. 6d.

WADKIN, LTD. Interim dividend 5 per cent (same).

THOS. W. WARD, LTD. Final dividend 10 per cent, plus a bonus of 5 per cent, making, with the interim, a total distribution of 20 per cent.

COMPANY		Denom.	Middle Price	COMPANY		Denom.	Middle Price
Abwood Machine Tools, Ltd.	Ord.	1/-	9d.	Harper (John) & Co., Ltd.	Ord.	5/-	15/9
Armstrongs, Stevens & Son, Ltd. ...	Ord.	5/-	8/3	" "	4½% Red.	£1	12/10½
Allen (Edgar) & Co., Ltd.	Ord.	£1	35/4	" "	Cum. Prf.		
" "	5% Prf.	£1	15/3*	Herbert (Alfred), Ltd.	Ord.	£1	36/3
Arnott & Harrison, Ltd.	Ord.	4/-	15/6	Helroyd (John) & Co., Ltd.	"A" Ord.	5/-	12/9
Asquith Machine Tools Corp., Ltd. ...	Ord.	5/-	21/6	" "	"B" Ord.	5/-	12/3
" "	6% Cum. Prf.	£1	10/6	Jones (A. A.) & Shipman, Ltd.	Ord.	5/-	22/-
Birmingham Small Arms Co., Ltd. ...	Ord.	£1	31/9	" "	7% Cum. Prf.	5/-	5/-
" "	5% Cum.	£1	15/6	Kayser, Ellison & Co., Ltd.	Ord.	£1	46/6
" "	"A" Prf.			" "	6% Cum. Prf.	£1	18/3
" "	6% Cum.	£1	18/-	Kendall & Gent, Ltd.	Ord.	5/-	7/-
" "	"B" Prf.			Kerry's (Gt. Britain), Ltd.	Ord.	5/-	6/3
" "	4% 1st Mort.	Stk.	80½	Kitchen & Wade, Ltd.	Ord.	4/-	8/3
British Oxygen Co., Ltd.	Ord.	£1	43/-	Martin Bros. (Machinery), Ltd.	Ord.	2/-	2/4½
Brooke Tool Manufacturing Co., Ltd. ...	64% Cum. Prf.	£1	22/-	Massey, B. & S., Ltd.	Ord.	5/-	9/-
Broom & Wade, Ltd.	Ord.	5/-	3/10½	Modern Engineering Machine Tools Ltd.	Ord.	5/-	10/7½
" "	Ord.	5/-	13/3	Newall Engineering Co., Ltd.	Ord.	2/-	4/9
" (David) Corporation Ltd.	6% Cum. Prf.	£1	17/9	Newman Industries, Ltd.	Ord.	2/-	2/3
Buck & Hickman, Ltd.	54% Cum. Prf.	£1	15/6	" "	6% Prf. Ord.	5/-	5/6
Butler Machine Tools Co., Ltd.	6% Cum. Prf.	£1	17/9	Noble & Lund, Ltd.	Ord.	2/-	3/9
C.V.A. Jigs, Moulds & Tools, Ltd. ...	Ord.	5/-	8/-	Osborn (Samuel) & Co., Ltd.	Ord.	5/-	21/-
" "	5% Cum. Prf.	£1	13/9	" "	54% Cum. Prf.	£1	25/9
Churchill (Charles) & Co., Ltd.	54% Red.	£1	11/3	Pratt (F.) & Co., Ltd.	Ord.	5/-	22/6
" "	Cum. Prf.			Scottish Machine Tool Corporation, Ltd.	Ord.	4/-	5/6
Churchill Machine Tool Co., Ltd.	Ord.	2/-	5/1½	Shardlow (Ambrose) & Co., Ltd.	Ord.	£1	43/6
" "	6% Cum. Prf.	£1	26/4½	Shaw (John) & Sons, Wolverhampton, Ltd.	Ord.	5/-	14/1½
Clarkson (Engrs.), Ltd.	Ord.	5/-	18/1½	Sheffield Twist Drill & Steel Co., Ltd.	Ord.	4/-	12/9
Cohen (George), Son & Co., Ltd.	6% Cum. Prf.	£1	10/3	" "	5% Cum. Prf.	£1	15/-
" "	Ord.	5/-	15/-xd	Stedall & Co., Ltd.	Ord.	5/-	7/6xd
Coverly Gauge & Tool Co., Ltd.	Ord.	5/-	11/6	" "	"B" non-voting Ord.	10/-	22/-
" "	44% Cum. Prf.	£1	14/-	Sykes (W. E.) Ltd.	Ord.	5/-	8/-
Coventry Machine Tool Works, Ltd. ...	Ord.	10/-	16/3	Tap & Die Corporation, Ltd.	44% Deb.	Stk.	82/-
Craven Bros. (Manchester), Ltd.	Ord.	£1	16/3	" "	1961-1977		
Elliott (B.) & Co., Ltd.	Red. Prf.	£1	13/9	Wadkin, Ltd.	Ord.	10/-	18/9
" "	Cum. Prf.			Ward (Thos.) W., Ltd.	Ord.	£1	85/6
Expert Tool & Case Hardening Co., Ltd.	Ord.	2/-	1/3	" "	5% Cum.	£1	16/-
Firth Brown Tools, Ltd.	Ord.	5/-	8/4½	" "	1st Prf.	£1	24/-
Elliott (B.) & Co., Ltd.	Ord.	1/-	3/3xd	" "	5% Cum.		
" "	44% Red.	£1	13/9	Willson Lathes, Ltd.	2nd Prf.	Ord.	2/4½
Greenwood & Batley, Ltd.	Cum. Prf.						

The Middle Prices given in the list are in several cases nominal prices only and not actual dealing prices. Every effort is made to ensure accuracy, but no liability can be accepted for any error.

* Sheffield price.

† Birmingham price.

PRICES OF MATERIALS

All prices per ton except where otherwise stated.

Pig-Iron

Foundry and Forge No. 3, Class 2

Middlesbrough zone Birmingham £21 6 0
£20 18 3

Phos. 0.1 to 0.75% Birmingham £23 17 0

Scottish Foundry Grangemouth £25 3 6

Hematite

English No. 1

N.E. and N.W. Coast £25 6 6
Scotland £42 2 0
Sheffield £25 13 0
Birmingham £27 4 0

Welsh £25 6 6

Steel Products

Medium plates £45 11 6
Mild steel plates, ordinary* £42 2 0
Boiler plates* £44 12 0

Flat bars 5 in. wide and under } £40 0 6
Round bars under 3 in. }
Billets, rolling quality, soft U.T. £32 15 6

Phosphor Bronze

Ingot (288) (A.I.D.) d/d £270 0 0

Copper

Cash (mean) £241 15 0
Cold rolled and hot rolled sheets
4 ft. by 2 ft. by 10 SWG £306 5s. 0-£306 10 0

Rods ½ in. to 1 in. diam. £324 5 0
Tubes, ½ in. bore by 10 SWG, ton lots, per lb. 3s. 1½d.

Wire rod, black, hot-rolled (½-1 in.) English £257 17 6

Zinc

Refined, minimum 98 per cent purity, current month (mean) £70 17 6

Brass

Tubes, solid drawn, per lb. 1s. 10½d.
Strip 63/37, 6 in. by 10 SWG coils, ton lots £254 0 0-£256 15 0

Rods, ½-3 in. diam. (59 per cent copper) 2s. 0½d.

Yellow Metal

Condenser plates, per ton £189 0 0
Rods, per lb. 2s. 1½d.

Aluminium

Ingot min. 99.5 per cent Canadian d/d £180 0 0

Lead

Refined, minimum 99.97 per cent purity, current month (mean) £74 15 0

Tinplates

U.K. Home trade: Handmill f.o.t. makers' works £3 11 8½
Cold reduced, f.o.t. makers' works £3 7 4½

U.K. Export: Hot rolled basis, f.o.t. works' port 72s. 6d.-75s. 0d.
Cold reduced basis, f.o.t. works' port 75s. 0d.

Gunmetal

Ingot, 85.5 S.S. ex works £191 0 0
* N.E. Coast, N. Joint Area, Central Scottish Zone.

† U.T. soft basic.

‡ Official maximum price, after allowing for adjustments for increase in price of tin.

MAKERS' PRICES

Hexagon Steel Bars¹

Sizes in inches from 1 in. up to 2-2½ and 2-4½ a/f, ex works 2 ton basis £42 17 0

Free cutting black £47 6 6

Reeled Steel Bars¹

Single-reeled 1½ in. upwards, f.o.t. works (+ usual extra for sizes) £43 9 6

Free cutting £47 19 0

Precision-ground Mild Steel¹

1-in. dia. + 0.00025-in. 4-ton lots, per cwt. 121s. 6d.

Bright Ground Stainless Steel Bars¹

EN56AM (martensitic, free cutting) £285
EN58AM (austenitic, free cutting) £353

High-Speed Steel

Black random length bar. All prices basic, per lb., subject to extras.

Molybdenum "66" 5s. 10d.
Molybdenum "46" 5s. 8d.

14 per cent tungsten 5s. 6d.
16 per cent tungsten 5s. 10d.

18 per cent tungsten 6s. 0d.
22 per cent tungsten 7s. 0d.

5 per cent cobalt 9s. 1d.
4-75/5-25 molybdenum + 6-0/6-75 tungsten + 1-75/2-05 vanadium per cent (5-6-2) 6s. 0d.

Precision-ground, High-speed Free-turning Brass Rod¹

½-in. dia. ± 0.00025-in. 2-ton lots, per lb. 2s. 5½d.

Grey Iron Rod

Die Cast¹ in random lengths 18 in. to 26 in. rough machined ½-in. above listed size. Extra for definite lengths. Discounts for orders over £150.

Per cwt. net. Mark I Mark III
¾ or ¾ in. 245s. 4d. 318s. 10d.
1 or 1½ in. 196s. 4d. 251s. 10d.

1½ to 2 in. 137s. 10d. 171s. 2d.
2 to 2½ in. 106s. 2d. 125s. 11d.
2½ to 3½ in. 91s. 6d. 106s. 4d.
3½ to 12 in. 86s. 6d. 99s. 2d.

Continuous Cast
10-ft. lengths, centreless machined 1 to 3-in. dia. + 0.010 to 0.020 in., prices as quoted for die cast bar⁴

6-ft. lengths ¾ or ¾ in. 245s. 4d.
1 or 1½ in. 196s. 4d.

+ 0.010 in. Extra for hardenable 1½ to 2 in. 137s. 10d.
alloy iron⁵ 2 to 2½ in. 106s. 2d.

Per cwt. net 2½ to 3½ in. 91s. 6d.

Stellite¹

Welding Rods plain ¾ in. dia. per lb. 30s. 0d.

Toolbits ¾ in. sq. x 4 in., each 22s. 3d.

1 Colvilles, Ltd., Glasgow, and 17 Grosvenor Street, London, W.1. 2 Pratt, Levick & Co., Ltd., Chester, 3 Spartan Steel & Alloys, Ltd., St. Stephens Street, Birmingham, 6. 4 Sheepbridge Alloy Castings, Ltd., Sutton-in-Ashfield, 5 "Flocast," Harold Andrews Sheepbridge, Ltd., Halesowen, 6 Deloro Stellite, Ltd., Highlands Road, Shirley, Solihull.

BASIC PRICES FROM LONDON STOCK¹

Free Cutting Steel

Bright cold drawn: (Usaspeed) over 1½ to 2 in. £59 17 6

Lead bearing (Usaled) £64 4 0

Precision ground, 1½ in. £81 13 6

Bright Drawn

M.S. bars (M.M.C.) over 1½ in. to 2 in. £55 3 6

Square edge flats (Usafat) £72 0 0

M.S. angles (Usaspeed) £99 10 0

Casehardening (EN) (Usacase) over 1½ in. to 2 in. £63 9 6

M.S. bars (EN3B) (Usamild) over 1½ to 2 in. £57 3 6

Carbon manganese semi-freecutting case hardening (EN202) (Usaspeed 202) over 1½ to 2 in. £72 19 0

35/45 ton tensile (EN6) (Usen) over 1 to 1½ in. £64 17 6

0-4 Carbon Normalised (Usaspeed "40") over 1½ in. to 2 in. £66 19 6

Carbon manganese steel to Specification EN.16.T (Usaspeed 5565), per ton £127 11 3

Ground Flat Stock

18-, 24-, and 36-in. lengths (Usaspeed). List prices less 5 per cent

Oil Hardening Cast Steel

Non-shrink (Usaspeed N.S.O.H.) ½ in. to 2½ in., per lb. 1s. 11d.

Non-distorting heavy duty (Usaspeed H.C.H.C.) ½-in. to 2½-in., per lb. 4s. 2d.

Silver Steel

(0.194-in. to 1½-in.) Genuine Stubbs quality, per lb. 4s. 6d. less 27½%

M.M.C. quality, per lb. 2s. 5d. + 6½%

Boxes of 16 assorted sizes ½-in. to 1-in. dia. 7s. 6d.

Stainless Steel

K.E. 40AM (Freecutting), per lb. 3s. 3½d.

Glacier Machined Bronze Bars

Phosphor bronze (288) } Prices on application
Lead bronze }


High-speed Steel

18 per cent tungsten. Prices on application, Toolholder bits: Usaspeed "Super" } List price
" " "Supreme" }
" " "Cobalt 10 }

Shimstock

Steel assorted, per tin 3s. 6d.
Brass " " 7s. 3d.

6 Macready's Metal Co., Ltd., Pentonville Road, N.1. Subject to confirmation by London Office. Delivered free by van in London area.



"Composine"

COMPOUND AND SIMPLE ANGLE SINE TABLES

NEW UNIVERSAL TYPE: MADE TO HINGE FROM
EITHER END OF BASE PLATE TO ENABLE
ALL COMPOUND ANGLES TO BE OBTAINED

◀TYPE E.W.U/L. Face 11in. × 7in. £185 complete with
6in. centres.

SIZES: TYPE E.W.U/L.

Face (T Slotted).....11in. × 7in.

Base.....12in. × 8in.

Height at rest.....5in.

10in. and 5in. Roller Centres.

TYPE E.W.U/S

Face (T Slotted).....8in. × 5in.

8in. and 5in. Roller Centres.

N.P.L. Certificate supplied at cost if required
Guaranteed accuracy 0.2 minutes of arc.
Can be supplied with electric magnetic
or non-electric magnetic face.

WINDLEY BROTHERS LIMITED
CROWN WORKS · CHELMSFORD · ENGLAND
TELEPHONE: CHELMSFORD 2224

ARNO

TYPE 3V VERTICAL MILLER



- ★ Swivelling and sliding head
- ★ Power feeds in three directions
- ★ Rapid traverses with single lever control
- ★ Centralised grouping of control levers
- ★ Hardened and ground gears
- ★ Schlesinger limits

Table w.s. 63" × 15"
Spindle speeds (20)
30—1,200 rpm.
Power traverses
5½" × 14½" × 21½"
Table feeds (16)
.281"—22" per min.
H.P. 17
Weight 7040 lbs.

Sole Agents

PIDGEN BROS

LIMITED

HELMET ROW, OLD STREET
LONDON, E.C.1.

Telephone Clerkenwell 6481

When answering advertisements kindly mention MACHINERY.

FOR SILENT RIVETING

HERE IS HOW YOU CAN SPEED THE JOB - AND CUT COSTS


Do you make automobile components, accessories, electrical equipment? If they require riveting you need T.T. Rivet Spinners. Not only are they faster and cheaper to operate, they enhance the final appearance and form a perfect head without swelling the rivet shank. Coping with mild steel rivets up to $\frac{3}{4}$ in. dia. the range includes vertical single spindle machines suitable for most purposes, and horizontal duplex models for heading both ends in one operation. Your samples completed for approval.

TURNER

MACHINE TOOLS LTD
63-68, PRINCIP ST., BIRMINGHAM, 4

Telephone: ASTON CROSS 2244

*Illustrated:
RS3 V.M.D. A.E. $\frac{3}{4}$ in. cap.
air operated machine on cabinet
base.*



'CENTEC' 2

Universal Precision Milling Machines with

① ② ③ Possibilities of table movement

ALL GEARED 6 spindle speeds

BRITISH
MADE

Calibrated
dial and
lead screw

③

① ④ Power feeds


② Capstan handle
rack and pinion

With big advantage of fast table approach by Capstan Handle followed by automatic feed on cut and fast return by Capstan Handle.

Index table
Dividing head
Quick-action
swivel vice
Rotary table

Table
working surface
2A—16in. x 4 $\frac{1}{2}$ in.
2B—25in. x 5in.

Long
Traverse
8in.
13in.



Vertical swivelling head for MILLING and DRILLING at all angles.

CENTEC MACHINE TOOLS LTD

Hemel Hempstead, Herts.

Telephone: Boxmoor 584-5-6

"ILO CUT"

NEAT CUTTING OILS

— used by NORTON MOTORS Ltd



"Ilocut" being used to bore and face light alloy die cast front hub shells.



And users not only of our range of "Ilocut" Neat oils—but "Dixol" Soluble oils, too. In fact, the famous Norton company uses Wakefield-Dick production oils exclusively. Why do so many leading engineering companies specify our production oils? Basically, because their consistently high quality helps to get better results. And, hardly less important, because our highly skilled production oils engineers are always able to help over unfamiliar hurdles. In short, "know-how" and "service."

WAKEFIELD-DICK INDUSTRIAL OILS LTD · 67 GROSVENOR STREET · LONDON · W.1
A MEMBER OF THE WORLD-WIDE WAKEFIELD CASTROL ORGANISATION



JIGS & FIXTURES
IN A FEW HOURS

WHARTON
Tooling

FOR MILLING • DRILLING • TURNING

WHARTON
Tooling

FOR SHORT RUNS & BATCH PRODUCTION

WHARTON
Tooling

FOR PROTOTYPE & EXPERIMENTAL WORK

WHARTON
Tooling

FOR TIME & COST SAVINGS

WHARTON
Tooling

WHARTON & WILCOCKS LTD
20 BULL PLAIN • HERTFORD • ENGLAND
Telephone: HERTFORD 4041


LINDLEY'S

bright and

heat treated

Bolts and

Set Screws



LINDLEY'S

turned

from bar and

cold formed

Nuts



WORKS AT
LONDON AND
EUDENDEN,
YORKSHIRE.

C. LINDLEY & CO. LTD.

Head Office: Englefield Road, London, N.1.
Phone: CL 1552 0643 (5 lines) Grams: Beauvoir, Norder, London.

When answering advertisements kindly mention MACHINERY.



RAPID RUST REMOVAL

S

POSITIVE PROTECTION



One *COLD* application removes surface rust and combines with the rest, however deep seated, sealing off the pores of the metal with a protective phosphate plating. No after rinse neutralising, no need to wipe off. Non-toxic, non-volatile, non-inflammable. A perfect base for paint, cellulose or enamel. Industrial sizes $\frac{1}{2}$, 1, 5, 10 Galls and upwards. Now available in 'POLY-PACKS' of 6 ozs and 1 pint.

RID-O-RUST

(By the makers
of Spectra-Color
layout fluids)

SPECTRA CHEMICALS LTD.
SPECTRA WORKS, HIGH STREET, CATERHAM, SURREY
Tel: CATERHAM 3182 & 2293
Grams: SPECTRA, CATERHAM

COOKE

OPTICAL CLINOMETER

The accuracy of this instrument is in no way dependent on screws, worms or racks. The graduations are carried on a glass circle and are read by a high power microscope giving a clear reading to one minute of arc against a brightly illuminated background. The cast iron base is of vee and plane construction.

Fully described in publication CE 600.




Cooke Troughton & Simms

LTD

Y O R K & L O N D O N

Are these hands helping *you*?



These hands are but a pair among many engaged in the continuous testing and experimental work carried out in P.J. laboratories, where skilled paint technicians tackle the complex problems which confront industrial paint users. Your area P.J. technical representative will bring you the services of this team of experts to advise and assist you with your finishing problems.

You can rely on

PINCHIN JOHNSON

for Paint and Service

PINCHIN, JOHNSON & CO., 4 CARLTON GARDENS, LONDON, S.W.1

Telephone: TRAfalgar 5600

LOCAL BRANCHES & STOCK DEPOTS:

BELFAST:

Dalton Buildings, Dalton Street.
Belfast 58643

BIRMINGHAM, 1:

King Edward's Place, Broad Street.
Midland 1042-3-4

BOOTLE, 20:

72 Brewster Street.
Liverpool, Bootle 2121

BRIGHTON, 1:

26-27 Elder Place. Brighton 23739

BRISTOL, 8:

21 High Street, Clifton. Bristol 33889

GLASGOW, C.2:

Ocean Chambers, 190 West George St.
Douglas 3281-2

LEEDS, 11:

123 Water Lane. Leeds 24377

MANCHESTER, 3:


22 Bridge Street. Blackfriars 3800

NEWCASTLE-ON-TYNE, 1:

Pudding Chare.
Newcastle-on-Tyne 21919

SOUTHAMPTON:

41 Lower Canal Walk.
Southampton 23648



HEID PLANER DRIVES

Speed planing times

Among the many advantages of a HEID planer drive are:—

- Increased output.
- Speeds increased to full capacity.
- Greater pulling power.
- Up to one-third time saved.
- From 3 to 12 additional speeds.
- Fast, accurate and smooth reversal.
- Pushbutton control.
- Automatic protection against overloads.
- Easy operation and maintenance.


HEID

Versatile range of clutches

ELECTROMAGNETIC MULTI-DISC CLUTCHES

without slip rings

Stationary magnetic coils eliminate shocks during acceleration and braking. Rotating elements have been reduced to a minimum. There are no carbon brushes, no sparking, no power failures caused by oily slip rings and no adjustment or maintenance of brush gear. Torque capacities from 8.6 to 4,560 lbs./ft. Other types available with air gap, wet or dry operation. Also with slip rings.



Sole Selling Agents U.K.



NEWMAN INDUSTRIES LIMITED


Machine Tool Division

YATE • BRISTOL • ENGLAND

Telephone: CHIPPING SODBURY 3311

Telegrams: "DYNAMO YATE"

When answering advertisements kindly mention MACHINERY.

AGEMASPARK F. 500 Swiss Made**SPARK-EROSION MACHINE**

To remain competitive in the toolmaking field, you cannot afford to be without this precise and advanced machine.

Ideal for the production or modification of all types of moulds, dies or punches, in hardened steel or tungsten carbide.



Table Size: 20in. by 16in.

Electrode Traverse 12in. by 8in.



Inclinable and Rotating Electrode Spindle
Retractable Dielectric Tank



Powered Electrode Traverse and Feed

Max. Area of Erosion, 70 sq. in.

Surface Finish Obtainable, 12 micro-inches

SECURE DETAILS TODAY:

Sole U.K. Agents:—



4 GRANGE ST., ST. ALBANS, HERTS. Tel: St. Albans 56731/2 Grams: Amelco, St. Albans



does the trick again . . .

giving the best performance possible, with the aid of the Polygon Tool Box. This lathe attachment swings the balance of production in your favour. Time spent on shapes such as hexagons, octagons, squares, etc., is reduced by as much as ONE THIRD.


Write NOW for a copy of our descriptive booklet on the "Polygon Tool Box"

Thomas Chatwin & Co.

GT. TINDAL STREET, BIRMINGHAM, 16 Tel: Edgbaston 3521

25, Hanover Square, London, W.1. Tel: Mayfair 8783

ONE OF THE **BROCKHOUSE** COMPANIES



BRUSH SPRINGS BY TERRYS

Our long experience has taught us how to make good BRUSH SPRINGS in steel and phosphor bronze. Please may we quote to your samples or prints?



HERBERT TERRY & SONS LTD

REDDITCH *Spring Specialists for over 103 years*

Manchester: 279 Deansgate London: 27 Holborn Viaduct, E.C.1
Birmingham: 210 Corporation Street

When answering advertisements kindly mention MACHINERY.

HT 25A

L


**HIGH PERFORMANCE
FROM OLD MACHINES!**

WESTON

AIR-HYDRAULIC

PRODUCTION UNIT

**for Fast Approach and Return Speeds
...at a very sensible price.**



**GIVES HIGHER PRODUCTION ON—
MILLING, DRILLING, GRINDING, ETC.**

An entirely self-contained unit, easily fitted to most types of machine tools. 6in. movement is provided and the tool feed movement is variable by a side table dog. The return stroke is at the original fast movement. Infinitely variable feed rates from 2in. per minute upwards, with fast approach and rapid return. Instant control by manual valve. Work table 18in. by 6in. Base 24in. by 8in. Recommended pressure 70 to 100 lbs. per sq. inch. Ask for complete details.

THE WESTON MACHINE TOOL CO., LTD

210 BRACEBRIDGE STREET, ASTON, BIRMINGHAM 6 Tel: ASTon Cross 1788

SPECIALISTS in used and reconditioned machine tools

USED MACHINE TOOLS FOR IMMEDIATE DELIVERY ★

ACME-GRIDLEY $\frac{3}{8}$ in., 1in., 2in., 2 $\frac{1}{2}$ in.,
Six-Spindle Bar Automatics.

ACME-GRIDLEY 6 $\frac{1}{2}$ in. Six-Spindle
Chuckling Automatics.

B.S.A. ACME-GRIDLEY $\frac{1}{2}$ in. Six-Spindle
Bar Automatics.

B.S.A. ACME-GRIDLEY 5 $\frac{1}{2}$ in. Six-Spindle
Chuckling Automatic.

B.S.A. 168AL Single-Spindle Automatic
Screw Machines.

B.S.A. 5in. and 9in. Single-Spindle
Chuckling Automatics.

B.S.A. Multi-Tool Lathes, 6in. x 12, 20 and
28in.

B.S.A. No. 7 and No. 8 Centreless Grinding
Machines.

B.S.A. 50H Honing Machine.

B.S.A. LANDIS 6in. x 30in. Type C Plain
Grinders.

B.S.A. POTTER & JOHNSTON 5D
Automatic Turret Lathes.

AMERICAN Broaching Machine 10/48.

ASQUITH Two-Spindle Profiling Machine.

BRADFORD Lathe.

HERBERT Vertical Millers 10V, 18V, and
46V.

HOLROYD Two-Spindle Profiling
Machines.

HULLER No. 5 Tapping Machines.

INDEX "52" Single-Spindle Automatics.

LANDIS 10 x 24 Universal Grinder.

POTTER & JOHNSTON 5D Automatic
Turret Lathe.

WARD 2A Capstan Lathes.

WARD OE Capstan Lathes.

★ Offered subject to prior sale.
All machines motorised suitable for
400-440 volts, 3 phase, 50 cycle supply.

We offer good prices for your surplus plant. Send
us details—we will inspect immediately and make
a firm offer. Write, wire or phone...




When answering advertisements kindly mention **MACHINERY**.



TOOLS FROM

HALLMAC



the progressive decision

Hallmac carry immense and comprehensive stock ranges of Engineers' Small Tools, Macrome Treated Tools, Hand and Power Tools. Their distribution and service network covers the country. Your entire current needs in this field and all future expansions and special problems can be taken care of by the single decision—tools from Hallmac.

HALLMAC TOOLS LIMITED

Head Office and Depot: PO Box No. 39, Macrome Road, Wolverhampton. Telephone 58001 (9 lines)

LONDON: 21, Ivor Place, N.W.1. Telephone PADDington 0204

MANCHESTER: Transport House, 1 The Crescent, Salford 5, Lancs. Telephone PENdleton 3656

GLASGOW: Central Chambers, 11 Bothwell Street, C.2. Telephone CENTral 5066

Sales Managers for the Hand Tool Division of the Breen Manufacturing Company

JW.A4 4308

When answering advertisements kindly mention **MACHINERY**.

L2

MARK YOUR NAMEPLATES


— MORE RAPIDLY AND EFFICIENTLY

THE NEW STANDWELL

MODEL 'K' BENCH MOUNTING DIAL TYPE MARKING MACHINE

Unique Features include:—


- Vertical adjustment to marking head.
- Rapid positioning for marking.
- Automatic spacing of characters.
- Perfect alignment of Type.
- Choice of character sizes.
- Special marks as required.
- Marks articles up to 7in. thick.



THE STANDWELL EQUIPMENT CO. LTD.

CAMBRIDGE GROVE ROAD, KINGSTON - ON - THAMES

Phone: Kingston-on-Thames 4566 (3 lines) Grams & Cables: Impress, Kingston-on-Thames



NEW IMPROVED "ACE" ROTARY CIRCULAR TABLES ADJUSTABLE WORM & WORM WHEEL Sizes 6", 7½", 10", 12", 16", 20", up to 52".

All tables are 1/10th min. readings, except 6in. dia.—
2 min. reading. Calibrated in Degrees. Instantaneous
Release Worm for Rapid Indexing.

THE MOST COMPETITIVE PRICED TABLE
ON THE MARKET TO-DAY

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BATHAM 8551 (5 lines)

★ ACE 10in. Heavy duty Dia.

UNIVERSAL ANGLE TABLE



British made

ROTARY
TILTING
TABLE
WITH
SWIVELLING
BASE
★ FOR
DRILLING
SHAPING
MILLING
GRINDING
★ FOR
TOOLROOM
OR
PRODUCTION

★ UNIVERSAL APPLICATION !!!


W. URQUHART 1023-7 Garratt Lane, London
S.W.17. BATHAM 8551 (5 lines)

VOLMAN


GEAR HOBBERS & GEAR SHAPERS

*Backed by over
35 years' experience*


**ALL AVAILABLE
FROM STOCK**



MODEL FO.6
Capacity 31½"
diameter x 4 D.P.



MODEL OF.10
Capacity 49"
diameter x 2½ D.P.



MODEL OH.6
Capacity external
gears 17½"; internal
gears 19½" x 6
mod.

Exclusive distributors in the United Kingdom:

ALSO AVAILABLE FROM STOCK OH.4 Gear Shaper
Capacity 7½" x 6 D.P.


ELGAR

MACHINE TOOL COMPANY LIMITED

RIGHT OPPOSITE NORTH ACTON STN.

172-178 VICTORIA ROAD · ACTON · LONDON W3 · Telephone ACORN 5555

Midlands Office and Showrooms: 1075 KINGSBURY ROAD, ERDINGTON, BIRMINGHAM 24. Tel. Castle Bromwich 3781/2
Scottish Agents and Showrooms: ANGUS & CRICHTON (SALES) LTD., 37 DALMARNOCK ROAD, RUTHERGLEN, LANARKSHIRE
NRP2190



MULTIPLE DRILL HEADS

★ **COMPACT IN DESIGN**
★ **FIXED OR ADJUSTABLE CENTRE DISTANCES**

Hey Multiple Spindle Drill Heads convert Standard Drilling and Boring Machines to High Production Machines permitting drilling of all holes in a component simultaneously, with production rates equal to those obtainable on expensive special purpose machines.

Compact design reduces to a minimum, distance from drill head to machine spindle, whilst careful selection of material ensures an extremely efficient light weight head.

Heads are available with any number of spindles, covering a wide range of sizes

MAXIMUM PRODUCTION ON DRILLING, REAMING, TAPPING AND SPOT FACING OPERATIONS


We also manufacture Rotary Cams and Profile Milling Machines, Short Thread Milling Machines, Gear Tooth Rounding Machines, Tapping Machines, End Facing and Centring Machines, Special Machine Tools for High Production.

HEY

ENGINEERING CO. LTD.
COVENTRY PHONE: COVENTRY 86641

NRP

ALANBROS 11



Precision bench surface grinding machine

LIP

Developed for the watch clock instrument and allied industries

Capacity : LENGTH 202 mm
BREADTH 108 mm
HEIGHT 125 mm

Surface of magnetic chuck :
105 x 152 mm.

Accessories available :

Stand
Dust extractor
Dressing diamond with holder universal vice

LIP INDUSTRY




BESANÇON : 7, rue des Chalets. Tél. 59-31

Agents for Great Britain : TORNOS SALES C^o
E. M. Vaughan Ltd
Broadgate House
COVENTRY

Catalogue sent on request

The HYPROFILE

UNIVERSAL HYDRAULIC DUPLICATING ATTACHMENT
A COMPLETE PORTABLE UNIT EASILY FITTED TO ANY STANDARD MACHINE TOOL ● **PROVED ON PRODUCTION**



OUTSTANDING FEATURES

1. A Universal Hydraulic Duplicator for Lathes, Shapers, Planers, Boring and Grinding Machines.
2. Low cost duplicating of parts or contours on the face, diameter, or bore.
3. Swivelling Tracer Bracket through 360° enables 90° angles and undercuts to be produced at high speed.
4. Rotating cut Control Slide through 360° allows the cut to be fed in at the required angle.
5. Any position Template Holder to suit job or the Operator, easy access for changing the template or stylus.
6. Template can be set at minimum distance from the tool giving rigidity and accuracy in full view of the operator.
7. Can be installed by the Operator in minutes, and fits any standard Machine Tool.
8. No brackets to make.
9. No holes to tap.
10. Ready for use on delivery.

A tricky job..

PROFILE TURNING MOTOR CAR TYRE MOULD, WITH TEMPLATE ATTACHED TO SADDLE, ENABLING WORK-PIECE TO BE REMOVED WITHOUT DISTURBING SET-UP

Send us your profiling problems and arrange for a demonstration !


ARMYTAGE (TOOLS) LTD.
 FOUNDRY LANE · KNOTTINGLEY · YORKSHIRE · ENG.
 Telephone 2743-4

The features illustrated above are the subject matter of one or more of several patents

Descriptive Catalogue supplied on request

When answering advertisements kindly mention MACHINERY.


B&T SHIM WASHERS




★

Made in diameters from $\frac{1}{8}$ " to 10" with bores to suit and any quantity, material, brass or steel shim stock in thicknesses between .002 and .06". Also laminated shims up to 6" dia. Tab washers and shims of irregular shapes can also be produced, and we shall be pleased to receive your enquiries.

BONEHAM & TURNER LTD MANSFIELD
NOTES
 PHONE 896




oooooooooooooooooooooooooooooooo



NUMBERING HEADS

for Serial Marking

Funditor Numbering Heads are available with consecutive and repeat actions and can be supplied with dovetail to fit Marking Machines or with shank for Fly, Hand, Power or Pneumatic Presses. Automatic numerators may be equipped with non-automatic prefix or suffix wheels. Wheels can be made-up bearing figures, letters, inspection stamps or symbols as required.




Special male and female electrically heated embossing numerator for 9 mm. film.

FUNDITOR

FUNDITOR LIMITED,
 3 WOODBRIDGE STREET, LONDON, W.1.
 Phone: CLErkenwell 6155 - 7

When answering advertisements kindly mention **MACHINERY**.

**OUTPUT INCREASED
BY 80% ON THIS
USING /**



BW

**AUTOMATIC
MAGAZINE BAR FEED**

- TIME TO LOAD A 10' BAR — 4 SECS.
- OCCUPIES THE MINIMUM FLOOR AREA
- OBTAINABLE FOR EITHER 10' OR 12' MAX. LENGTH BARS
- AUTOMATIC EJECTION OF SHORT ENDS

DETAILS FROM:—

BROWN & WARD (TOOLS) LTD.
HATHERTON LANE • LEAMORE • WALSALL • STAFFS

PATENT APPLIED FOR

At Messrs. Tecalemit Ltd. Plymouth, the average daily production of Piston Rods, as illustrated above, for one of their range of Grease Guns was 2,200 pieces.


The installation of a BROWN AND WARD Automatic Bar Feed to the OOG. Brown and Sharpe Automatic producing these items has resulted in an increase in the output of 4,000 pieces per day, an increase of over 80%.

The economy which can be effected by this efficient but competitively priced unit cannot be overlooked when considering the potential operating efficiency of your automatic bar machines.

Send for details now ! !


When answering advertisements kindly mention **MACHINERY**.

B&T SHIM WASHERS





Made in diameters from $\frac{1}{8}$ " to 10" with bores to suit and any quantity, material, brass or steel shim stock in thicknesses between .002 and .06". Also laminated shims up to 6" dia. Tab washers and shims of irregular shapes can also be produced, and we shall be pleased to receive your enquiries.

BONEHAM & TURNER LTD MANSFIELD
NOTES
PHONE 896



Barrel-shaped numerator with solid engraved die and automatic numbering wheels.




Automatic numerator for serial numbering flat parts.

NUMBERING HEADS

for Serial Marking

Funditor Numbering Heads are available with consecutive and repeat actions and can be supplied with dovetail to fit Marking Machines or with shank for Fly, Hand, Power or Pneumatic Presses. Automatic numerators may be equipped with non-automatic prefix or suffix wheels. Wheels can be made-up bearing figures, letters, inspection stamps or symbols as required.



Special male and female electrically heated embossing numerator for 9 mm. film.

FUNDITOR


FUNDITOR LIMITED,

3 WOODBRIDGE STREET, LONDON, W.1.

Phone: CLerkenwell 6155 - 7

When answering advertisements kindly mention **MACHINERY**.

**OUTPUT INCREASED
BY 80% ON THIS
USING /**



- TIME TO LOAD A 10' BAR — 4 SECS.
- OCCUPIES THE MINIMUM FLOOR AREA
- OBTAINABLE FOR EITHER 10' OR 12' MAX. LENGTH BARS
- AUTOMATIC EJECTION OF SHORT ENDS

DETAILS FROM:—

BROWN & WARD (TOOLS) LTD.
HATHERTON LANE • LEAMORE • WALSALL • STAFFS

PATENT APPLIED FOR


At Messrs. Tecalemit Ltd. Plymouth, the average daily production of Piston Rods, as illustrated above, for one of their range of Grease Guns was 2,200 pieces.

The installation of a BROWN AND WARD Automatic Bar Feed to the OOG. Brown and Sharpe Automatic producing these items has resulted in an increase in the output of 4,000 pieces per day, an increase of over 80%.

The economy which can be effected by this efficient but competitively priced unit cannot be overlooked when considering the potential operating efficiency of your automatic bar machines.

Send for details now ! !

When answering advertisements kindly mention MACHINERY.



New

New

New

the New DUNBAR & COOK Collet Chuck

Designed for use with "Ward" 2A, 3A, or "Herbert" 2D and 4 Senior Capstans and Air Operated Lathes, this over size collet chuck enables second operation work up to four inches diameter to be accommodated but retains all the benefits of a ball chuck.


DUNBAR & COOK LTD · NEW JOHN STREET · BIRMINGHAM 6

Phone: ASTon Cross 2571/2/3

Grams: "CUBAR" Birmingham

SPECIALISTS IN THE MANUFACTURE OF

**SPECIAL PURPOSE
MACHINES
JIGS AND FIXTURES**



**COVERS and
PACKINGS**
FOR MODERN INDUSTRY

**FORTOX FLEXIBLE
COVERS** protect machinery and exclude dirt. Made in neoprene nylon proofed leather or coated fabrics to suit all conditions. New type of construction gives expansion to contraction ratio of 10-1. Single items supplied to special requirements without tool charge.

FORTOX SEALS AND PACKINGS are manufactured to high standards of accuracy ensuring positive sealing and trouble free life. A range of polyester rubbers, silicone leathers and synthetics is available for extreme conditions. Single items supplied promptly.

Write to-day for full details of our work.
A.I.D. approved.



Henry Beakbane (Fortox) Limited

HEAD OFFICE AND TANNERY

THE TANNERY-STOURPORT ON SEVERN-WORCS

TELEPHONE STOURPORT 2011

LONDON WORKS

68-70 LAMT ST. BOROUGH SE1

TELEPHONE HOB 0438

When answering advertisements kindly mention **MACHINERY**.

PNEUTOMATION

*a power for production
that's yours to command*


What you need in your works is this pocket-sized elephant —

PNEUTOMATION! You'll find PNEUTOMATION has all the power of a pachyderm, plus compactness. You get the same tireless energy, accurately applied to the right place at the right time, under perfect control.

PNEUTOMATION is tailor-made to work with the minimum of elbow room and the wide range of standard equipment fits any job from bell-ringing to jig-boring. Simple design, careful workmanship and completely non-corrodible materials cut replacement and maintenance costs, make Lang PNEUTOMATION a really long-lasting, trouble-free system.

Pneutomatic never forgets to operate

The 'Pneulang' basic cylinder unit, just one of the 204 cylinders available 'off-the-shelf'. The range of PNEUTOMATION equipment also includes many types of manual and automatic valves, lubricators, air flow regulators, pipes and fittings, etc.



PNEUTOMATION
energy under control



Plan with

LANG PNEUMATIC LTD

VICTORY WORKS, BIRMINGHAM ROAD, WOLVERHAMPTON Tel. 25221-2-3

Associated with Desoutter Brothers (Holdings) Ltd.

P.1651

When answering advertisements kindly mention MACHINERY.

STAG MAJOR *★ Superweld Tools*

George Hatch Limited, Stockist-Agents for London and the Southern Counties are able to supply the famous Edgar Allen STAG MAJOR SUPERWELD TOOLS ready for use and from a comprehensive stock supply all shapes and sizes of standard tools.

The solid end of STAG MAJOR SUPERWELD TOOLS is no mere layer, but electrically butt-flash welded Stag Major super high speed steel on medium Carbon Steel Shanks. They give maximum performance with an exceptionally long cutting life.

Illustrated tool chart available free on request.




★ Stockist Agents for London and the Southern Counties:



**GEORGE HATCH
LIMITED**

3, QUEENHITHE, UPPER THAMES STREET, LONDON, E.C.4

Telephone: CENTral 7751



Our business is reliability




The whole basis of our business has always been to supply high pressure fittings which will guarantee the reliability of pipe line systems. Experience of high pressure problems has brought with it the large range of fittings now produced by Ermeto.


ERMETO
MADE IN ITALY

Details of high pressure couplings and valves will be sent on request.

British Ermeto Corporation Ltd, Hargrave Rd, Maidenhead, Berks. Tel: Maidenhead 6100 (10 lines)



Model A.E.4. All Electric Radial Drilling Machine. Centralised control. Six sizes: 4' to 8'. 12 Speeds. 4 Feeds. Drills $2\frac{1}{2}$ " from solid in mild steel and taps $1\frac{1}{2}$ " Whitworth.



Models E.G.4 and E.G.8. All Electric Girder Type Radial Drilling Machines. Centralised control. Each model made in five sizes from 4' to 8' E.G.4: 4 Speeds. 3 Feeds. E.G.8: 8 Speeds. Range 20-500 r.p.m. 3 Feeds. Drills 2" from solid in mild steel.

The "Town" range of drilling machines has developed from more than 50 years'

TOWN

experience. Town's are well known by satisfied users all over the world.

Write for fully illustrated leaflets


FREDK. TOWN & SONS LTD
HALIFAX - YORKSHIRE

Telephone: 40373 Telegrams: Town Engineers Halifax


Model A.E.2. All Electric Heavy Duty Vertical Drilling Machine. Centralised control. Two sizes: 36" and 42". 18 Speeds. 8 Feeds. Drills $3\frac{1}{2}$ " from solid in mild steel.



Model A.E.5. 42" All Electric Sensitive Radial Drilling Machine. Centralised Control. 9 Speeds. 3 Feeds. Drills $1\frac{1}{2}$ " from solid in mild steel and taps $\frac{1}{2}$ " Whitworth.



Model C.E.1. All Electric Radial Drilling Machine. Centralised control. Three sizes: 5', 6' and 7'. 18 Speeds. 8 Feeds. Drills 3" from solid in mild steel and taps 2" Whitworth.



When answering advertisements kindly mention **MACHINERY**.



mixed up with ^{small bore} metal tubing?

Why not let us sort things out? Our range of light metal tubing is generally recognised to be unbeatable in extent, consistency and low cost. We manufacture for every kind of industrial and engineering purpose in 3/64" to 1/2" o.d., from 3/32" to 20' 0" lengths from 0.006" to 0.064" wall thickness. We supply in super purity aluminium, commercial purity or light alloys.

In addition, we do a large business in brass, commercial h.c. and o.f.h.c. copper tubing and fabricate small tubular parts involving bending, turning or pressing exactly to customer's specifications.

You can rely on

ELLAY
Tubes
LTD.

ELLAY TUBES LIMITED

Cox Green Works, Maidenhead, Berks.
Telephone: Maidenhead 3303



Are your spinnings pressing . . . your pressings urgent . . . ?

. . . in short, can you use a really reliable engineering service . . . capable of producing metal spinnings, pressings (and the tools) and sheet metal work of a very high standard . . . and capable of keeping delivery promises? We provide just such a service and will be pleased to undertake your work.


CORNERCROFT
GROUP OF COMPANIES



We also make jigs, tools, drill and assembly fixtures, checking gauges, plastic moulds and mouldings, etc.

Cornercroft Limited
(The Cornercroft Group of Companies)
Ace Works - Coventry
Telephone: Coventry 40561
and at 31 Clarges St., London W.1

When answering advertisements kindly mention **MACHINERY**.




why pick on us?

We're just the type for Imperial Typewriters.

They picked on us to cast the aluminium side plates for their new typewriter because they knew we'd do it quickly, cheaply and well.

Imperial Typewriters are just the type for us.

They wanted quantity production of the type of casting for which we are well equipped. If that's the type of job you want done — pick on us.



the whole in one

BRITISH DIE CASTING AND ENGINEERING CO. LTD.

EDWARD ROAD · NEW BARNET · HERTS · TEL: BARNET 9211


ALSO AT WEST CHIRTON TRADING ESTATE · NORTH SHIELDS

NORTHUMBERLAND · NORTH SHIELDS 2100



CRC37

When answering advertisements kindly mention MACHINERY.



...for higher efficiency in the foundry

The "WELWYN" Abrasive Wheel CUTTING-OFF MACHINE

FOUNDRY VERSION. Especially designed for foundry use, this machine speeds the cutting-off of runners and risers on all types of castings and is also useful for cutting bars and sections. The 12½ h.p. motor gives ample power. Spindle speed 3400 r.p.m. with a 12" dia. wheel. Capacity under the wheel is 16" and the generous table area permits large work to be handled with ease.

★ Specialists in High Grade Grey Iron and Non-Ferrous Castings in all Alloys . . .
We Welcome your Enquiries

JOHN HILL & SONS (IRONFOUNDERS) LTD.

(A MEMBER OF THE STAVELEY COAL AND IRON CO. LTD., GROUP)

ALBION STREET, WOLVERHAMPTON • PHONE 23445



For Flute Milling... STRAIGHT AND SPIRAL

WARDWELL 90FM

Automatic HYDRAULIC FLUTE MILLER

The 90FM is rigid, fast, and accurate. The spindle housing swivels to 45° for spiral flutes. Indexing from 2 to 30 flutes is automatic. Table feeds are from ⅛" to 30" per min. with rapid approach and return. The table size is 28" x 10" with 9" travel. Capacity: ⅛" to 4" diameter.

Also WARDWELL FLUTE GRINDERS

SOLE U.K. DISTRIBUTORS:



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14

Telephone WESTERN 9877 (8 lines)


Telegrams: ACCURATOOL HAMMER LONDON

Write today
for
Catalogue

THE BRITISH NORTHROP

An ultra-modern precision grinder presenting a large working surface and of very robust and rigid construction, with

- **A High Rate of Stock Removal**
- **Sensitive Controls**
- **Hydraulic Feed**



**VERTICAL
GRINDING
MACHINE
VG 2 30"x12"**



TABLE	working surface, length x width	30" x 12"
	longitudinal traverse	45"
	table speed	0-48 ft/min
	admits between table and wheel	12"
HEAD	vertical movement of wheelhead	13"
	speed of wheel	1420 r.p.m
	peripheral speed of wheel	4750 ft/min
	diameter of wheel	12"
	movement of head per revolution of handwheel050"

Write for full particulars to—

BRITISH NORTHROP LIMITED • BLACKBURN • ENGLAND

BN 27

When answering advertisements kindly mention MACHINERY.

M


Over 500,000 in use

ACRU

NEON INDICATOR LAMPS

Are specially suitable for use on Machine Tools and Engineering Equipment because:-


- They are unaffected by vibration.
- Since they have no filament, breakages are impossible.
- They stand excess voltage up to 100 per cent.
- Normal life is more than 20 times that of filament lamps.
- Can be used direct on mains and 400-440 Volts.
- Twenty different models for every possible purpose and can be supplied from stock.
- Can be supplied in Amber, Red, Clear and Green colours
- Easily fixed, one hole fitting.



**The ACRU Electric Tool
MANUFACTURING CO., LTD.**

Acru Works, Demmings Road,
Councillor Lane, Cheadle, Cheshire

Telephone: GATley 4050



ARBOGA VERTICAL MILLING MACHINE MODEL EM 825

Fills an outstanding requirement for small work.

- Table, 17 $\frac{1}{2}$ in. by 9 $\frac{1}{2}$ in. or 22in. by 9 $\frac{1}{2}$ in.
- Longitudinal traverse, 11in. or 15 $\frac{1}{2}$ in.
- Eight speeds, 100 to 2,900 r.p.m.
- Table to Spindle 20in.
- Swivelling head, Rigid Column, Cast-iron base, No. 3 Morse Taper, 1in. bore.
- Price: £265, table, £277 10s., 22in. table.


DISTRIBUTORS AND STOCKISTS FOR THE UNITED KINGDOM.



Showroom & Sales: 204-206 Acton Lane, Harlesden, N.W.10. Tel. ELG 3834

OUTSTANDING IN VALUE AND PERFORMANCE

- Table - 25in. by 6in.
- Table travel - 15in.
- Cross feed - 5 $\frac{1}{2}$ in.
- Vertical feed - 11in.
- 12 spindle speeds from 50 to 1,650 r.p.m. Full range of accessories can be offered.
- Price including standard motor. Brook Push-button starter, suds pump and cutter arbor - £316



'SENIOR' MODEL MI. MILLING MACHINE

- For full particulars write to manufacturers
- T. SENIOR, ATLAS WORKS, LIVERSEDGE, YORKS

When answering advertisements kindly mention MACHINERY.



... it must be a standard plain cylindrical bearing which doesn't need oiling

In conditions where maintenance for lubrication is difficult or undesirable, the use of Reservoir sintered-metal oil-retaining bearings ensures that oil is fed automatically by capillary action direct


to the bearing surface. There are shapes and sizes of Reservoir bearings for every normal medium duty, and most sizes of plain cylindrical bearings to B.S.I. standard dimensions are held in stock.

... you should

specify

Reservoir

Sintered-Metal OIL RETAINING BEARINGS



Please write or 'phone for Technical Brochure SD.40 or Catalogue of sizes SD.58

THE MORGAN CRUCIBLE CO. LTD., WANDSWORTH WORKS, POINT PLEASANT, LONDON, S.W.18
VANdyke 6422

SM 122 A

When answering advertisements kindly mention MACHINERY.

M★

Five steps to
Prosperity

Intensified
MECHANISATION

Renewed
EQUIPMENT

Increased
PRODUCTION

Improved
TRANSPORT

Better
DISTRIBUTION

All these call for more **CAPITAL**
which Equity plans will provide.

**EQUITY
CREDIT**

COMPANY LIMITED

INDUSTRIAL BANKERS


24 Berkeley Square, London, W.1

Telephone: MAYfair 9090

Midlands Office:

88/89 Darlington Street, Wolverhampton, Staffs

Telephone: Wolverhampton 26545




From
1 oz to 1 cwt

When the call is for Grey Iron Castings, Henley Foundries can answer it . . . Swiftly, Economically

- Good Machining Properties • High Dimensional Accuracy
- First-Class Finish and Appearance • Repetition Work a Speciality

HENLEY FOUNDRIES

All enquiries to: HENLEY FOUNDRIES LTD., BANNER'S LANE, CRADLEY, CRADLEY HEATH, STAFFS. PHONE: CRADLEY HEATH 66901



**Quality
turned
parts**

- ★ All Materials—Stainless & High Tensile Steel, Nylon, Tuinol, etc.
- ★ Small Gears—Spurs, Sprockets, Ratchets, Bevels, etc.
- ★ Grinding, Heat Treatment, Plating.
- ★ 50-5000 Quantities a speciality
- ★ All enquiries promptly handled
- ★ A.I.D. approved, On M.O.S. Lists.

S.M.E.C. LIMITED 

STEYNING • SUSSEX • ENGLAND Phone STEYNING 2228


When answering advertisements kindly mention MACHINERY.

MARTONAIR

STANDARD AIR CYLINDERS

**REDUCED
PRICES**

**STOCK
DELIVERIES**



**IMPROVED
PERFORMANCE**

STANDARD FEATURES

Light alloy end covers and manganese bronze bearing housing.
Steel-backed lead-bronze bearing bush.
Precision ground steel piston rod.
Fully adjustable cushioning.
Wide choice of mountings.
Specially finished seamless steel tubing.

TO SPECIAL ORDER


Non-ferrous cylinder barrels available up to 4in. bore. Piston rod wiper seals.

RANGE FROM 2in. to 8in. DIAMETERS
STOCK STROKES 3in., 6in., 9in. and 12in.
ANY OTHER STROKES AVAILABLE


MARTONAIR LIMITED

PARKSHOT • RICHMOND • SURREY • ENGLAND


TELEPHONE : RICHMOND 2201 (6 lines)




FLANGE MOUNTING
B




SIDE MOUNTING
C




REAR
TRUNNION MOUNTING
D




CENTRAL
TRUNNION MOUNTING
H



FRONT
TRUNNION MOUNTING
K



REAR
HINGE MOUNTING
L



FRONT
HINGE MOUNTING
M

MANUFACTURERS OF PNEUMATIC HOISTS • CYLINDERS • CONTROL VALVES AND ACCESSORIES

When answering advertisements kindly mention MACHINERY.

AD.41
M2★

Precision Castings for every Industry



PRESSURE DIE CAST
in
High Tensile
Zinc

GRAVITY DIE CAST
in aluminium

ADOF

THE ALUMINIUM BRASS & DIECASTING FOUNDRY LTD
14-15 GASKIN STREET · ISLINGTON
LONDON · N1 Phone CANONBURY 7141/2

LINK-V



FASTENER

is suitable for
ROLLS OF SOLID CONSTRUCTION V-BELTING
Patent No. 749362 and others

- ★ M, A, B, C, P & D sections available.
- ★ BELTING supplied in 50ft. and 150ft. rolls.
- ★ QUICKLY FIXED. Any size of belt made up in a few minutes.
- ★ EASILY DETACHABLE. Belt can be shortened and fastener used again.
- ★ STRONG JOINT. Indefinite life of joint by replacing oil impregnated bronze bushes.

FLEXICON LTD.
NORTH WING MILLS · BRADFORD · YORKS
PHONE: 23941

Write for fully descriptive leaflet.

CUT COST-SAVE TIME-SPEED PRODUCTION

UNIVERSAL DRILLING JIG
'REGLUS'


THE 'REGLUS' Drill Jig is designed to simplify and rationalise present-day drilling practice.

The measuring, straightening and trial-drilling operations hitherto necessary, the marking-out and centre-punching of the work, and the production of expensive special-purpose jigs, are all dispensed with.

The 'REGLUS' can be adapted to any individual drilling job in a matter of seconds and may be set directly from any blueprint with the greatest of ease.

It can be used whether the workpiece is cylindrical, square, rectangular, multi-angular, spherical or flat. It enables accurate drilling on prototype toolroom work and on batches of components.

The vernier settings ensure complete accuracy for a multiplicity of jobs which could otherwise only be obtained with individual special-purpose jigs.

**FRED FERRARIS (CLERKENWELL) LTD.**

18 NORTHAMPTON SQUARE, LONDON, E.C.1

Telephones: CLERKENWELL 2676/7

TOOLING SERVICE

★
Designers & Manufacturers of
JIGS · FIXTURES
PRESS TOOLS
GAUGES · MOULDS
and
SPECIAL PURPOSE MACHINES

★
RATCLIFFE
TOOL Co. Ltd.

GORST ROAD, LONDON, N.W.10.

Telephone: ELGAR 6693

and at
COED COCH RD., OLD COLWYN, N. WALES

Tel: COLWYN BAY 55288


A.I.D.
ApprovedA.R.B.
Approved

When answering advertisements kindly mention MACHINERY.

Useful little book

... for the steel buyer,
the tool room manager,
the production engineer —
in fact anyone who has
to use or order tool and
high speed steels.
"Sanderson Steels"
describes our standard
range and illustrates
typical applications.

Write for a copy



When answering advertisements kindly mention MACHINERY.



foot lever PRESSES

Specially designed for high output with unskilled labour. Foot operation leaves operator's hands free for manipulation of the workpiece. Supplied for bench or stand mounting.
PROMPT DELIVERY.
Ask for details.

ASK FOR CATALOGUES OF COMPLETE RANGE OF DIAL GAUGES, PRESSES AND DRILLING MACHINES
GENEROUS TERMS TO MERCHANTS

MANUFACTURED SOLELY BY

ENGINEERING PRODUCTS LIMITED

GLENBROOK WORKS, LITTLERS CLOSE,
MERTON ABBEY, LONDON, S.W.19

Telephone: LIBERTY 1085 & 1086

ESSEX UNIVERSAL JOINTS

'W' TYPE

Manufactured in a range of 14 sizes from $\frac{1}{8}$ in. to $2\frac{1}{2}$ in. It is suitable for machine tool applications where backlash has to be kept to a minimum and space is limited. Prices and technical data on application.



THE MOTOR GEAR & ENGINEERING CO. LTD.

ESSEX & CORONA WORKS - CHADWELL HEATH - ESSEX - Phone: Seven Rovers 3456-7745 (10 Lines)

Die Sinking

FOR THE RUBBER, GLASS, AUTOMOBILE
AND AIRCRAFT INDUSTRIES

SCANNING PROFILING & ROTARY FORMING

From customers' own models, castings
or materials if desired

CAPACITY UP TO 26" x 34" or
48" x 15" area or 24" dia. x 30" high

JIGS TOOLS & FIXTURES

SPECIAL MACHINES
WOOD METAL & PLASTER
PATTERNS & MODELS

DROP HAMMER & DRAWING TOOLS

For the Aircraft and Automobile Industry
by precision cast-to-form methods in
Cast iron and Zinc base alloys

CASTINGS OF ALL TYPES
(EXCEPT STEEL)

FINCH WATSON LTD
ACCRINGTON Phone: Accrington 5238/9

When answering advertisements kindly mention MACHINERY.



ENGINEERS' PRECISION TOOLS



No. 902 ADJUSTABLE INSIDE MICROMETER cap 2" - 8", is supplied complete with micrometer body, extension rod, distance piece, and extension handle in a velvet-lined instrument case.



No. 941X ADJUSTABLE MICROMETER, cap 0" - 4" supplied complete with setting rods, adjustable anvils and adjusting keys in fitted wooden box.



No. 961 MICROMETER cap 0" - 1" is pearl chrome plated for easy reading and manufactured to British Standard Institution Specification. Supplied with setting key in new spring-hinged box.



No. 1021 SET OF MICROMETERS, containing 1 each Micrometers Nos. 961, cap 0" - 1", 966/2" cap 1" - 2", and 966/3" cap 2" - 3"

MEASURE UP TO ANY JOB

The next time you buy tools, remember that it pays to buy good tools, tools upon whose accuracy you can rely.

The next time you buy tools, specify **(M&W)** tools—YOU CAN RELY ON THEM.

SEND 10½d. IN STAMPS FOR A COPY OF OUR LATEST CATALOGUE, MENTIONING THIS JOURNAL.

MOORE & WRIGHT (Sheffield) LTD., 14/28 NORTON LANE, SHEFFIELD, 18.

When answering advertisements kindly mention MACHINERY.

could you use the skill

Rotheroe & Mitchell Ltd., have expert facilities for the development, design, tooling and testing of all types of equipment, including electronic apparatus.

If you are having difficulty in meeting delivery promises, why not take advantage of our service, after all sub-contracting has been our business for 21 years.

of 100 engineers?

There is no reason why you shouldn't. That is the experience and skill you have at your service when you contact Rotheroe & Mitchell Ltd., and that is a very sound move if you are concerned with the making of precision components from bar or castings, or the manufacture and assembly of complete equipments in the Instrument and Electro-Mechanical field.

Write or telephone for further details today.

ROTHEROE & MITCHELL LTD

Electrical and Mechanical
Instrument Makers

Aintree Road, Perivale, Middlesex Tel: PERivale 2238-9

Fit the thread to the job!

Makes soft threads hard
Gives new threads for old

Made in high carbon
steel for use in
aluminium and
magnesium . .
also in stainless
and bronze for
other applications



Details and samples on request—
CROSS MANUFACTURING CO. (1938)
Ltd.

BATH, SOMERSET. Tel. Combe
Down 2355-8
Grams: Circle BATH

SPECIALISTS IN THE MANUFACTURE OF JET ENGINE LABYRINTHS, CIRCLIPS, SPRING WASHERS, SPRINGS, ETC.

CROSS
THE BRITISH
WIRE THREAD
INSERTS




A.I.D.
D.I. Arm
A.R.B.
Approved

PRECISION
Engineers

Capstan auto and centre lathe turning
Horizontal and vertical milling
Drilling and tapping
Centreless surface and internal grinding
Case-hardening and stove enamelling
Own Design and Drawing Office,
Toolroom and Experimental Department
**Machining specialists in stainless and
various high tensile steels**

SCREW MACHINE PRODUCTS LTD
Wooburn Green · Near High Wycombe · Bucks
Telephone: BOURNE END 111

"Over 80% of our material goes through the CUT-OFF DEPT. Will horizontal bandsawing reduce waste and give faster floor to floor times. ?"



Yes, if it's a *STARTRITE* Meba

ACTUAL EXAMPLE

MATERIAL

5in. diameter 18 per cent. Tungsten Content, H.S.S. Bar Stock. (Price 6/4d. lb.)

OPERATION

Cut off into blanks for special cutters.

MACHINE "Startrite-Meba"

Time per cut ... 20 mins.
Material Wastage per cut ... 0.825 cut ins.
Tool Life ... 120 cuts
Finish: Suitable for second operation, Surface Grinding.

PREVIOUS METHODS

Time per cut ... 35 mins.
Material Wastage per cut ... 1.6 cut ins.
Tool Life ... 8 cuts
Finish: Second operation Lathe Face unsuitable for Surface Grinding.


MATERIAL SAVING OVER 120 CUTS

Chip Waste ... £8.0.0
Tool Costs ... £6.0.0
Time ... 30 hours

HORIZONTAL CUT-OFF BANDSAW

Capacity up to 12½in. round and square bar—sections up to 17½in. wide. Infinitely variable cutting speeds from 46 to 230 ft./min.

Rapid stock handling through high speed vice clamp lever and automatic swivel end-stop. Wet or dry cutting.



FOR FURTHER INFORMATION

PLEASE WRITE TO:

THOS. P. HEADLAND LTD

MELON ROAD, LONDON, S.E.15

Telephone:
NEW X 4300

Telegrams:
Teepatch, London S.E.15

When answering advertisements kindly mention MACHINERY.



4, 5 and 6 Tool Stations
Collets, Chucks, Tapping Head, Turret Depth Stop, Pre-selector Variable Speed Drive
EMBASSY MACHINE & TOOL COMPANY LTD.


248, Watford Way, Hendon, London, N.W.4.

Phone: SUNnyhill 2829

CONTINUOUS FILING

speeds production

Size of table 20in. by 20in.
 Depth of throat 18in.
 Cutting speed 5 speeds
 Range 9 to 44 m/min
 Smallest hole for introducing the file chain 1/16in.
 Power required approximately 0.75 H.P. 220/380 Volts
 Table inclinable 20° forward 15° back
 Three widths and sections of band file may be used 1/16in., 1/8in., 1/4in. rough medium or fine cut



The new
GROB

(MODEL F.A.B. 18)

BAND FILING MACHINE

FISHER DEANE ENGINEERING CO LTD

HOWARD CLOSE - HAMPTON - MIDDX Tel: MOLney 2612

MARLCo

MINOR INDEXING ATTACHMENT



EX STOCK DELIVERY

... Standard index plate of 12 divisions.
 Special plates up to 20 divisions. Supplied with collet mounting and interchangeable 5 1/2in. table
 Standard collets 1 1/2in.-1 1/4in. by 3/8in. dia., specials on request. Can be locked in any position.
 LARGER ATTACHMENT ALSO AVAILABLE

W. H. MARLEY & CO. LIMITED

NEW SOUTHGATE WORKS, 105 HIGH RD., LONDON, N.11

TELEPHONE: ENTERprise 5234 5578

HARRIS

PATENT

FLOATING REAMERS

- Micrometer adjustment to 0.0005 in.
- Variable float unaffected by adjustment
- Maximum support for cutters
- Rigid positive locking

8 Sizes for holes from 1in. to 4 1/2in. dia.
 Ask for fully descriptive leaflet

F. & T. KITCHIN VICKERSDALE WORKS
 STANNINGLEY, PUDSEY, YORKSHIRE

SOCKET HEAD SCREWS

PROMPT DELIVERY OF ALL STANDARD SIZES

SEND FOR LIST Telephone: LEYLAND 81202

OLIVERS SOCKET SCREWS LIMITED,

MOUNT PLEASANT · LEYLAND · LANCASHIRE




When answering advertisements kindly mention MACHINERY.

TILLING—STEVENS PROLONG FATIGUE LIFE BY SHOT PEENING


Here is a less publicised but most important application of the Wheelabrator Airless Shot system. The operation is shot peening, the component, the rocker arm of a 3 cylinder 2 stroke diesel engine; and the process: treating the inner arches so as to strengthen the outer fibres against direct stresses. Messrs. Tilling Stevens Ltd., of Maidstone extend the fatigue life of these highly stressed components by submitting them to 3 minutes under a blast of S.320 cast steel ball shot. Much research has proved the superiority of Wheelabrator cast steel ball shot for many such processes and adequate stocks are carried to offer immediate delivery of all grades.



TILGHMAN'S ROTARY TABLE AIRLESS WHEELABRATORS



ALSO
WHEELABRATOR
STEEL SHOT
FOR
IMMEDIATE DELIVERY
IN ALL GRADES



TILGHMAN'S LIMITED

A member of the Stavley Coal & Iron Co., Ltd., Group

BROADHEATH · ALTRINCHAM · CHESHIRE

LONDON OFFICE: 1 CHESTER STREET, S.W.1

AGENTS:

MIDLANDS: R. J. Richardson & Sons Ltd., Commercial Street, Birmingham.

SCOTLAND: Baird & Co. Limited, 227 Bath Street, Glasgow, C.2
110 Hanover Street, Edinburgh, 2

NORTHERN IRELAND: W. E. Stewart Industrial Services Ltd.,

16 Sussex Place, Belfast

W145

When answering advertisements kindly mention MACHINERY.

THE FOURTH DIMENSION

... tells all !

Space/time ? In a casting, or a forging, a tiny space unfilled will destroy, if it is not found in time. Member Companies of the Birfield Group were some of the earliest in this country to install regular X-ray examination of their products as the 4th dimensional check on the quality of their productions. Up-to-the-minute methods are part of the secret of Birfield Group success. Every Member Company of the Group is backed by the resources—manufacturing and technical—of every other company in the Group.

Forgings for high-stress components

through the **Birfield Group**



BIRFIELD INDUSTRIES LTD
STRATFORD HOUSE LONDON W1

ARBOGA

GEARED HEAD
1" PILLAR DRILL

12 SPEEDS
200-3600 rpm

As illustrated **£131.0.0**
With circular
table **£115.0.0**

DISTRIBUTORS AND STOCKISTS
FOR THE UNITED KINGDOM

MORTIMER ENGINEERING
PROPRIETORS COMPANY & SUBSIDIARIES LTD

Showroom & Sales: 204-206 Acton Lane, Harlesden, N.W.10. Tel. ELG 33' 4

When answering advertisements kindly mention **MACHINERY**.

MARLOW

Mk. IV VERTICAL
MILLING MACHINE

- ▶ SWIVELLING AND DOWN FEED HEAD
- ▶ LARGE CAPACITY
- ▶ TABLE 28" x 8"
- ▶ 6 SPEEDS 85 to 1450 r.p.m.
- ▶ SPINDLE TO TABLE 20"
- ▶ HEIGHT 80"

MARLOW Models

MK IV (Illustr.) £285

MK I 22" x 6" £198


MK II 28" x 6" £210

MK III 28" x 8" £225

VICTA ENGINEERING CO

Offices:
Thicket Corner, Maidenhead
Tel 50 and at: Eagle Works,
Chester Rd. Boreham Wood,
Herts.

Tel: Elstree 3146



Special Purpose Machines

S&B

We now have facilities for designing and manufacturing Special Purpose Machines from our standard lathes. Air, Hydraulic or Mechanical Operation.

SMART & BROWN (Machine Tools) LTD.

25, MANCHESTER SQUARE, LONDON, W.1.

Telephone: WELbeck 7941/6

A.W. NEWMAN & SONS LIMITED

Prompt
REPAIRS
TO ENGINEERING
MEASURING AND
TESTING
INSTRUMENTS

Phone: PARK 6946
152a Holland Park Ave., London, W.11

The Complete PLATING SERVICE

ACTION Factory

Decorative Nickel and Chromium Plating. Specialising in high quality work.

"ATLAS" SATIN CHROME

Has now been well established as the ideal finish for Camera and Instrument parts. It has a pleasing colour which is durable, untarnishable and easily cleaned. A separate department ensures careful handling of delicate parts.

HARD CHROME

A well-equipped department for handling large or small quantities of components or parts requiring Hard Chrome deposits ranging from 0.001in. to 0.030in. Heavier composite deposits also undertaken.

TIN-NICKEL

An alloy deposit, matt or polished, capable of withstanding a variety of corrosive agents.

"ATLAS" ELECTRO BLACK

This finish is considered superior to black nickel and can be produced on any plateable metal in either matt, semi-bright or a fully polished finish.

CENTRELESS POLISHING

A mechanical method of polishing tubes up to 6 inches in diameter, showing a saving on hand polishing methods.

ANODISING (plain or colour), PHOSPHATING, CADMIUM, TIN, ZINC, BRASS, SILVER AND RHODIUM, POLISHING AND LACQUERING

A.I.D., A.R.B., & I.A. APPROVED

ATLAS PLATING WORKS LTD.

ATLAS WORKS : AVENUE ROAD

ACTION : LONDON : W.3

TELEPHONE : : ACORN 1102 (3 lines)



BATTERSEA Factory —BARREL PLATING

The largest Barrel Plating Unit South of the Midlands for

CADMIUM, ZINC, TIN, SILVER, BRASS, BARREL BRONZING AND LACQUERING.

BARREL CHROMIUM

For plating large quantities of small articles, showing a saving on hand polishing and wiring.

ROTOFINISH PROCESS

A mechanical method of metal polishing and deburring where a mirror finish is not essential, usually showing a saving of 50% to 80% on costs by eliminating hand polishing. Its controlled action removes burrs, sharp corners to close tolerance so that even precision machined parts can be processed in quantities.

SEMI-AUTOMATIC

Nickel/Chrome unit for mass production of small parts.

"ALTAS" CHEMICAL BLACK FINISH

Atlas chemical black is a cheap yet satisfactory finish for all types of STEEL Pressings, tools, automobile and cycle components, bolts, nuts, screws, washers, and the multitude of other items generally associated with the engineering industries. The finish can be used for a number of purposes and is at the same time both decorative and protective.

A.I.D., A.R.B., & I.A. APPROVED

ATLAS PLATING WORKS LTD.

ATLAS WORKS : 8-10 INGATE PLACE

QUEENSTOWN ROAD : LONDON

S.W.8

TELEPHONE

: MACAULEY 2976



ATLAS

When answering advertisements kindly mention MACHINERY.

WE HAVE THE 'MEASURE' OF Porosity

Porosity in metal has always been a problem, but to-day its effects can be extremely serious especially in castings used in Aircraft, Electronic and Nuclear equipment. A casting containing microporosity, is not necessarily structurally unsound, and impregnation of the casting by the latest resins can render it "as new". Even a casting that has had many hours of machining time spent on it before the effects of porosity are noted, can be reclaimed—and what is so vital, the fine tolerances are completely unaffected by impregnation. The process is inexpensive and there is no limit to the size of casting that can be treated. For castings used in equipment where safety is of prime importance, they can be impregnated thereby ensuring that they are perfect and entirely safe from porosity. Such impregnation is demanded for certain Nuclear and Electronic equipment. Please write for full details or let us send one of our experienced engineers to your Works.

Approved by Admiralty, M.O.S., A.I.D., A.R.B.

INDUSTRIAL IMPREGNATIONS LTD.

THE LARGEST IMPREGNATING ENGINEERS IN EUROPE

HEAD OFFICE & FACTORY:

9, WILLOW ROAD, POYLE ESTATE, COLNBROOK, Bucks.

Telephone: Colnbrook 2086/7

BIRMINGHAM

14-16 Port Hope Road,
Sparkbrook, Birmingham, 11.
Telephone: Victoria 5312.


OVERSEAS:

Impregnaciones Industriales S.A.
Madrid & Barcelona.

OLDHAM

45, Roscoe Street,
Telephone: Main 5350.

RAYNER POWER DRIVES



Infinitely Variable

2 H.P. varigear
40 to 200 r.p.m.

**COMPACT PURPOSE-MADE
POWER DRIVES ARE OUR BUSINESS
PETER RAYNER LTD**

121 WHITEHALL RD · LEEDS 12 TELEPHONE: LEEDS 33844

Maher...

a name to remember when disposing
of your surplus stocks of
HIGH SPEED & ALLOY STEEL BARS

ALSO
**TUNGSTEN MOLYBDENUM
NICKEL TITANIUM**

**COBALT
SCRAPS & RESIDUES**

HIGHER PRICES FROM THE SPECIALISTS

J. W. MAHER & SON LTD.

Scrap Department, Edward Street, Sheffield 3, England
Phone: Sheffield 27976 Cables: Jomah, Sheffield

absterge (to clean by wiping)

Austins supply the best cleaning rags for every purpose. Some jobs call for coarse, heavy fabric some for soft, closely woven materials—we can meet all requirements with carefully selected rags that are thoroughly washed and sterilized in our own plant. Orders of all sizes are handled with promptness and reliability. Please let us quote you for regular supplies.

AUSTINS industrial cleaning rags

E. AUSTIN & SONS (LONDON) LTD. GUN WHARF
Gunmakers Lane · E.3 · Tel ADVance 1211



When answering advertisements kindly mention MACHINERY.

** At this moment*

THE *British* **VARIABLE SPEED UNIT**

IS IMPROVING MACHINE PERFORMANCE
IN ALL THESE INDUSTRIES . . .


PAPER MAKING
PRINTING
CARDBOARD
MAKING
MECHANICAL
HANDLING
RUBBER
MANUFACTURE
PLASTICS
TEXTILES
DYEING

MACHINE TOOLS
PETROLEUM OIL
SOAP WORKS
WELDING
BISCUIT MAKING
BREWERY
MACHINERY
FOOD
PROCESSING
SUGAR REFINERY
FOUNDRY

CHOCOLATE
REFINERY
CABLE
MANUFACTURING
WIRE-DRAWING
CERAMIC
INDUSTRY
COLLIERIES
INDUSTRIAL
HEATING
CHEMICAL PLANT

SLIP PROOF
CONSTANT
SPEED HOLDING

NOTE THE
COMPACT
STURDY
CONSTRUCTION



SEVEN STANDARD
SIZES INPUT SPEED
1,430 R.P.M.
INFINITELY VARIABLE
OUTPUT SPEEDS
UP TO 1,800 R.P.M.
POWER OUTPUT FROM
0.15 TO 18 H.P.
ACCORDING TO SIZE.

Write today for full details to

F. U. LONDON LTD.

WRENCOTE HOUSE,

119/121 HIGH ST., CROYDON, SURREY

TELEPHONE: CROYDON 8296

THESE
TOOLS
PRESS
THE MAIN
COMPONENT
FOR THE
**MORRIS-
OXFORD
RADIATOR
GRILLE**


AND ARE
MADE IN

NARITE
The **DIE METAL
SUPERB**

WRITE FOR A COPY OF THE
2nd (REVISED) EDITION OF
OUR BROCHURE AND FULL
TECHNICAL INFORMATION.


N. C. ASHTON LTD.
ST. ANDREW'S ROAD,
HUDDERSFIELD, ENGLAND.
TEL: HUDDERSFIELD 6263/4.

NO PICK-UP
WRINKLING
OR GALLING



PHOTOGRAPH BY COURTESY OF:-
MESSRS MORRIS MOTORS LTD. (RADIATORS BRANCH) OXFORD
CW 3312

When answering advertisements kindly mention MACHINERY.



A.B.C. 4-WAY TOOLPOST ACCURATELY INDEXING

Supplied to suit any make or size of lathe.
Can be locked in any position regardless of Index.

Sole Manufacturers: **A. B. CREED LTD.**
Little Ilford Lane, London, E.12. Tel: Ilford 0455

London Stockists: Acbars Ltd · Buck & Hickman Ltd · Buck &
Ryan Ltd · George Hatch Ltd · Richard Melhuish (London Ltd)
Pander Engineering Supplies Ltd · Pidgen Bros. Ltd
A. H. Ritchie & Co.



**BUT IT'S
BETTER TO
INSTALL UDAL
PRESS GUARDS**

Many a pressworker exposes himself to danger because the guard slows him down, irritates him, frustrates him. That's one good reason for fitting Udal 'Fastrip' guards. Guard and clutch are synchronised to ensure split-second timing, allowing the highest standard of safety without impeding production. Send for details today.

J. P. UDAL LIMITED

INTERLOCK WORKS,
COURT ROAD,
BIRMINGHAM, 12
Phone: CALthorpe 3114

Udal
PRESS GUARDS

These PARALLEL ACTION Pliers are FIRM FAVOURITES with all TRADESMEN

END CUTTING
NIPPER
No. 301



FLAT NOSE
PLIER
No. 406



SIDE CUTTING
PLIER
No. 405



CLAMPING
PLIER
No. 479



SNIPER NOSE
PLIER
No. 433



MAUN INDUSTRIES LIMITED MANSFIELD, NOTTS.

STEEL FABRICATION SPECIALISTS

—GUILLOTINING—ROLLING—
—PROFILING—WELDING—
—MACHINING—

CoFIDE
ENGINEERING LTD.
EMPIRE WORKS, 163 CLARENCE STREET,
KINGSTON-ON-THAMES

Telephone: KINGston 6820

"COVENTRY"

WET TOOL GRINDER

Specially designed for tungsten carbide tools: one wheel for roughing and one for finishing. Large diameter ball-bearing spindle. Sturdy construction throughout, with self-contained motor drive as shown.

Write for full details.

CENTAUR TOOL WORKS

EYRE ST., SPRINGHILL BIRMINGHAM

Phone EDEBASTON 118/9. Grams CAPTAN BIRMINGHAM



now
on the press
MACHINERY'S
 ANNUAL
Buyers' Guide
1959
 EDITION

the
 standard
 reference
 book
 for
 buyers
 of all
 plant
 equipment
 and
 materials
 for
 engineering
 shops

1000 pages giving the
 names, products and
 trade names of over
 4000 firms

**order your
 copy now**

Available JANUARY 1959

TO MACHINERY (Book Department)
National House, West St. Brighton

Please send a copy of MACHINERY'S
 ANNUAL BUYERS GUIDE (30th edition)
 on publication. Price 12/6 post free

NAME _____



SIGNATURE _____

ADDRESS _____

DATE _____

QUALITY CONTROL

of pressure die castings



Maintaining the correct chemical analysis of die casting alloys, particularly with regard to impurity limits, is of paramount importance in the production of high quality die castings. Our Laboratory is equipped with one of the few direct reading spectrographs in use in this country.

As a result the requirements of the B.S.I. Certification Scheme for zinc alloy die castings are far exceeded. Every melt is analysed and the holding furnace of every machine is checked for impurities at least once per shift, enabling any variance from specification to be quickly identified.

With the utmost confidence, we can therefore claim to supply castings of the highest quality. *Quotations, without obligation, from drawings, specifications or samples.*



BS 1004

**PRESSURE DIE CASTINGS in
 ZINC, ALUMINIUM AND SOFT ALLOYS**

SPARKLETS LIMITED

DIE CASTING DIVISION

TOTTENHAM, LONDON, N.17

When answering advertisements kindly mention MACHINERY.

How important is SURFACE FINISH CONTROL?



Are your Draughtsmen, Foremen, Inspectors and Machinists surface finish conscious? If so, your products will have a high reputation; if not, your products will not be classed as high quality. "RUBERT" Surface Roughness Scales provide a reference of calibrated Surface Roughness for comparison of machined surfaces by sight and touch and fulfil the need for a simple, dependable standard for visualising, selecting and specifying surface conditions for production work.

Whether you have electronic instruments to test Surface Roughness or not, your Draughtsman always needs Surface Roughness Standards to enable him to specify the required surface finish, and the Machinist cannot be without these because he must always have a comparison handy to tell him whether the finish is good enough, not good enough, or too good.

"RUBERT"

Surface Roughness Scales

are used by hundreds of the most prominent British Firms

ASK FOR LEAFLETS

**RUBERT & CO. LTD., Chapel St.
Acru Works Demming's Road
Councillor Lane CHADLE CHES.**

Telephone : GATley 6058

Subsidiary of the ACRU Electric Tool Mfg. Co. Ltd.



PRECISION TOOLMAKING & ENGINEERING

**SPECIAL
PURPOSE
MACHINES
JIGS · FIXTURES
PRESS TOOLS
MOULDS
DIES
GAUGES**

SHIRLEY
TOOLS & ENGINEERING
LIMITED

*Immediate Capacity
Prompt Delivery*

1-3 ELGIN ROAD
SOUTHAMPTON
Telephone: 21881

REMEMBER!

TAL

for

**PRESSURE
DIECASTINGS**

**ZINC B.S. 1004 OR ALUMIN
LARGE OR SMALL**

Enquiries to
T.A.L. DEVELOPMENTS LTD.
BROADWATER WORKS, GARMAN ROAD, TOTTENHAM, N.17
TELEPHONE : TOTTENHAM 2722/3

When answering advertisements kindly mention MACHINERY.

CLASSIFIED ADVERTISEMENTS

RATES : PLAIN ADVERTISEMENTS Except "Situations Wanted" (ALL TYPE) : 2/2 per line. MINIMUM 8/8 (4 lines) OR £1 8s. 2d. per inch (13 lines per inch). Box Nos. 1/3 extra per insertion. SITUATIONS WANTED : 1/8 per line. MINIMUM 6/8 plus 1/3 Box No. SPECIAL DISPLAY TYPE (with or without Blocks) : ½ p. £1 10s.; ¼ p. £3; ¼ p. £6 or £2 per inch (min. ¼ in.). Series rates on request.

CONTRACT WORK

...DESIGNS...

PRECISION PRODUCTS (ROMFORD) LTD.

TOOL DESIGNERS
AND MANUFACTURERS

For all your needs

IN
JIGS · FIXTURES
GAUGES · PRESS TOOLS
FORM TOOLS AND
SPECIAL MACHINES



Viking Works, London Rd.,
Romford, Essex. Tel : Romford 61991/2

ENGINEERING
DESIGN
SERVICE

DESIGNING OF
GENERAL & SPECIAL
MACHINES
DRAFTING
DETAILING

DAVID L. EVANS (Research) LTD
56 Kingsway, London W.C.2.
Hallowell 4968


DEVELOPMENT
AND
PROTOTYPE WORK

WE DESIGN

AND MANUFACTURE
PRESS TOOLS
AND DO THE
PRESS WORK

A.I.D. & A.R.B. APPROVED

NAISH BROS. & CO. LTD.
124, CHELTENHAM ROAD,
BRISTOL. Tel.: 25532-3



PRESS TOOLS

LAMINATIONS—COMBINATION—PROGRESSION, ETC.

**JIGS—FIXTURES—PROTOTYPE and
PRE-PRODUCTION MACHINING**

Designing—Short Order Work—Sub Assemblies Completely Toolled

**JIG BORING AND PRECISION GRINDING
LANDEN (ENGINEERS) LTD.**

1a, Aubert Park, Highbury, London, N.5
Phone : CANbury 1075

Presswork Up to 50 Tons, In-
cluding deep drawing. Long or short runs.
Customers' tools and materials acceptable.
Tooling and designing.—BIRCH & JACQUES
(TOOLMAKERS), LTD., Hesham Trading
Estate, Walton-on-Thames. Tel.: W-on-T 5370.

Die Casting Moulds Designed
and detailed ready for manufacture.
Components redesigned to suit production by
casting.—Apply A. V. KELLY, Phone: Waltham
Cross 2863.



when you are on the carpet

—take 'ABBEY' ASPIRIN

... AND SOLVE ALL YOUR
DESIGNING PROBLEMS

Let us relieve your troubles with our rapid and competitive design and manufacturing services. We specialise in transfer and special purpose machines, auto tooling, jigs and fixtures, press tools, plant layout and factory services.

Members of the Federation of Engineering and Design Consultants

THE ABBEY TOOL CO. LTD.

CHURCH HILL · COLESHILL · BIRMINGHAM · TEL : COLESHILL 3276
109 FISHERGATE · PRESTON · LANCs · TEL: PRESTON 2309

● **ENGINEERING BUYERS NEED MACHINERY'S ANNUAL BUYERS' GUIDE**

When answering advertisements kindly mention **MACHINERY**.

N

Classified Advertisements (CONTRACT WORK, contd.)



TOOL DESIGNERS & MANUFACTURERS

JIGS, FIXTURES,
PRESS TOOLS, SPECIAL
PURPOSE MACHINES
JIG BORING & PROTOTYPE
WORK

TARGET ENGINEERING LTD.

NORTHFIELD ROAD, COVENTRY

Telephone: Coventry 22254 and 22080



W.R. SOUTHWELL (DESIGNS) LTD
30 ST. DUNSTONS HILL, CHEAM
SURREY • Phone: FAIRLANDS 3617 & 7548

DESIGN & PLANNING

PRESS TOOLS
JIGS & FIXTURES
SPECIAL PURPOSE M/C'S
DIECASTING MOULDS
PLASTIC MOULDS
PIPING, DUCTING, ETC

Export Enquiries Invited

GEARS

Gears, All Types, Production or
replacement, spurs up to 36in. dia. Your
blanks or ours.—SPREADBOROUGH ENG'G.
LTD., 30, Heath Street, N.W.3. HAM 8937.



SMALL GEARS

ALL TYPES OF SMALL GEARS

UP TO 8in. DIA. 10 to 64 D.P.

ESTABLISHED IN 1880

G. W. EVERY & SONS, LTD.

49, THORNHILL RD., LONDON, N.1. Phone: NORTH 1827

GEARS We are Specialists

Experienced Gear cutters at your service
No need to let a gear problem stamp you
Expert knowledge is on hand
Rapid delivery from customers' own blanks
All gears cut, or made complete to your requirements
Trust your gear-cutting to us (over 30 years experience)
Every satisfaction assured
We send your enquiries, large or small, prompt attention given

F. M. ILLICH (GEARS) LTD.

4A JAMESTOWN ROAD, LONDON, N.W.1

Tel: Gulliver 5046

SPIRALS • SPURS WORMS & WHEELS • BEVELS • SPROCKETS
CAPACITY LIST ON APPLICATION



When answering advertisements kindly mention MACHINERY.

ALUMINIUM FOUNDRIES

Gravity Dies designed, manufactured and
proved. Capacity Immediate

R. E. ORMEROD LTD
Ednall Lane • Bromsgrove • Wore

CAPACITY AVAILABLE

FOR DESIGN AND MANUFACTURE OF
SPECIAL PURPOSE MACHINES

ALSO
MACHINING CAPACITY ON
CENTRE LATHES, CAPSTANS,
GRINDING, DRILLING & MILLING
MACHINES.

MOORE & ELLIS

(LONDON) 1946 LTD.

61, UNION STREET, BOROUGH, S.E.1

TELEPHONE: HOP 2504

Presswork Up to 40 Tons, Circu-
lar and surface strutting on latest J. & S.
machines. Tools designed and made for the
trade or your article produced throughout in
our works. A.I.D. approved. Enquiries
welcomed.—WEMBLEY TOOL CO., LTD.,
2, Bridge Road, Willesden, N.W.10. WIL
9607/8.



Gear Cutting Super Accurate.

Spurs and Spirals to Admiralty class one
specification. Prototype quantities. Very quick
delivery.—NEWMONT ENGINEERING COM-
PANY, LTD., Nodis Works, Julien Road,
Ealing, W.5. Phone: EALing 3924.

IMMEDIATE CAPACITY AVAILABLE

- GEAR CUTTING to 24in.
- THREAD MILLING 6in. by 40in.
- PLANING 6ft. by 2ft. 6in.
- BROACHING

MAURALL ENG. CO.

38-40, Upper Clapton Road, E.5
Telephone: AMHerst 6163.

GEARS—PRECISION AND INSTRUMENT MACHINE CUT

Max. capacity 12 D.P. 8in. dia

Blanks turned and cut.

SETON CREATION ENGINEERING LTD.,
TRADING ESTATE, PARK ROYAL ROAD, N.W.10
A.I.D. Phone ELGor 3356/7 A.R.B.

Classified Advertisements (CONTRACT WORK, contd.)

Complete production of

GEARSSPURS · SPIRALS · BEVELS
WORMS · WHEELS · RACKS
SPROCKETS & CLUTCHESExtra rapid delivery
from Customers own BlanksA.I.D.
APPROVED**THE DAVALL GEAR COMPANY LTD.**

GEARWORKS · HIGH STREET · POTTERS BAR · MIDDLESEX

Telephone POTTERS BAR 23823

**GENERAL ENG'G.
SERVICES****Immediate Capacity Available**
castings, non-ferrous, die, shell moulded, sand, etc. Also machining and stove-enamelling.—**MILLS ENGINEERING PRODUCTS, LTD.**, Barnet. Phone: Barnet 6744.**Luton Engineering Pattern Co.**
are prepared to undertake the manufacture of all classes of wood and metal patterns and accuracy and prompt delivery guaranteed.—Send your enquiries to 80A, Princes Street, Luton. Phone 961.**Immediate Capacity Available.**
Cri-dan screwing 4in. O/D, 6in. I/D, taper or Multi start. Capstan up to 2in. dia., Milling, Profiling, Turning, Drilling, Grinding. Long or short runs. Satisfaction guaranteed. A.I.D. and A.R.B. approved.—**JAMES CROLL, LTD.**, Newtown, Parkstone, Poole, Dorset. Tel. Parkstone 8598.**DAVIES-CHARLTON (U.K.) LTD.**STATION SAWMILLS, BARNOLDSWICK, VIA
COLNE, LANCs. TEL. BARNOLDSWICK 3310
A.I.D. APPROVEDAre specialists in component
production for the Aero-Jet
engine industry, and can offer
capacity on**THREAD GRINDING
THREAD ROLLING**Capstan, Auto and Centre Lathe
turning. External, internal
Centreless and surface grinding.
Horizontal, vertical and profile
milling. Drilling, Tapping and
Honing.**QUOTATIONS FOR LARGE OR SMALL
QUANTITIES****IDEAL****HARDENING CO., LTD.**

DAVIS ROAD, CHESINGTON, SURREY

**HEAT TREATMENT
SPECIALISTS****HARDENING OF
EVERY DESCRIPTION
AND SANDBLASTING**

Tel.: ELMBRIDGE 6556-6567

**IMMEDIATE CAPACITY
AVAILABLE**

Capstan Work up to 1 1/2 in. Bar

and 6 in. Chucking

Milling, Drilling, Grinding

Boring and Assembly Work

Jigs & Fixtures

Also Hardening for the Trade

A.I.D. and A.R.B. approved

B. TOONE**(NOTTINGHAM) LTD****NEWDIGATE ST.****NOTTINGHAM**

Tel.: 76661-2-3

Centre Lathe Turning Up to
7 1/2 in. centres by 48 in. b.c. Tool, Prototype
and small batch work. Modern plant. A.I.D.
approved.—**WARD ELECTRIC CO. (NOB-
WOOD), LTD.**, 44, Chapel Road, W. Norwood,
S.E.27. GIPSY Hill 1620.**CROYDON TOOL****AND CASE HARDENING SPECIALISTS****EXPERTS IN ALL HEAT TREATMENT OF METALS**

CYANIDE HARDENING · ANNEALING · SHOT BLASTING

KEEN PRICES · WE COLLECT AND DELIVER

UNION ROAD, WEST CROYDON. PHONE: THORNTON HEATH 5222

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

NITRAM METAL TREATMENT & ENG. CO. LTD.

SILVERDALE ROAD, HAYES, MIDDLESEX

A.I.D. A.R.B.
APPROVED

BRIGHT ANNEALING

TELEPHONE
HAYES 5111/2

Thames Valley Pattern Works Ltd.

ELMTREE ROAD, TEDDINGTON

Phone: MOL 698 MOL 6097

**ENGINEERS' PATTERNS
MODEL MAKING
INSTRUMENT CASES
CABINET MAKING
PERSPEX MODELS & MOULDS
GENERAL WOODWORK**

A.I.D. ——— **THE** ——— CUN 5195
HEAT TREATMENT
PEOPLE OF LONDON
G.R.M. HEAT TREATMENTS LIMITED, PADDINGTON, W.9.

STAINLESS STEEL SPECIALISTS

Fabrication, welding and X-ray
inspection, pressings and machined
parts.

THE TAYLOR RUSTLESS
FITTINGS COMPANY, LIMITED,
Ring Road,
Lower Wortley,
Leeds, 12

Induction hardening
and brazing, etc. We collect
and deliver

Shot blasting.

PRECISION HEATING LTD.

142A Canbury Park Road, Kingston-on-Thames
Surrey. Phone: KINGSTON 1468

Barrel Finishing. Specialists in
Barrel Finishing. Compounds and media
supplied. Contract work undertaken.—Send
samples to GRANATT CHEMICAL & ENGI-
NEERING CO., Austin Road, Battersea
S.W.11 MACaulay 7723.

ABBEY HEAT TREATMENTS LTD.
PLAZA WORKS, HIGH STREET, MERTON, S.W.19
FOR ALL TYPES OF HEAT TREATMENT.
WE COLLECT - WE DELIVER
TELEPHONE: CHerrywood 2291

When answering advertisements kindly mention **MACHINERY**.

WELDING CAPACITY AVAILABLE

A Factory equipped with modern auto-
matic plant covering a wide range of
longitudinal and circumferential sub-
merged and open arc welding and
capable of undertaking large quantity
production, has spare capacity available.
It has a wide experience on work of this
character and is in a position to give
quotations at competitive prices with
early and reliable delivery rates.
The organisation has comprehensive
development, test and inspection facilities
and is experienced in dealing with
quality products at high rates of pro-
duction.

Enquiries should be addressed to—
**BOX Z.526, MACHINERY, Clifton
House, Euston Road, N.W.1.**

REPAIRS

By

WELDING

**BROKEN MACHINE TOOL PARTS
& DAMAGED PLANT IN ALLOY STEELS,
CAST IRON & NON-FERROUS METALS
SPEEDILY REPAIRED BY WELDING**

ESTABLISHED OVER 40 YEARS

THE BLAKER MOTOR WELDING CO. LTD.

Welding Engineers

BUKES RD., PARK ROYAL, LONDON W.3.
Phone: ACCON 4811. Gram: Blakerweld. Euston Road

PROTOTYPES & SPECIAL PURPOSE MACHINES

REPAIRS & SALVAGE BY DISPOSITION
MACHINING, FORGING & FABRICATING
GEORGE MILLS (ENGINEERS) LTD.
BECKENHAM, KENT. TEL: SYDENHAM 5255

PROTOTYPE & PRODUCTION

ELECTRONIC WIRING, COIL WINDING,
INSTRUMENTATION & TESTING
SETON CREAGHE ENGINEERING LTD.,
G. W. Trading Estate, Park Royal Road,
N.W.10.
A.I.D. ELGAR 3354 7 A.R.B.

WOOD & METAL

PATTERNS

HAND MACHINE OR SHELL MOULDING
Keen Quotations Good Delivery
B. LEVY & Co. (Patterns) Ltd.
1-5 OSBERT ST., LONDON, S.W.1
Telephone: VICtoria 1073 & 7496

Planing, Boring and Large Turn-
ing capacity available. Also capacity on
chucking automatics and general machines.—
Enquiries to BOX Z.554, MACHINERY, Clifton
House, Euston Road, N.W.1.

Classified Advertisements (CONTRACT WORK, contd.)

Semi-automatic pinion cutting capacity immediately available.

Large range of hobs held in stock.
Also capacity on Mikron 79s.

ROBERT PRINGLE & SONS
36-42, Clerkenwell Road, London, E.C.1
Telephone: CLERKENWELL 2341

•• MACHINING ••

AUTO TURNED PARTS

FINE TOLERANCES, MAX. DIA. 1 1/2 in.
INDEX SS & GRIDLEY MULTI AUTOS
THREAD CHASING MANUFACT'RS
ROLLER BOX TOOL HOLDERS

BENTON ENGINEERING CO. LTD.

Tonbridge Road, Harold Hill, Essex
Ingrebourne 3864/5

PRECISION & GENERAL MACHINING

including

Thread Milling • Radial Drilling
Metal Spinning


A.I.D. and I.F.V. Approved. Enquiries invited.

Surplice & Tozer Eng. Co., Ltd.
Acre Works, Windsor

Windsor 1657 & 1844

Member of the Metropole Group

CAMS



APPROX.
48
HOURS
DELIVERY

FOR
ALL
SINGLE
SPINDLE
AUTOS

EDWARDS BROS.
51 GUNGE LANE, SOUTH WOODFORD, E.19
TELEPHONE: WARD LANE 1000

MACHINING

ECLIPSE

METAL INDUSTRIES LTD.
Sedgley Rd. West Tipton • Staffs.

GENERAL ENGINEERING WORK
PRODUCTION OR PROTOTYPE
JIGS • FIXTURES • ASSEMBLY
Pressure diecasting in zinc or lead

MACHINING CAPACITY AVAILABLE

PHONE: KIN 6112

CAPSTAN
TURNING
MILLING
DRILLING

SEND US
YOUR
ENQUIRIES

TURRET LATHES
CENTRE LATHES
ALL GRINDERS
ETC.

GOOD DELIVERIES — QUALITY — KEEN PRICES

W. G. MARSDEN ENG. LTD. 30 FIFE ROAD, KINGSTON, SURREY

CAPACITY AVAILABLE

AUTOMATICS—Single & Multi.

BULLARDS—6 & 8 Spindle.

COPY LATHES—Capstan Lathes.

DRILLING—Radial & Multi.

FORGING—Upset to 5" dia.

HORIZONTAL BORING—Medium.

PRESS WORK—750 Tons Maximum.

PURLEY WAY
CROYDON
CRO 0066

TROJAN LIMITED

A.I.D. D.I.A.R.M.
A.R.B.—I.F.V.
APPROVED



IMMEDIATE CAPACITY FOR MEDIUM - HEAVY MACHINING

Modern Planing,
Vertical and Horizontal
Boring Mills, Milling
and Drilling of work up
to 5 tons.

Moulding and Machining
Capacity for Non
Ferrous Components
up to 5 Cwts, including
High Speed Routing
and Precision Milling.

CARRON COMPANY • CARRON • FALKIRK • STIRLINGSHIRE

RESEARCH

ENGINEERS LTD.

FOR

SUPER ACCURATE CAMS

SEE "MACHINERY" 22nd JANUARY 1954 FOR
METHOD OF CUTTING. REPRINTS AVAILABLE

NORTHAMPTON GROVE, CANONBURY, LONDON, N.1.

Telephone: CANONBURY 4244 (4 lines)

Telegrams: WILMAKET, NORDO, LONDON

PRECISION TURNED PARTSA.I.D., A.R.B., C.I.A. & I.F.V., APPROVED
AUTO AND CAPSTAN QUANTITIES

Send your specification to:

AYLESBURY TURNED PARTS

(True Screws) Limited

Britannia St., Aylesbury, Bucks.

Tel: Aylesbury 2424 (3 lines)

Automatic Work Up to 1½in.

Immediate capacity available—

TRUE ENGINEERS, LTD.,

Wharf Lane, Bourne End, Bucks. Phone 1310.

Automatic and CapstanCapacity Available up to 2½in. dia.—
WILLIS ENGINEERING, 65A, High Street,
Hampton Hill, Middlesex. Molesey 4273.**Automatic Turned Parts, Press**Work, Press Tool Making, Capstan and
Centre Lathes, Milling, Drilling, Thread Milling.
Capacity available—PARKER ENGINEERING
(KINGSTON), LTD., 209-202, (A)bridge
Road, Kingston-on-Thames. KIN. 5501.**Planing Capacity, Heavy or Light**

Turning up to 5ft. diameter.

Special machines to customers' design.

F. ATKINSON & SONS, London, LTD.,

66, King's Cross Road, W.C.1. Terminus 4050.

Immediate Capacity Turning,capstans, milling, drilling, die and tool
making.—MILLS ENGINEERING PRO-
DUCTS, LTD., Barnet. Tel.: BARNET 6744.**Metal Spinnings. Immediate**capacity for metal spinnings and sheet
metal work. A.I.D. approved.—HIGHBURY
METAL SPINNING CO. (1955), LTD., 30,
Highbury Place, N.5. CANonbury 2906.**Horizontal Production Milling**for the trade. Slots, flats, squares, etc.,
of all descriptions milled on latest plant. Best
prices for long runs, satisfaction guaranteed.—
UNICORN PRODUCTS, LTD., 110-131, Stan-
stead Road, Forest Hill, London, S.E.23.
Telephone: Forest Hill 7688 (3 lines).**Capstan and Turret Lathe**Capacity available up to 4½in. diameter
bar and 2½in. diameter chucking. Castings and
Forgings a speciality. Milling, drilling and
centre lathe turning. High class work with
prompt delivery. Enquiries invited to:—

WHITWAM & ELEY,

22/24, Stafford Road, W.3. Acorn 8364.

Automatic Capacity Availableon Inlet single spindle auto, up to 2½in.
dia.—ARTHURS ENGINEERING, Heron-
Trading Estate, Molesey Road, Heron-
Surrey. Phone: Walton-on-Thames 5119.**Capstan Capacity Immediately**

available, 8 B.A.—1½in. Steel or Brass.

Large stocks of raw materials:—

SACRON, LTD.,

7, Chiswick High Road, W.4. Tel. CHISwick 3506

Capstan Capacity Immediatelyavailable 10 B.A. to 1½in. B.M.S. Stainless
Brass, etc. All materials in stock.—CHISWICK
ENG., LTD., Pluckington Place, Southall,
Middlesex. Tel: Southall 2247.**High Precision Grinding of**Tungsten Carbide and Steel Tools.
Accurate profile grinding and progression tools
a speciality.—S.T. LTD., 22-26, Upper Mulgrave
Road, Cheam, Surrey. Phone: VICtor 0074/5.**FINE LIMIT GRINDING**

MILLING, TURNING, DRILLING.

Complete Service Offered.

SETON CREAGHE ENGINEERING LTD.,

Trading Estate, Park Royal Road, N.W.10

A.I.D. ELGar 33567 A.R.B.

Centreless Grinding

ALL TYPES OF FORM, THROUGH AND PLUNGE

BAR GRINDING

½in. to 5in. DIA. UP TO 15ft. LONG

IMMEDIATE CAPACITY ON CAPSTAN MILLING
CENTRE LATHES, AUTO AND ALL TYPES OF GRINDING**REDCAR ENGINEERING CO. LTD.**

HOLLY ROAD WORKS, TWICKENHAM, MIDD. Tel. POP 6157 & 708

A.I.D. & A.R.B.

APPROVED

WE WOULD WELCOME YOUR ENQUIRIES FOR:—

- MILLING—Horizontal & Vertical.
- CENTRE LATHES to 38in. Dia.
- CAPSTANS to 2½in. Dia.
- PLANING TO 6ft. x 3ft. x 3ft.
- BORING—Horizontal & Vertical.
- Cylindrical Grinding to 20in. Dia. x 84in.
- Surface Grinding to 24in. x 8in.
- Drilling and Thread Tapping.

A.I.D. APPROVED

BOWES ROAD ENGINEERING CO. LTD.

BOWES ROAD, NEW SOUTHGATE, N.11. Phone BOW 2284/5/6

E. R. LATTIMER LTD

A.I.D. & A.R.B.

APPROVED

Offer Complete Service for
PRECISION PROFILE MILLING, JIG BORING
LIGHT TO MEDIUM COMPONENT MANUFACTURE
TOOL DESIGN & MANUFACTURE
SMALL ASSEMBLIES, DIE & MOLD MANUFACTURE
SMALL PRESSURE DIE CASTINGS
IN HAZAR ALLOY TO B.S. 1004
SUPER PRECISION HYDRAULIC COMPONENTS AND ASSEMBLIES
FOR WHICH WE HAVE HYDRAULIC TESTING EQUIPMENT

SHAKESPEARE
STREET,
SOUTHPORT

Phone: 57696 7

AUTOPRODUCTIONS LTD.Automatics: Single Spindle
Index "18" "24" "36" "52" "B.42"
Multi Spindle: 1½in. and 1½in. WickmanCapstan
Drilling
MillingCentreless Grinding
Polygon Turning
Chemical Blacking

CAPACITY AVAILABLE

53, Green St. Sunbury-on-Thames

Phone: 2499

PLOUGH GRINDING

24 hr. Service

High Speed Service Tool Co. Ltd.
Maple Road, Surbiton, Surrey.
Elmbridge 1135-6-7.**ROSSER & RUSSELL LTD.**Queen's Wharf, Hammermith,
LONDON, W.6.


Telephone: RIVerside 4161.

**GENERAL ENGINEERS
AND
MANUFACTURERS OF
SPECIAL MACHINERY
TO
CUSTOMERS DESIGN**

WE MAKE TANKS, FRAMES, DUCTS, INSTRUMENT
PANELS AND CHIMNEYS.Let us have your enquiries for welded
fabrications large or small. And we can
press 200 Tons, guillotine ½ in. plate,
bend and cylindrical roll.SHELMERDINE & MULLEY LTD.
EDGEWARE ROAD, CRICKLEWOOD,
N.W.2.

GLAdstone 7677-8-9

When answering advertisements kindly mention MACHINERY.



cam CUTTING

PRECISION TRACK MILLING OF FACE, BOX & CYLINDRICAL CAMS UP TO 30 INCHES DIAM.

ZEPHYR Engineers Ltd TEL: EUS. 7624
24/32 EUSTON BUILDINGS, LOND. N.W.1

CUTTING TOOLS AND PRECISION GRINDING



TECHNITOOLS LIMITED
419, WINDMILL ROAD, WEST CROYDON, SURREY
TELEPHONE AND INLAND TELEGRAMS: THORNTON HEATH 051

Multi-spindle and Single-spindle

Auto Turning up to 2in. bar capacity, capstan turning from the bar up to 2 1/2in. dia. chuck work up to 1 1/2in. dia., thread milling, milling, shaping, drilling, etc., capacity available. Any tolerance and quantity. Satisfaction absolutely guaranteed.—UNICOEN PRODUCTS, LTD., 119-122, Stanstead Road, Forest Hill, S.E.26. Phone: FOREST Hill 7688 (3 lines).

Spur Gear and Sprocket Cutting

from blanks supplied or machined complete. Phone: EUSTON 1354.
TURNER BROS.,
10, Pratt Mews, Camden Town, N.W.1.

GRINDING

IMMEDIATE CAPACITY AVAILABLE
CYLINDRICAL • INTERNAL • SURFACE
LATEST TYPE MACHINES
PLOUGH GRINDING — 24 HOUR SERVICE
also

General Machining, Fitting and Complete Assemblies
Special Purpose Machines Designed and Built to Specification

We shall be pleased to advise on your Grinding and Machining Problems

HOLLAND & CAESAR LTD
ENGINEERING CONTRACTORS
GRINDING SPECIALISTS

ORKEY WORKS, 3-5 LEIGHTON PLACE,
LONDON, N.W.5

Est. 1836

Telephone: Gulliver 3047 and 6444

Immediate Capacity Available,
on single spindle Automatics up to 1 1/2in.—
JAN PRECISION SCREWS, 38, Woodthorpe
Road, Ashford, Middlesex. Phone: Ashford 4524.

Capstan Capacity Available
1in. to 1 1/2in. Stainless, B.T., B.M.S.,
etc. No quantity too small.—**ACME WORKS,**
Purkington Place, Southall, Middx. Tel.:
Southall 2247.

► We are equipped to provide a first-class machine shop capacity

PLANING 12 FEET • HORIZONTAL BORING • VERTICAL BORING • RADIAL DRILLING
CENTRE LATHES • COMBINATION TURRET LATHES • HORIZONTAL MILLING
VERTICAL MILLING • GRINDING • DRILLING • WELDING • PROFILING • HONING

D. A. GUNN ENGINEERING LTD

32 PARK ROAD NORTH • LONDON • W.3 Tel.: ACOrn 4841/4

SEND
US
YOUR
ENQUIRIES

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

CAPACITY AVAILABLE

TRADE WORK DIVISION

PRECISION**MACHINING** of most descriptions**GENERAL ENGINEERING**

and

MANUFACTURING

A.I.D. and A.R.B. approved

S. M. STUART-TURNER & CO.

(SURREY) LTD. FAIRVIEW ROAD NORBURY

LONDON S.W. 18 TEL. POL. AND 273 2

TAM. ATRGOUT STREET LONDON

CYLINDRICAL GRINDING CAPACITY

External up to 12in. dia. by 36in.

Internal up to 7in. by 8in.

MARSDEN & SHIERS, LTD

Davis Road, Chessington, Surrey.

A.I.D. & A.R.B. A.N.R. Approved.

Telephone: ELMbridge 5333 & 5334

AUTOMATIC
TURNED PARTS

WEST ST. REIGATE 2177

AMBRESSEY
ENGINEERING CO. LTD.

1½ in. Bar, 4in. Chucking
AUTO CAPACITY**ECONOMIC PRICES** from 500 UP
made possible by**THE HYDRO COPYING TAREX****HUNTLEY & SPARKS, LTD.,** Wandie Road,
London, S.W. 19, A.I.D., A.R.B. LID 2446**Thread Milling for the Trade**
up to 6in. O.D. and 5in. I.D. Any thread,
any quantity. Keen prices for long runs.
Satisfaction guaranteed.**UNICOEN PRODUCTS, LTD.**
119-121, Stanstead Road, Forest Hill, London,
S.E. 20. Telephone: Forest Hill 7688 (3 lines).**W. D. HORNE & CO.,**
LTD.**MILLING** **TURNING**
DRILLING **CAPSTAN**
CAPACITY AVAILABLEWoodbridge House, Aylesbury Street
London, E.C. 1
CLERKENWELL 6668 & 6980**Centreless Grinding is the**answer to many production problems.
We specialise in it, and so perhaps can help you.
We have capacity from ½ in. up to 3in. diameter
for all types of centreless grinding and can also
make your complete components on our Autos
and Capetans. (Up to 1½ in. diameter.)We believe our prices are as competitive as
any, and we know our deliveries are better than
most. Phone or write for quotation or ask for
our representative to call. We collect and
deliver.—**FITZNER, LIMITED**, 197-199, Kings
Road, Kingston-on-Thames. Tel.: KINGston
1451.**Cylindrical and Internal Grind-**ing, max. swing 8in., capacity available.
Close limits. Modern plant. A.I.D. approved.—
WARD ELECTRIC CO. (NORWOOD), LTD.,
44, Chapel Road, West Norwood, S.E. 27.
Gipsy Hill 1020.**Metal Spinings Produced to**your requirements. Economically. On
Time. A.I.D. approved.—**MARTIN-GOLOD**
LTD., Maybury Gardens, N.W. 10. WIL 3888.Gear Cutting, Auto Turret, Capstan
and Centre Lathe Turning, Milling,
Planing, Hardening and Grinding,
Profile Cutting and Welding.**SMITH & NETHERWOOD,**
LTD.

Tanyard Road, Quarmby,

HUDDERSFIELD.

Phone: MILNSBRIDGE 1865.

• PRESS WORK •**Metal Pressings**TO ANY TOLERANCE
SHAPE OR QUANTITYSERVICE and PRECISION
at COMPETITIVE PRICES**ECONOMIC STAMPINGS LTD.**

DISRAELI STREET, LEICESTER • TELEPHONE 3985

MEMBER OF THE BENTLEY GROUP

PRESSWORK**PRESS TOOLS****JIGS & FIXTURES****GRAVITY DIES****ASSEMBLIES**

The

THORAN ENGINEERING**COMPANY LIMITED****SOUTH POTTERIES ESTATE****WHITE HART LANE****TOTTENHAM N.17**

TELEPHONE: BOWES PARK 8383

SUB-MINIATURE PRESSINGS

and multi-stage precision press work

In all materials

PROMPT DELIVERIES

G. A. PRECISION PRODUCTS LTD

No. 2 Factory, Darnes Lane

Potters Bar, Middlesex

Potters Bar 6895

Pressings and Stampings, Ltd.,

Eccleston Road, West Ealing, W.12.

Presswork up to 150 tons. Double action deep-

drawing Guillotine sft. by 10 S.W.G. Spot

welding.—Assembly. Tool making and electro-

plating.—Phone: Ealing 3667-8.

Pressings in All Metals Up to

60 tons. Press tools manufactured in our

own toolroom. Light assemblies. Domestic

Electrical and Mechanical. All finishes. A.I.D.

and A.R.B. approved. Advice and estimate

given free. Inquiries to:

METAL COMPONENTS, LTD.,

Dolphin Road, Shoreham-by-Sea, Sussex.

Phone: Shoreham-by-Sea 2224/5.

PRESSWORK
PRODUCTS
Specialists
in Accuracy

Light Pressings •
Deep Drawing •
Spring Pressings •

Write or Phone Us At

STATION WORKS
LUDLOW ROAD
MAIDENHEAD BERKS

Phone: Maidenhead 700 (3 lines)

• TOOLMAKING •**DORMER & WADSWORTH**PLASTIC
MOULDS
PRESS TOOLS
JIGS
FIXTURES ETC.51-53
BICKERSTETH RD.
PITCHAM RD.
TOTTING
LONDON S.W. 19

TELEPHONE: BALHAM 1006 (2 LINES)

JIG BORING

ON SIP JIG BORERS

EDMONTON TOOL & ENG. CO. LTD

141, HERTFORD ROAD, EDMONTON N. 9


TELEPHONE: EDMONTON 4412/3

SPURS, SPIRALS, BEVELS, WORMS

& WORMWHEELS

GEAR CUTTING

When answering advertisements kindly mention MACHINERY.



THE FIRM WITH HALF A DOZEN JIG BORERS for PRESS TOOLS etc.

HIGH SPEED SERVICE TOOL CO. LTD.
Maple Road, Surbiton, Surrey. Elmbridge 1135-6-7
STUDER PROFILE GRINDING A SPECIALITY.

Press Tools

**JIGS
FIXTURES
GAUGES**

JIG BORING

ON NEW 4G SIP JIG BORER

THE MITCHAM JIG & PRESS TOOL Co. Ltd.

BENEDICT RD., MITCHAM, SURREY

Telephone: Mitcham 3635

MacDowall

JIGS, FIXTURES
PRESS TOOLS &
GAUGES
PRECISION ENGINEERS
SPECIAL MACHINERY

MACDOWALL EQUIPMENT COMPANY LIMITED
NORTH STREET ROMFORD ESSEX

ROMFORD 61981

A.I.D. A.R.B.
Member of the Gauge & Toolmakers Association

- **MOULDS** Compression and Injection Plastic
- **MOULDS** Pressure Diecasting
- **MOULDS** Rubber and Gravity
- **JIG & FIXTURES**
- **PRESS TOOLS**
- **PRESS WORK** up to 25 tons
- **AUTOMATIC & CAPSTAN TURNED PARTS**

TO BE PRECISE IT'S
Camdentools

21-22, HONYWOOD ROAD,
BASILDON, ESSEX.

Phone: Basildon 20506/7.

Capacity Available, Press Tools,
Jigs, Fixtures, Production of Metal
Pressings, Prototypes and Jobbing. Light
Assemblies.

ELLIOTT & WEST,
587, Liverpool Road, N.7. Phone: NORth 2366.

Press Tools, Press Work, Jigs,
Fixtures, Caps and Auto. Turning,
Special H.S. Cutters. Components manufactured
and assembled to spec.—L. PERSON & SON,
63, Shaftesbury Street, N.1. CLE. 7139.

JIGS
And **FIXTURES**
Designed & Manufactured by
DINSDALE ENGINEERING CO. LTD
LEEDS PLACE, TOLLINGTON PK. LONDON N.4

PRESS TOOLS
JIGS, FIXTURES,
PRESSURE DIES,
GENERAL MACHINING,
JIG BORING, PRESS WORK,
ETC.
Please send your enquiries to
THE MIDDLETON TOOL & ENG. CO. LTD
ALEXANDRA RD., PONDERS END, MIDDX.
Telephone: HOward 2252/3/4

When answering advertisements kindly mention **MACHINERY**.

LENCHS

(BIRMINGHAM) LTD
TOOLMAKERS
Barr St., BIRMINGHAM 19.

Sole Manufacturers of:

OAKALOY

CARBIDE TOOLS & TIPS

PRESS TOOLS · JIGS ·
FIXTURES

Literature on request → Tel: Northern 8421 (4 lines)

COVENTRY GRINDERS LIMITED

AID, ARB, IEME Approved

Phone: 73344/5

FORM GRINDING SPECIALISTS

Send us your enquiries for Gauges, Form Tools, Copying Lathe Templates, Jigs & Fixtures, Impact Punches & Dies, Precision Cams, Crushers, Prototype components, Centreless, External, Internal, Blanchard, Surface & Jig Grinding, Etc. A complete tool room and gauge room at your service.

ENGINEERS & PRESS TOOL MAKERS

Speciality—Press Tools For The Tin Box Trade
DIE FORGINGS · POWER PRESS REPAIRS

H. & G. HOPTON (Est. 1870)

119-121, BLACKSTOCK RD., LONDON, N.E.

Telephone: Canonbury 9444/5

Toolmaking. First Class Com-
pany has immediate capacity available.
Press tools, Jigs, Fixtures, Special cutters, etc.
—BOX Z564, MACHINERY, Clifton House,
Euston Road, N.W.1.

**PRESSURE
DIE-CASTING DIES**

PRESS TOOLS · JIGS · FIXTURES · GAUGES

**★ MOULDS FOR
PLASTICS**

SHINDLER ENGINEERING CO LTD

ST. CHADS PLACE, KING'S CROSS, W.C.1 TELEPHONE TEAHDAS 6461

PRECISION

ECONOMY

Jigs and Fixtures Moulds and Press tools

Eastfield Side, Sutton-in-Ashfield, Notts

CHIS 5842. **R. E. CARDER LTD.** CHIS 4611.
1 & 2, Chiswick Common Road, London, W.4

JIGS — TOOLS — AND PRESS TOOLS
UNIVERSAL GRINDING
—JIG BORING, GENERAL
GOOD CLASS MACHINING WORK—
DESIGN OFFICE & DEVELOPMENT WORK

JIG GRINDING CAPACITY

Available on new Hauser Machine.

STEEL CRAFT JIG & TOOL CO.

Horton Bridge Road, West Drayton.

Phone: West Drayton 2580

ESTD 1889

R-STEPHENS & SON LTD

**PRESS TOOLS · JIGS
FIXTURES · MOULDS
GAUGES · DESIGNS**

115 CHURCH ROAD
UPPER NORWOOD
LONDON S.E.11

PHONE
LIVINGSTONE
2265-6

SPECIALITIES

Machine Engraved Feed Dials.
Scales, Nomenclatures, Labels, etc., in Metal
and Plastics. Quick Delivery.—O. H. KAMPP
& CO., Tanyard Works, Beaminster, Dorset
Phone: Beaminster 440.

Cleveland Automatics Rebuilt
by experts. Replacement Parts, Manu-
facturers of Roller Boxes, Turret and Cross Slide
Tooling.—THE TIMS ENGINEERING CO.,
LTD., Vileyard Works, Surinfield, Wals-
ley, N.W.6. Phone: Maida Vale 0049.

TIME RECORDERS—Sales—
Rental Service. Tel. HOP 2239.
TIME RECORDER SUPPLY &
MAINTENANCE CO., LTD.,
157/159, Borough High Street, London, S.E.1

When answering advertisements kindly mention **MACHINERY**.

**NOW AVAILABLE
ON OPEN
GENERAL LICENCE**

AMERICAN BALL and ROLLER BEARINGS

*Distributors of the following Anti-Friction Bearings
(MADE IN U.S.A.)*

FAFNIR

Special Purpose Bearings - Aircraft Bearings - Machine Tool Bearings
(Instrument type Precision Bearings)

SEALMASTER

Ball Bearing Pillow Blocks and Units

ROLLWAY

Special Heavy Duty Roller Bearings

R.B.C.

Twentieth Century - Pitchlign - Cyclops

SHAFER

ConCaVex Aircraft Roller Bearings

LINK-BELT

Ball and Roller Bearing Units

M.P.B. Inc.

Miniature Precision Ball Bearings

TAPERED ROLLER

Bearings

Trade enquiries would be welcomed for other American Bearings

E. J. JACK LTD.

Est. 1924

AMERICAN DIVISION

154 CAMDEN HIGH STREET, LONDON, N.W.1

Telephone : Gulliver 5761 (6 lines)

U.K. Division

MARLBOROUGH WORKS

HARMOOD STREET, CHALK FARM, LONDON, N.W.1

Telephone : GULLiver 2234 (5 lines)

When answering advertisements kindly mention MACHINERY.

WIDDOWSON'S specialise
in re-building
your
CINCINNATI
MILLING MACHINE

HERBERT WIDDOWSON & SONS LIMITED
CANAL STREET WORKS · NOTTINGHAM · ENGLAND TELEPHONE 42061

GARFIELD AUTOMATIC NUT TAPPER


Made in two models covering
the tapping of nuts from $\frac{1}{4}$ to $\frac{3}{4}$
inclusive.

Fast production, easily tooled.

Can be supplied either Belt or Motor Driven

GEO. H. ALEXANDER MACHINERY LTD.

82-84 Coleshill Street, Birmingham 4, England




TAPERLOCK & TRILOCK GAUGE HANDLES Engraving Service & BLANKS Complying to B.S. 1044

Blanks in soft and annealed condition or in hardened state with centres lapped
and taper ground to size. Handles anodised to your specific colour



BRILHART LTD · HATFIELD · DONCASTER · Tel: Stainforth 595

Albion COUNTING INSTRUMENTS



(patented design)
Send for catalogue
to Instrument Division
B. & F. CARTER & Co. LTD.
BOLTON 19 Bolton 4344 (3 lines)

If you use compressed air
YOU NEED

Norgren EQUIPMENT



**FILTERS
LUBRICATORS
REGULATORS**

C. A. Norgren Ltd., Shipston-on-Stour
Warwickshire. Telephone: 110 & 106

'WORTH'
PIPE UNIONS
for Steam, Water, Oil
or Gas.
NEVER LEAK
WALTER SLINGSBY & CO., LTD.
WASK WORKS KEIGHLEY

FLEXIBLE METALLIC CONDUIT and solderless couplings

For protecting cables leading to:
motors, switchboards, starters, etc.

ALL SIZES FROM
 $\frac{1}{4}$ in. to 3 in.

THE DONOVAN ELECTRICAL CO. LTD.
(Wholesaling Division)
GRANVILLE STREET · BIRMINGHAM 1



BRAND NEW BALL & ROLLER BEARINGS

OVER 4,600,000 IN STOCK IN MORE THAN 4,000 TYPES
BRITAIN'S LARGEST STOCKS

STOCK LIST AVAILABLE

CLAUDE RYE BEARINGS

895-921 FULHAM RD., LONDON S.W.6
RENOVN 6174 (EXT. 24) TELEX 2-3453



When answering advertisements kindly mention **MACHINERY**.

Classified Advertisements (SPECIALITIES, contd.)



**AUTOMATIC
NUMBERING
MACHINES**
for
**MARKING
ALL TYPES
OF METALS**

Phone
GERard 5051

A.E. GALE LTD.

ARCHER ST. WORKS,
ARCHER STREET
SHAFTESBURY AVE.
LONDON W.I.



**Universal
Ball Bearing Co.**
111-115 Hammersmith
Grove, London, W.6
**FACTORS
MANUFACTURERS
AND REPAIRERS**

Phone: Grams: "Universal Bearing
Riverside 3262-3-4. Hammersmith

Tungsten Carbide Tool

Manufacturers of standard and special form tools in high speed steel and tungsten carbide. Our range includes reamers, cutters, workrest blades and wear-resistant parts. Carbide supplied to customers' specification and express service given for emergency tooling.

DIAGRIT GRINDING CO., LTD.,
Marden, Kent.
Phone: Marden 962.

PACKING AND SHIPPING**R. & J. PARK, LTD., Dominion**

Works, Chiswick, Emdand. Export packers, shippers and forwarding agents. Specialists in packing heavy machinery.

The "Coxeter" Revolving
Centre, from 76s. All sizes from stock.—
REVOLVING CENTRES, LTD., Oxford.

ANNOUNCEMENTS**•WORK TO PLACE.**

Compression Moulding Capacity
required for Switch Parts on 100/120 Presses. Moulds available. Keen prices essential for this highly competitive field.—**BOX Z578, MACHINERY, Clifton House, Euston Road, N.W.1.**

BUSINESS OPPORTUNITIES**AUSTRALIA**

English Company Director, resident Sydney, 25 years engineering experience, wishes contact manufacturers desiring expand activities in Australia. Willing undertake market surveys, negotiation manufacturing licences, agencies, etc. Highest credentials.

Write **BOX Z 500, MACHINERY, Clifton House, Euston Road, N.W.1**

Sheffield Engineering Firm with comprehensive engineering plant and extensive experience in the design and production of all types of machinery, including special purpose plant, wishes to undertake the manufacture of complete or part assemblies including assembly line production. Own Drawing Office and Pattern Shop. Technical Representatives in all areas.—**BOX L 771, MACHINERY, Clifton House, Euston Road, N.W.1.**

Advertiser Wishes to Contact bona-fide Iron and Steel Scrap, export-licence holder, with view to placing firm contracts with bank letter of credit.—**BOX Z571, MACHINERY, Clifton House, Euston Road, N.W.1.**

Mechanical Engineering Design and development firm, active in mass-production industries, offers good commission for introductions resulting in additional business.—**BOX Z455, MACHINERY, Clifton House, Euston Road, N.W.1.**

BUSINESS FOR SALE

Consistently Prosperous, Thirty years old private limited company; engineers, mill furnishers, works suppliers, tool dealers, etc., in N. Midlands, busy industrial area. Sale as going concern. Age and health reasons.—**BOX Z567, MACHINERY, Clifton House, Euston Road, N.W.1**

AGENCIES

Well known **ENGLISH GEAR SPECIALISTS** considering **FORMING SELLING ORGANISATION** for **FOREIGN MACHINE TOOLS.**

Would welcome enquiries for Agencies from Manufacturers, **ESPECIALLY FOR GEAR MACHINES AND EQUIPMENT.**

BOX Z448, MACHINERY, Clifton House, Euston Rd., N.W.1.

PATENTS—TRADE MARKS

Bosshardt, Percival, & Co.
(Chartered Patent Agents), 94, Market Street, Manchester, 1. Telephone: Manchester, Blackfriars 6758.

BUSINESS PROPOSITIONS**£500,000 AVAILABLE**

to purchase an old-established Business in any Trade. Present Management can remain.

Write in confidence to:
**REGINALD TERRELL
BUSINESS BROKERS LTD.**
46 St. James's Place,
London, S.W.1. (HYD. 1678)

Private Advertiser Would Be interested in investing say £6,000 in any proposition where part time services would be acceptable. Location preferably within 70 miles Guildford. Some engineering experience, would consider run down firm if agreeable to share fairly any past losses recovered. Not interested in get rich quick scheme.—**BOX Z573, MACHINERY, Clifton House, Euston Road, N.W.1.**

TRANSLATIONS

Technical Translations, German, Hungarian, Roumanian, Specialised in Mech. Eng.—**W. RETZLER, 51, Dilton Road, Leatherhead, Surrey.** Telephone: Leatherhead 4024.

PHOTOGRAPHY

Miles & Kaye, Ltd., 102, South-ampton Row, London, W.C.1. Holborn 6658. Specialists in commercial and industrial photography for over 60 years. All branches of photographic work undertaken.

Photographs by MACHINERY set the standard in engineering publicity. Our studio is one of the best equipped in the country. Ideal for really good photographs of tools, attachments and portable equipment. Mobile units available for taking photographs in black and white or in natural colour in your own or your customers' works. Specimens of work submitted on request.—Full particulars from the **SERVICE MANAGER, MACHINERY PUBLISHING COMPANY, LTD., National House, West Street, Brighton, 1.**

MATERIALS FOR SALE

E. Stephens & Sons, Ltd., Bath Street, London, E.C.4. CLE 1721. Tube Rounds, Flats, Hex. Cut to size. Quick delivery.

MATERIALS WANTED

Steel, Aluminium, Brass, Sheets, and Offcuts, 10 to 24z. Small or large quantities. Cash payments.—**DYAS & FOWLE, 41, Loudoun Rd., N.W.8, Maida Vale 2711, 5477**

BRITAIN'S BIGGEST BUYERS

WANT**NEW BALL & ROLLER
BEARINGS**

OF ALL TYPES & SIZES

CLAUDE RYE BEARINGS

895-921 FULHAM RD. LONDON, S.W.6
RENOV 6174 (EXT. 24) • TELEX 2-3453

When answering advertisements kindly mention **MACHINERY.**

PLANT WANTED

Wanted. Reasonably Modern machine tools and sheet metal working machinery. Best prices paid.—W. FORREST & CO., LTD., Industry Works, Sylvester Gardens, Sheffield, 1. Sheffield 28514/5.

B.G. MACHINERY, LTD., Montemery Street, Sparkbrook, Birmingham, 11, will pay good prices for Machine Tools of first-class make and in good condition.—Phone: VICTORIA 2851/0.

A. LAWRENCE & CO. (MACHINE TOOLS) LTD.

will be pleased to purchase your surplus Modern Machine Tools either on a cash or part exchange basis. Ask our representative to call and inspect.

Welsh Harp, Edgware Road, London, N.W.2
Telephone: GLAdstone 0033

WANTED

Modern Vertical Spindle (Plough) Surface Grinding Machine, reciprocating rectangular hydraulic table. MUST have segmental grinding wheel of 24in. minimum diameter. **PRECIMAX** preferred; other makes considered.

SOUTHERN ENGINEERING & MACHINERY CO.
Connaught Buildings,
Millbrook, Southampton.
Telephone No: 73101/2/3.

Machine Tools and Sheet Metal Working Machinery, modern items of all types required.—CHARLES E. MATTHEWS (MACHINE TOOLS), LTD., 34, Gladstone Road, Croydon. (Thornton Heath 1785.)

Vertical Head Wanted for Cincinnati No. 2 Dial Mill.—BOX Z485, MACHINERY, Clifton House, Euston Road, N.W.1.

kent
Give Value

WHETHER BUYING OR SELLING
USED MACHINE TOOLS

Contact:—
K.E.N.T. MACHINERY & ENG. CO.
Datchelor Place Mews, London, S.E.5.
Telephone: ROD 4149.

CENTAUR TOOL WORKS, Birmingham, 18, pay best prices for good modern secondhand Machine Tools by first-class makers. Write or phone and our representative will call. Phone: FIVEBASTON 1118 and 1119. 'Grams: Capetan, Birmingham.

Machine Tools, Power Presses and Sheet Metal Machinery. Minute machines or complete plants purchased. Immediate inspection.—ALBERT EDWARDS (MACHINERY), LTD., 79/89, Pentonville Road, London, N.1.

WANTED!

USED MACHINE TOOLS

We offer generous prices for your plant or accept in part exchange for modern equipment

E.H. JONES
(MACHINE TOOLS) LTD

48, HIGH ST. EDGWARE, MIDDX
Telephone: EDGware 4488/9
BIRMINGHAM: MIDLAND 5593

SURPLUS MACHINE TOOLS REQUIRED

OFFER YOUR MACHINES TO

J.E. RAISTRICK LTD.

POYLE TRADING ESTATE
COLNBROOK, SLOUGH,
BUCKS.

TEL: COLNBROOK 2421

Electrically Heated Platens wanted, about 20in. x 20in., suitable for Compression Moulding Presses.—BOX Z538, MACHINERY, Clifton House, Euston Road, N.W.1.

NORTON

GENEROUS PRICES
for "NEARLY NEW"
MEDIUM &
HEAVY DUTY MACHINE TOOLS
Ring: TATe Gollery 0633.4

REVERSE CHARGE
TELEPHONE CALLS
ACCEPTED!

W. NORTON (MACHINERY) LTD.
GROSVENDR GARDENS HOUSE, GROSVENDR GARDENS
LONDON S.W.1. Telephone: TATe Gollery 0633.4/5

Wanted, Machine Tools and Sheet Metalworking Machinery, particularly post war models.—H. BELL (MACHINE TOOLS), LTD., Walter Street, Leeds, 4. Tel. 65-7398.

Harrison or Similar 1in. Centre Lathe. Approx. 30in. by 10in. Surface Grinder, 6/8in. Power Saw, 10/12in. Wheel Pedestal Grinder. No dealers.—FISHER TOOL, Hattons Lane, Liverpool, 16. CHILDWALL 5543.

Autos Wanted. Schutte SB & SD 35 and 53.—Particulars and price to BOX Z580, MACHINERY, Clifton House, Euston Road, N.W.1.

Acme Gridley and New Britain 6-spindle bar Autos wanted. 14in. dia. upwards. Not earlier than 1948.—Details and price to BOX Z582, MACHINERY, Clifton House, Euston Road, N.W.1.

Automatics Required, All Sizes by Index, Tornos and Swiss Peterman.—Brief details stating prices to BOX Z588, MACHINERY, Clifton House, Euston Road, N.W.1.

Vertical Borers Required, 9ft. to 40ft. dia. for rough work. Age immaterial providing low price.—BOX Z594, MACHINERY, Clifton House, Euston Road, N.W.1.

*Wanted
Urgently*

Late Type Machine Tools
Best Prices are offered for latest types of Machine Tools. Send us details of what you have and our representative will call to inspect.

J. B. MACHINE TOOL CO. LTD.
312 BRADFORD ST., BIRMINGHAM 5
Telephone: MIDland 4375

WANTED
GOOD CLASS MACHINE
tools and sheet metal
machinery.

EDWIN MILLEN

70 Clerkenwell Road, London, E.C.1
Phone: Clerkenwell 6064

WANTED
ALL TYPES OF MODERN
MACHINE TOOLS

Please write or phone details to:
THE MIDLAND MACHINE TOOL CO.
BRADLEY, BILSTON, STAFFS.
Tel.: Bilston 42471/4

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT WANTED, contd.)

WANTED GOOD MACHINE TOOLS

Offer your Surplus Tools to us. We pay a good price

M. WARD

(MACHINE TOOLS) LTD.
1, KILBURN HIGH ROAD,
LONDON, N.W.6

MAIDA VALE 1195-96

Telegrams: Emwarner. Kil., London
One minute from Kilburn Park Station
Bakerloo Railway

2 us.

Harry Kirk Will Purchase
modern quality machine tools for cash.
Whole plants or individual items. Full details to:—

HARRY KIRK ENGINEERING, LTD.,
Machine Tool Division,
Brandon Road Works,
Brandon Road, Coventry.
Telephone: Walsgrave-on-Sowe 2213/4.

Wanted, Horizontal Spindle

Plano-type Milling Machine with minimum table traverse 48in.—BOX Z531, MACHINERY, Clifton House, Euston Road, N.W.1.



**WE ARE KEEN BUYERS
OF GOOD MODERN
MACHINE TOOLS.**

**INSPECTION WILL BE
ARRANGED AT ONCE.**

M. C. LAYTON LTD.
96-98 VICTORIA STREET,
LONDON, S.W.1

Telephone: VICTORIA 7778/9.

Index Autos Wanted by User.—
BOX Z422, MACHINERY, Clifton House,
Euston Road, N.W.1.

3 Dimensional Diesinking Machine.
Deckel or Alexander.—Details and price to BOX Z557, MACHINERY, Clifton House,
Euston Road, N.W.1.

WILLIAM URQUHART
Proprietors:
M. & R. Urquhart
MODERN MACHINE TOOLS
of all types.
GOOD PRICES. Send details to
WM. URQUHART,
1023/27 Garratt Lane, London, S.W.17
Tel: BALHAM 8551

WANTED MODERN MACHINE TOOLS

We pay cash for single machines or complete plants

SEND US DETAILS
IMMEDIATE INSPECTION ARRANGED
**SOUTHERN ENGINEERING
AND MACHINERY CO.**
CONNAUGHT BUILDINGS
TANNERS BROOK, MILLBROOK
SOUTHAMPTON
Telephone: Southampton 73101/2/3

PLANT FOR SALE**HENRY BUTCHER & CO.***Specialists in the*

• VALUATION AND SALE OF FACTORIES, PLANT AND MACHINERY •

73 CHANCERY LANE, LONDON, W.C.2

TEL.: HOLBORN 8411 (8 lines) GRAMS: PENETRANCY, HOLB., LONDON

Three LISTER DIESEL ENGINES, 38/4.

All in excellent condition. One nearly new. Two with outboard bearings for Belt Drive. Two Fuel Tanks.

Two Maudslay D.C. Generators 100v. 225 amps.

Tel: BARnet 4648.

Workpans, Large Quantities

Stroud Gauge Workpans, size 16in. by 14in. by 5 1/4in. forged riveted handles, approx. weight 8 lb., price 8s. 6d. each, quantities. Other sizes manufactured.—Contact J. HURTONS WORKS, Astley, Shrewsbury. Tel. Shawbury 266

Cincinnati Production Hor. Mill

Table 41in. x 10in., 28in. traverse, 415/3/50, 16 speeds, 50-1,500.—C. DUGARD, LTD., Denmark Villas, Hove 32471.

A Comprehensive Selection of
Modern Machine Tools Always
in Stock

WM. PARTINGTON LTD.
Trafford Park Rd.
Trafford Park
Manchester 17

TRAFFORD PARK 0332

Progress 5E (New) 2in. Capacity

Pillar Drilling Machine with compound table. Motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Expanding Lathe Mandrel Sets

Range 1in. to 2in. Leconte Pattern. List £17 5s. Ex Government Bargain. Unused. Boxed. 26 10s. set, p.p. 3s. 6d. Also 2in. to 3in. 25 10s. carr. 5s.—STEVENAGE TOOLS & SWITCHES, LTD., Stevenage, Herts.

Herbert Horizontal Broacher,
50in. stroke. 20 ton capacity. 2 1/2in. dia. screw. A.G.H. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. NORTHERN 1234/5.

Archdale 2 Spindle Drilling and
boring machine. A.G.H. No. 5 M.T. spindles. Mot.—WILCOX & CO., Barr Street, Birmingham 19. NORTHERN 1234/5.

Brown & Sharpe Automatics:

Several No. OG, No. 2G and No. 00G. All late serial numbers and in good condition. Reasonable prices. M/C's complete with stock supports, feed and speed gears.—Can be seen at MELBOURNE ENGINEERING CO., LTD., Derby Road, Melbourne, Derbyshire. Phone: Melbourne 232.

MACHINE TOOLS—THE HEART OF INDUSTRY RE-BUILDING SPECIALIST TO THE TRADE

Guaranteed 6 months. Crane Capacity 15 tons.

**400 TOOLS IN STOCK
NEW, USED AND RE-BUILT**

Priced Brochure on request

OUR STOCKS SO QUICKLY CHANGE—We cannot individually advertise the full range.

Sole Agents for H.M.V. (Swedish)
3-5 HORIZONTAL BORERS

MARTIN BROS. (MACHINERY) LTD.

EMPRESS WORKS • CORNBROOK
MANCHESTER 16

Tel: TRAFFORD Park 1091-2

When answering advertisements kindly mention MACHINERY.

RING BELLS for machine tools

LEEDS 63-7398

CINCINNATI No. 3 Dial Type Vertical Milling Machine. Speed Range 18-450 r.p.m.

HERBERT 47V Vertical Milling Machine. Speed Range 21-750 r.p.m.

ARCHDALE 18in. Vertical Milling Machine. Speed Range 79-2,000 r.p.m.

ARCHDALE 30in. Vertical Milling Machine. Speed Range 49-525 r.p.m.

MILWAUKEE 2H Universal Milling Machine. Speed Range 30-1,400 r.p.m. Comprehensive equipment.

BROWN & SHARPE No. 2 Universal Milling Machine. Speed Range 40-1,300 r.p.m.

PARKSON 2T Universal Milling Machine. Speed Range 15-360 r.p.m. Comprehensive equipment.

PARKSON 1NA Universal Milling Machine. Speed Range 17-450 r.p.m. Comprehensive equipment.

EDGWICK No. 2 Plain Milling Machine. Speed Range 21-380 r.p.m.

ARCHDALE 20in. Production Milling Machine. Speed Range 30-619 r.p.m.

BROWN & SHARPE No. 10 Production Milling Machine. Speed Range 55-1,800 r.p.m.

WARD 7 Combination Turret Lathe. Taper Turning, Bar Feed and Chucking. Speed Range 37-750 r.p.m. Comprehensive equipment.

WARD 7, 3A, 2A, 1A Capstan Lathes arranged Bar Feed.

NORTON 16in. x 50in. Universal Grinding Machine. Comprehensive Equipment.

CHURCHILL 12in. x 36in. Universal Grinding Machine. Comprehensive equipment.

NEWALL Type L 10in. x 36in. Plain Grinding Machine.

JONES & SHIPMAN 10in. x 27in. Plain Grinding Machine.

B.S.A. Landis Type C 6in. x 18in. Plain Grinding Machine.

CHURCHILL 24in. Ring Grinder.

CHURCHILL 42in. Ring Grinder.

SCRIVEN 35 Centreless Grinder.

HENDEY 24in. x 16in. S.S. & S.C. Lathe. Speed Range 14-560 r.p.m.

F.L.C.B. 17in. x 10ft. S.S. & S.C. Lathe. Speed Range 108-152 r.p.m.

OLDFIELD & SCHOFIELD 15in. x 8ft. S.S. & S.C. Lathe. Gap Bed. Speed Range 6.5-332 r.p.m.

OLDFIELD & SCHOFIELD 124in. x 7ft. S.S. & S.C. Lathe. Gap Bed. Speed Range 12-400 r.p.m.

MONARCH 16in. x 30in. Type CY S.S. & S.C. Lathe. Speed Range 14-600 r.p.m.

CINCINNATI Type LT 8in. x 5ft. S.S. & S.C. Lathe. Speed Range 16-392 r.p.m.

LANG 9in. x 5ft. 6in. S.S. & S.C. Lathe. Speed Range 8.75-240 r.p.m.

DEAN SMITH & GRACE 7in. x 3ft. 6in. S.S. & S.C. Lathe. Gap Bed. Speed Range 11-490 r.p.m.

DEAN SMITH & GRACE 7in. x 2ft. 6in. S.S. & S.C. Lathe. Gap Bed. Speed Range 11-490 r.p.m.

DENHAM 6in. x 3ft. 0in. S.S. & S.C. Lathe. Gap Bed. Speed Range 10-400 r.p.m.

KITCHEN & WADE 5ft. No. 5 M.T. Radial Drilling Machine. Speed Range 20-1,000 r.p.m.

TOWN 3ft. No. 3 M.T. Radial Drilling Machine. Speed Range 126-1,450 r.p.m.

ARCHDALE 4ft. No. 4 M.T. Radial Drilling Machine. Speed Range 80-2,000 r.p.m.

ARCHDALE 3ft. No. 2 M.T. Radial Drilling Machine. Speed Range 126-1,440 r.p.m.

ASQUITH LDR 4ft. No. 3 M.T. Radial Drilling Machine. Speed Range 70-2,000 r.p.m.

CLIFTON & BAIRD Punching and Cropping Machine. Cap. 4in. x 4in. x 1in. angle.

BIGWOOD 4 Roll Bending and Straightening Machine. Cap. 4ft. x 1in.

Modern Machines—Motorised 400-440/3/50. Fully Overhauled—Six months' Guarantee.

WESTERN MACHINE TOOLS (SWANSEA) LTD.

72, MANSEL STREET, SWANSEA.

Tel.: 50661/2.

PEARSON

ELECTRO HYDRAULIC FLANGING PRESSES

Bulkhead Type up to 1,200 tons.

Plateshop Type 120 to 500 tons.

Robust all-welded construction incorporating the most modern developments.

T. B. PEARSON & SONS LTD., WALKER, NEWCASTLE UPON TYNE, 6.

Telephone: Wallsend 64081.

Herbert Imperator S.S. & S.C.

Lathe. 8in x 63 in., equipped.—C. DUGARD, LTD., Denmark Villas, Hove 32471.

Wickman 7/8 in. Sliding Head

Precision Automatic. Full equipment, late model.

EDWIN MILLEN,

70, Clerkenwell Road, London, E.C.1. 'Phone: CLerkenwell 6084.

There are
HUNDREDS
of
MACHINES
to choose
from
at
THE F.J.E. MACHINE CENTRE

ISLINGTON PARK STREET, NEAR
HIGHBURY CORNER, LONDON, N.1
(on the main A1 Road from the North)

BATEMAN All Electric Planing Machine, 16ft. x 5ft. x 5ft. two Cross Boxes, One Side Box, Sole-noids, Lamps, Dynamo drive and controls. 400/3/50.

W. FORREST & CO. LTD.

INDUSTRY WORKS,

SYLVESTER GARDENS,

SHEFFIELD, 1.

'Phone: 23314/5.

"Invicta" 4M Shaping Machine

In new condition. Motorised 440/6/50.

Seen running. Price £325 on site. Inspection London.—BOX 2361, MACHINERY, Clifton House, Euston Road, N.W.1.

Richmond (New) HB3/12 4ft. 6in.

Radial Drilling Machine. No. 4 M.T.

Motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tamworth Brook, Southamton.

Tel.: Southampton 73101.

200 Ton Tangye Hydraulic

Straightening Press, bed 25ft. by 3ft., stroke 21in., motorised travelling table, 3 ram pump.

Bigwood Motorised Geared Beam Bending Machine, all steel, rectangular ram 12in. by 14in.

Scriven 3-Roll Plate Bending Machine, rollers 14ft. wide, 1in. capacity.

Archdale 4ft. Radial Drilling Machine.

Herbert Filing and Sawing Machine, 15in. square adjustable table.

Alexander 16in. Cutting-off Machine.

Herbert Hack-saw, 13in. blade, belt driven.

Wickstead Hack-saw, 16in. blade, 6in. by 6in.

Rex Hack-saw, 18in. blade, 8in. by 8in.

Colchester 7in. Centre Lathe, 7ft. gap bed.

Herbert Horizontal Milling Machine, 3ND table 6in. by 15in., 4 spindle speeds.

3,000 K.G. Capacity Avery Hardness Testing Machine, 10in. dia. table (2).

50-ton Inclined Geared Open Press.

Crow Harvey Punch, Shears and Angle Cropper, 18in. blade, 27in. throat, heavy duty.

Fels Punch, Shears and Cropper, 12in. blade shear 1in., takes 6in. by 6in. by 1in. angles.

Craig & Donald Bullet Shears, 8in. blade, 6in. by 1in. capacity.

Robertson Shears, 1in. capacity, 10 h.p., 28in. blade, 9in. maximum opening (2).

Robertson 7-roller Plate Flattener, 8ft. 6in. wide, approximately 1in. capacity.

Sedgwick 6ft. Folding and Bending Machine.

Landis Pipe Screwing Machine up to 12in. bore.

Berry 3-roller Plate Bender, 7ft. wide, approximately 1in. capacity.

Sweeney Fly Presses, all sizes, 20 available.

New 1-cwt. and 2-cwt. Hammers by Massey and Alldays & Unions, also 3/5 cwt. secondhand.

Oliver Flaming Hammer, 29in. gap.

E.O.T. Crane.

60/5 ton Clyde Goliath, 40ft. span, unused.

40/5 ton Babcock Goliath, 40ft. span, unused.

40/5 ton Adamson, 42ft. 3in. span, almost new.

40 ton Clyde, 42ft. 3in. span, still packed.

30/5 ton Adamson, 42ft. 3in. span, almost new.

40 ton Vaughan, 42ft. 3in. span, almost new.

30/5 ton Vaughan, 42ft. 3in. span, cab type (6).

FRED WATKINS (ENGINEERING), LTD., Coleford, Glos. 'Phone: Coleford 2271 (3 lines).



RUNNING SHORT?

REMEMBER...

WARDS might have it!

THOS. W. WARD LTD

ALBION WORKS, SHEFFIELD

A Good Number of High-class

Machine Tools always in Stock.—

ELLISON COOK Street, off Chapel Street,

Railford, 3, Lancs.

When answering advertisements kindly mention MACHINERY.

In Stock NOW

AUTOMATICS

PONGRACZ Single Spindle Automatic capacity 10 mm.
CONOMATICS 3½in. four-spindle Bar Automatics. (Three available.)
BULLARD 8in. six-spindle Vertical Chucking Automatic.

BORING MACHINES

RICHARDS Type PRT Horizontal Type Floor Boring Machine, 3½in. dia. travelling spindle and 28in. dia. facing head.
FRORIEP Vertical Boring Mill, table diameter 39in., maximum turning capacity 52in. (1955.)
ASQUITH 7in. Horizontal Floor Boring Machine.
BERTHIEZ Model 9340 Vertical Boring Mill, table diameter 7ft. 10in., maximum turning capacity 9ft. 6in. (1953.)
JUNGENTHAL Model KE.1200 Vertical Boring Mill, table diameter 39in., maximum turning capacity 50in. (1954.)

CAPSTAN & CENTRE LATHES

BRADFORD 8½in. centre height by 30in. between centres Centre Lathe.
HERBERT No. 8 Combination Turret Lathe.
HERBERT No. 12 Combination Turret Lathe with comprehensive tooling.
NILES Centre Lathes 13½in. centre height by 27ft. between centres. (Two available.)
BETTS-BRIDGFORD Centre Lathe, 15in. centre height by 16ft. between centres. (Two available.)
WARD No. 7 Combination Turret Lathe.
GISHOLT Model 1L Universal Turret Lathe. (Two available.)
LIBBY Model 4A Capstan Lathe.

DRILLING MACHINES

KITCHEN & WADE 28V10 Single Spindle Vertical Drilling Machine, No. 4 M.T.
HETTNER Radial Drilling Machine, having 10ft. Radial Arm elevating column type.
KITCHEN & WADE 4ft. 6in. Radial Drilling Machine.
TOWN 30in. Vertical Spindle Boring, Drilling and Tapping Machine. No. 5 M.T.
KITCHEN & WADE 4ft. Radial Drilling Machine.
ASQUITH ODI 6ft. Radial Drilling Machine.

GEAR MACHINES

MUIR 72in. spur and helical Gear Generating Machine.
KOLB Gear Grinding Machine.
GLEASON No. 9 Bevel Gear Completer Machine.
ORCUTT 24in. Gear Grinding Machine.
SYKES V.10 Gear Generator.
GLEASON 3in. Bevel Gear Generators (Two available.)

GRINDING MACHINES

New **EXCEL** No. 3 Hydraulic Surface Grinding Machine
NORTON Universal Grinding Machine, Type "C", capacity 12in. by 36in.
CHURCHILL Universal Grinding Machine, 10in. by 24in. between centres.
B.S.A. LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machine, 6in. by 30in. (Two available.)
CHURCHILL Model HBY Internal Grinding Machine.
CHURCHILL Hydraulic Universal Grinding Machine, capacity 24in. by 84in.
BLANCHARD No. 10 Vertical Spindle Surface Grinding Machine.
LANDIS Hydraulic Universal Grinding Machine, 14in. by 36in. between centres.
LANDIS Type D Hydraulic Crank Pin Grinding Machine, capacity 21in. by 72in.
New **EXCEL** No. 5 Tool and Cutter Grinder.
LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machine, 10in. by 36in.
NORTON 6in. by 18in. Plain Cylindrical Grinding Machine.
ABWOOD Vertical Spindle Surface Grinding Machine, 6in. by 18in.

MILLING MACHINES

MILWAUKEE No. 2H Vertical Milling Machine, table 50in. by 10in.
SUNDSTRAND Hydro-Screw Rigidmill Automatic Production Milling Machine, table 7in. by 14in., table traverse 48in.
MILWAUKEE No. 4H Plain Horizontal Milling Machine, table 74in. by 15½in.
VICTOMATIC Automatic Cycle Production Milling Machine, capacity 50in. by 10in.
REED PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.
CINCINNATI Hydromatic 3/24 Duplex Production Milling Machine. (Two available.)
REED PRENTICE No. 6 Vertical Milling Machine, table 84in. by 20in.
CINCINNATI 1/12 Horizontal Production Milling Machine.
CENTEC Model 3R Automatic Production Milling Machine, table 6in. by 25in.
CINCINNATI 2M Universal Milling Machine.

PLANING, SLOTTING AND SHAPING MACHINES

STOCKBRIDGE 20in. Shaping Machine.
URQUHART LINDSAY & ROBERTSON ORCHAR Spiral Drive Heavy Duty Planing Machine, capacity 16ft. by 5ft. by 5ft.
FRORIEP Planing Machine, 13ft. stroke by 3ft. 6in. with Lancashire Dynamo drive.

MISCELLANEOUS

SHEEPBRIDGE 20in./22in. Hydraulic Cold Circular Sawing Machine.
BENNIE Punching, Cropping, Notching Machine, Punch 1½in. through ½in.


 RING

CHIPPING SODBURY 3311

or contact our nearest Representative

NEWMAN INDUSTRIES LIMITED

Machine Tool Division

Telephone: Chipping Sodbury 3311
 London (Sloane 8206). Birmingham (Midland 1143).

YATE, BRISTOL

Telegrams: "Dynamo, Yate"
 Manchester (Deansgate 2837/8). Glasgow (Central 2101/2).

Newman
for MACHINE TOOLS

IRISH BELLS for machine tools

LEEDS 63-7398

CINCINNATI No. 3 Dial Type Vertical Milling Machine. Speed Range 18-450 r.p.m.

HERBERT 47V Vertical Milling Machine. Speed Range 21-750 r.p.m.

ARCHDALE 18in. Vertical Milling Machine. Speed Range 70-2,000 r.p.m.

ARCHDALE 30in. Vertical Milling Machine. Speed Range 20-222 r.p.m.

MILWAUKEE 2H Universal Milling Machine. Speed Range 30-1,400 r.p.m. Comprehensive equipment.

BROWN & SHARPE No. 2 Universal Milling Machine. Speed Range 40-1,300 r.p.m.

PARKSON 2T Universal Milling Machine. Speed Range 15-360 r.p.m. Comprehensive equipment.

PARKSON 1A Universal Milling Machine. Speed Range 17-450 r.p.m. Comprehensive equipment.

EDGWICK No. 2 Plain Milling Machine. Speed Range 21-380 r.p.m.

ARCHDALE 20in. Production Milling Machine. Speed Range 30-619 r.p.m.

BROWN & SHARPE No. 10 Production Milling Machine. Speed Range 55-1,800 r.p.m.

WARD 7 Combination Turret Lathe. Taper Turning, Bar Feed and Chucking. Speed Range 37-750 r.p.m. Comprehensive equipment.

WARD 7, 3A, 2A, 1A Capstan Lathes arranged Bar Feed.

NORTON 16in. x 50in. Universal Grinding Machine. Comprehensive Equipment.

CHURCHILL 12in. x 36in. Universal Grinding Machine. Comprehensive equipment.

NEWALL Type L 10in. x 36in. Plain Grinding Machine.

JONES & SHIPMAN 10in. x 27in. Plain Grinding Machine.

B.S.A. Landis Type C 6in. x 18in. Plain Grinding Machine.

CHURCHILL 24in. Ring Grinder.

CHURCHILL 42in. Ring Grinder.

SCRIVENER 2C Centreless Grinder.

HENDEY 24in. x 16in. S.S. & S.C. Lathe. Speed Range 14-560 r.p.m.

F.L.C.B. 17in. x 10ft. S.S. & S.C. Lathe. Speed Range 108-152 r.p.m.

OLDFIELD & SCHOFIELD 15in. x 8ft. S.S. & S.C. Lathe. Gap Bed. Speed Range 6.5-332 r.p.m.

OLDFIELD & SCHOFIELD 12in. x 7ft. S.S. & S.C. Lathe. Gap Bed. Speed Range 12-400 r.p.m.

MONARCH 16in. x 30in. Type CY S.S. & S.C. Lathe. Speed Range 14-600 r.p.m.

CINCINNATI Type LT 8in. x 5ft. S.S. & S.C. Lathe. Speed range 16-392 r.p.m.

LANG 9in. x 5ft. 6in. S.S. & S.C. Lathe. Speed Range 8,75-240 r.p.m.

DEAN SMITH & GRACE 7in. x 3ft. 6in. S.S. & S.C. Lathe. Gap Bed. Speed Range 11-490 r.p.m.

DEAN SMITH & GRACE 7in. x 2ft. 6in. S.S. & S.C. Lathe. Gap Bed. Speed Range 11-490 r.p.m.

DENHAM 6in. x 3ft. 6in. S.S. & S.C. Lathe. Gap Bed. Speed Range 10-400 r.p.m.

KITCHEN & WADE 5ft. No. 5 M.T. Radial Drilling Machine. Speed Range 20-1,000 r.p.m.

TOWN 3ft. No. 3 M.T. Radial Drilling Machine. Speed Range 126-1,450 r.p.m.

ARCHDALE 4ft. No. 4 M.T. Radial Drilling Machine. Speed Range 80-2,000 r.p.m.

ARCHDALE 3ft. No. 2 M.T. Radial Drilling Machine. Speed Range 126-1,440 r.p.m.

ASQUITH LDR 4ft. No. 3 M.T. Radial Drilling Machine. Speed Range 79-2,000 r.p.m.

CLIFTON & BAIRD Punching and Cropping Machine. Cap. 4in. x 4in. x 1in. angle.

BIGWOOD 4 Roll Bending and Straightening Machine. Cap. 4ft. x 1in.

Modern Machines—Motorised 400-440/3/50. Fully Overhauled—Six months' Guarantee.

WESTERN MACHINE TOOLS (SWANSEA) LTD.

72, MANSEL STREET, SWANSEA.
Tel.: 50061/2.

PEARSON

ELECTRO HYDRAULIC FLANGING PRESSES

Bulkhead Type up to 1,200 tons.
Plateshop Type 120-500 tons.
Robust all-welded construction incorporating the most modern developments.

T. B. PEARSON & SONS LTD.,
WALKER, NEWCASTLE UPON TYNE, 6.
Telephone: Wallsend 64081.

Herbert Imperator S.S. & S.C.
Lathe. 8in x 63 in., equipped.—C.
DUGARD, LTD., Denmark Villas, Hove 32471.

Wickman 7 1/2 in. Sliding Head
Precision Automatic. Full equipment, late model.
EDWIN MILLEN,
70, Clerkenwell Road, London, E.C.1. 'Phone: CLerkenwell 6064.

There are
HUNDREDS
of **MACHINES**
to choose
from
at
THE F.J.E. MACHINE CENTRE
ISLINGTON PARK STREET, NEAR
HIGHBURY CORNER, LONDON, N.1
(on the main A1 Road from the North)

BATEMAN All Electric Planing Machine, 16ft. x 5ft. x 5ft. two Cross Boxes, One Side Box, Sole-noids, Lances, Dynamo drive and controls. 400/3/50.

W. FORREST & CO. LTD.
INDUSTRY WORKS,
SYLVESTER GARDENS,
SHEFFIELD, 1.
'Phone: 23314/5

"Invicta" 4M Shaping Machine
in new condition. Motorised 440/8/50.
Seen running. Price £325 on site. Inspection
London.—BOX Z361, MACHINERY, Clifton
House, Euston Road, N.W.1.

Richmond (New) HB3/12 4ft. 6in.
Radial Drilling Machine, No. 4 M.T.
Motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tamers Brook, Mildred, Southampton. Tel.: Southampton 73101.

200 Ton Tangye Hydraulic

Straightening Press, bed 25ft. by 3ft., stroke 21in., motorised travelling table, 3 ram pump.

Bigwood Motorised Geared Beam Bending Machine, all steel, rectangular ram 12in. by 14in.

Scriven 3-Roll Plate Bending Machine, rollers 14ft. wide, 4in. capacity.

Archdale 4ft. Radial Drilling Machine.

Herbert Filing and Sawing Machine, 15in. square adjustable table.

Alexander 16in. Cutting-off Machine.

Herbert Hackaw, 13in. blade, belt driven.

Wicksteed Hackaw, 16in. blade, 6in. by 6in.

Rez Hackaw, 18in. blade, 8in. by 8in.

Colchester 7in. Centre Lathe, 7ft. gap bed.

Herbert Horizontal Milling Machine, 3ND table 61in. by 15in., 4 spindle speeds.

3,000 K.G. Capacity Avery Hardness Testing Machine, 10in. dia. table (2).

50-ton Inclined Geared Open Press.

Crow Harvey Punch, Shears and Angle Cropper, 18in. blade, 27in. throat, heavy duty.

Pels Punch, Shears and Cropper, 12in. blade shear 1in., takes 6in. by 6in. by 1in. angles.

Craig & Donald Billet Shears, 8in. blade, 6in. by 1in. capacity.

Robertson Shears, 4in. capacity, 10 h.p., 28in. blade, 9in. maximum opening (2).

Robertson 7-roller Plate Flattener, 8ft. 6in. wide, approximately 1in. capacity.

Sedgwick 6ft. Folding and Bending Machine.

Landis Pipe Screwing Machine up to 12in. bore.

Berry 3-roller Plate Bender, 7ft. wide, approximately 1in. capacity.

Sweeney Fly Presses, all sizes, 20 available.

New 1-cwt. and 2-cwt. Hammers by Massey and Alldays & Onions, also 3/5 cwt. secondhand.

Oliver Flanshing Hammer, 29in. gap.

E.O.T. Cranes.

60/5 ton Clyde Goliath, 40ft. span, unused.

40/5 ton Babcock Goliath, 40ft. span, unused.

40/5 ton Adamson, 42ft. 3in. span, almost new.

40 ton Clyde, 42ft. 3in. span, still packed.

30/5 ton Adamson, 42ft. 3in. span, almost new.

40 ton Vaughan, 42ft. 3in. span, almost new.

30/5 ton Vaughan, 42ft. 3in. span, cab type (6).

FRED WATKINS (ENGINEERING), LTD., Coleford, Glos. 'Phone: Coleford 2271 (3 lines).



RUNNING SHORT?

REMEMBER...

WARDS might have it!

THOS. W. WARD LTD
ALBION WORKS, SHEFFIELD

A Good Number of High-class
Machine Tools always in Stock—
ELLISON, Cook Street, off Chapel Street,
Salford, 3, Lancs.

When answering advertisements kindly mention MACHINERY.

In Stock NOW

AUTOMATICS

PONGRACZ Single Spindle Automatic capacity 10 mm.
CONOMATICS 3 $\frac{1}{2}$ in. four-spindle Bar Automatics. (Three available.)
BULLARD 8in. six-spindle Vertical Chucking Automatic.

BORING MACHINES

RICHARDS Type PRT Horizontal Type Floor Boring Machine, 3 $\frac{1}{2}$ in. dia. travelling spindle and 28in. dia. facing head.
FRORIEP Vertical Boring Mill, table diameter 39in., maximum turning capacity 52in. (1955.)
ASQUITH 7in. Horizontal Floor Boring Machine.
BERTHIEZ Model 9340 Vertical Boring Mill, table diameter 7 $\frac{1}{2}$ in., maximum turning capacity 9ft. 6in. (1953.)
JUNGENTHAL Model KE.1200 Vertical Boring Mill, table diameter 39in., maximum turning capacity 50in. (1954.)

CAPSTAN & CENTRE LATHES

BRADFORD 8 $\frac{1}{2}$ in. centr. height by 30in. between centres Centre Lathe.
HERBERT No. 8 Combination Turret Lathe.
HERBERT No. 12 Combination Turret Lathe with comprehensive tooling.
NILES Centre Lathes 13 $\frac{1}{2}$ in. centre height by 27ft. between centres. (Two available.)
BETTS-BRIDGFORD Centre Lathe, 15in. centre height by 16ft. between centres. (Two available.)
WARD No. 7 Combination Turret Lathe.
GISHOLT Model 1L Universal Turret Lathe. (Two available.)
LIBBY Model 4A Capstan Lathe.

DRILLING MACHINES

KITCHEN & WADE 28V10 Single Spindle Vertical Drilling Machine, No. 4 M.T.
HETTNER Radial Drilling Machine, having 10ft. Radial Arm elevating column type.
KITCHEN & WADE 4ft. 6in. Radial Drilling Machine.
TOWN 30in. Vertical Spindle Boring, Drilling and Tapping Machine. No. 5 M.T.
KITCHEN & WADE 4ft. Radial Drilling Machine.
ASQUITH ODI 6ft. Radial Drilling Machine.

GEAR MACHINES

MUIR 72in. spur and helical Gear Generating Machine.
KOLB Gear Grinding Machine.
GLEASON No. 9 Bevel Gear Completer Machine.
ORCUTT 24in. Gear Grinding Machine.
SYKES V.10 Gear Generator.
GLEASON 3in. Bevel Gear Generators (Two available.)

GRINDING MACHINES

New **EXCEL** No. 3 Hydraulic Surface Grinding Machine
NORTON Universal Grinding Machine, Type "C", capacity 12in. by 36in.
CHURCHILL Universal Grinding Machine, 10in. by 24in. between centres.
B.S.A. LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machine, 6in. by 30in. (Two available.)
CHURCHILL Model HBY Internal Grinding Machine.
CHURCHILL Hydraulic Universal Grinding Machine, capacity 24in. by 84in.
BLANCHARD No. 10 Vertical Spindle Surface Grinding Machine.
LANDIS Hydraulic Universal Grinding Machine, 14in. by 36in. between centres.
LANDIS Type D Hydraulic Crank Pin Grinding Machine, capacity 21in. by 72in.
New **EXCEL** No. 5 Tool and Cutter Grinder.
LANDIS Type "C" Plain Hydraulic Cylindrical Grinding Machine, 10in. by 36in.
NORTON 6in. by 18in. Plain Cylindrical Grinding Machine.
ABWOOD Vertical Spindle Surface Grinding Machine, 6in. by 18in.

MILLING MACHINES

MILWAUKEE No. 2H Vertical Milling Machine, table 50in. by 10in.
SUNSTRAND Hydro-Screw Rigidmill Automatic Production Milling Machine, table 7in. by 14in., table traverse 48in.
MILWAUKEE No. 4H Plain Horizontal Milling Machine, table 74in. by 15 $\frac{1}{2}$ in.
VICTOMATIC Automatic Cycle Production Milling Machine, capacity 50in. by 10in.
REED PRENTICE No. 5 Vertical Milling Machine, table 68in. by 16in.
CINCINNATI Hydromatic 3/24 Duplex Production Milling Machine. (Two available.)
REED PRENTICE No. 6 Vertical Milling Machine, table 84in. by 20in.
CINCINNATI 1/12 Horizontal Production Milling Machine.
CENTEC Model 3R Automatic Production Milling Machine, table 6in. by 25in.
CINCINNATI 2M Universal Milling Machine.

PLANING, SLOTTING AND SHAPING MACHINES

STOCKBRIDGE 20in. Shaping Machine.
URQUHART LINDSAY & ROBERTSON ORCHAR Spiral Drive Heavy Duty Planing Machine, capacity 16ft. by 5ft. by 5ft.
FRORIEP Planing Machine, 13ft. stroke by 3ft. 6in. with Lancashire Dynamo drive.

MISCELLANEOUS

SHEEPBRIDGE 20in./22in. Hydraulic Cold Circular Sawing Machine.
BENNIE Punching, Cropping, Notching Machine, Punch 1 $\frac{1}{2}$ in. through $\frac{1}{2}$ in.

RING

CHIPPING SODBURY 3311

or contact our nearest Representative

NEWMAN INDUSTRIES LIMITED

Machine Tool Division

Telephone: Chipping Sodbury 3311

Lon'on (Sloane 8206).

Birmingham (Midland 1143).

YATE, BRISTOL

Telegrams: "Dynamo, Yate"

Manchester (Deansgate 2837/8).

Glasgow (Central 2101/2).

Newman
for MACHINE TOOLS

Classified Advertisements (PLANT FOR SALE, contd.)

MACHINE TOOLS

SELECTIONS FROM LARGE STOCKS

KEARNS OC Horizontal Borer.
FRORIEP 48in. Vertical Borer, side head.
FENSBY 30in. Vertical Bore, side head.
BROWN & SHARPE No. 2 Vertical Miller.
MILWAUKEE 3H Vertical Miller, dial type.
CINCINNATI No. 2 Vertical Miller, dial type.
ARCHDALE 12in., 18in., 24in. and 30in. Vertical Mills.
CINCINNATI OS Auto Cycle Millers.
KENT OWEN 1-14 Miller.
ARCHDALE 28in. Horizontal Miller.
RICHLAND OS Universal Miller, 84in. by 9in.
EDGEMORE No. 2 Sintermill, 37in. by 12in.
CLEVELAND 24in. Automatics.
HERBERT No. 5 Auto. 18in. by 31in.
CONOMAT 4in. 4-spindle Automatic.

ASQUITH 6ft. Radial Drill.
KITCHEN & WADE 4ft. 6in. Radial Drill.
ARCHDALE "O" Multi Drill.
POLLARD 12X Multi Drill.
HERBERT Type V Drill.
POLLARD 4-spindle Sensitive Drill.
JONES & SHIPMAN 1in. Tapping Machines.

ORMEROD 26in. Slotter.
BETTS 12in. Slotter.
ORMEROD 18in. Traversing Head Shaper.

OSTER 6in. Screwing Machine.

SNOW NC14 Face Grinder.
HEALD 72 Siamatic Duplex Internal Grinder.
CHURCHILL HBS Automatic Internal Grinder.
CHURCHILL 8in. by 19in. Semi-Universal Grinder.
CHURCHILL 10in. by 24in. Universal Grinder.
CHURCHILL 12in. by 36in. Universal Grinder.
BROWN & SHARPE No. 2 Surface Grinder.
SNOW 24in. by 8in. Surface Grinder.
SNOW T.20 and T.14 Table Surface Grinders.
GARDNER 50in. Disc Grinder.
NEW OLIVETTI 13in. Swing by 48in. Cylindrical Grinders.

CHURCHILL 18in. by 6in. Plain Grinder.
MULTIMAT 7in. Capacity Centreless Grinder.
LANDIS 12in. by 32in. Crankshaft Grinder.
NEWALL 10in. by 48in. Model L.A. Hydraulic Cylindrical Grinders.
VAN NORMAN 16in. Raceway Grinders.
NEW MITCHELL 16in. Lathe, 17ft. 6in. between centres.
NEW MITCHELL 14in. Lathe, 9ft. 9in. between centres.
NEW MITCHELL 12in. Lathe, 10ft. 9in. between centres.
COLCHESTER Mascot 8in. Gap Bed Lathes.
HENDEY 14in. by 30in. Lathes.
WILLSON 7in. by 6ft. Gap Bed Lathes.
WARD No. 7 Capstan Lathe.
WARD 2A Capstans.
BARDONS & OLIVER No. 5 Capstan.
HERBERT 5B Capstan.
LIBBY 4A Capstan, bar feed, 24in.
HERBERT 2B Capstan, bar feed, 11in.
WARD No. 7 Combination Turret Lathe.
BEYLINGSTADT 48in. Surfacing and Boring Machine.

ALEXANDER Broaching Machine, 40in. stroke.
SYKES V10 Gear Generators, 0in.-14in. capacity.
CHURCHILL Cleveland 6in. Right Hobber.
ROBLE & LUND 5in./60in. Sawing Machines.
CLIFTON & WADDELL 15in. Sawing Machine.

Inspect under ideal conditions at
THE F.J.E. MACHINE CENTRE,
ELINGTON PARK STREET,
Nr. Highbury Corner, LONDON, N.1.

F. J. EDWARDS LTD.,
359-361, EUSTON RD., LONDON, N.W.1
Telephone: EUston 4681-3771.

And at Lansdowne House, 41, Water St.
Birmingham, 3. Telephone: Central 7606-8



JONES & SHIPMAN Model 540 Surface Grinder.

38in. Radial Sensitive Drilling Machine, ARCHDALE No. 3 M.T.

10in. x 4ft. Between Centres MITCHELL Centre Lathe.

No. 3 EXCEL Filing and Sawing Machine.

14in. BUTLER Slotting Machine, 39in. diameter table. 9-40 strokes per minute.

24in. x 9in. BUYER High-speed Vertical Milling Machine. Spindle speeds 265-1,860 r.p.m. As new.

27in. WOTAN Hydraulic Shaper. Automatic feeds and rapid traverses to the table. Ram speeds 16-98ft. per minute. Overhauled.

52in. x 10in. CINCINNATI Vertical Milling Machine. Model 2M. Power feeds and rapid traverses. Excellent condition.

10in. x 24in. NEWALL Type L.U. Universal Grinder. Hydraulic. Complete with internal spindle.

10in. x 24in. CHURCHILL Hydraulic Universal Grinder. Complete with internal spindle.

DIMCO (Gt. Britain) LTD.,

28, WOOD LANE,

SHEPHERD'S BUSH,

LONDON, W.12.

SHEPHERD'S Bush 401.

Herbert No. 7 Junior Combination Turret Lathe, 24in. hollow spindle, comprehensive turret equipment, motorised 400/3/50.—**SOUTHERN ENGINEERING & MACHINERY CO.,** Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Grinding Machines. Jones Shipman Fig. 1204 EUR, 8in. x 22in. Universal (nearly new). Jones Shipman Fig. 138, 10in. x 27in. Universal (1948). Myford MG9 5in. x 9in. Internal-External. Two Lumsden 70LEOD Vertical Surface 48in. x 12in. with chuck, etc., from £850.—**TATE MACHINE TOOL CO. LTD.,** 6, North End Parade (opp. Olympia), London, W.14. Telephone: Fulham 6563 (3 lines).

Herbert No. 4 Senior Capstan Lathes, with pre-optic heads in excellent condition. £500 each. Also one standard A.G.H. machine at £500. Inspect South London area.—**BOX 2568, MACHINERY, Clifton House, Euston Road, N.W.1.**

As our stock
changes very rapidly
it is not possible
to list weekly the
machines actually available.

ELGAR

MACHINE TOOL CO. LTD.

172-178 Victoria Road, Acton, W.3.

(Opposite North Acton station.)

ACOrn 5555

**Over 250 new Machine
Tools in stock.**

When answering advertisements kindly mention **MACHINERY.**

K·E·N·T

Ward No. 2A Capstan Lathes. £150-£250 each.

Holbrook 84in. S.S. & S.C. Lathe. Taper turning and collets. £375.

Herbert No. 1 Horizontal Lever Milling Machine. £75.

Zbrojovka Vertical Milling Machine. Sliding swivel head, 47in. x 12in. table. Power feed all ways and rapid. £475.

Ward No. 3A Capstan Lathes. £225.

Southend 5in. S.S. & S.C. Lathe. Full Eq. Nearly new. £175.

Stevens & Bullivant No. 10 Rotary Swaging Machine. £125.

Smith & Mills 16in. Shaping Machine. £275.

Herbert & Weingarten 30-ton Power Press, 4in. to 34in. Adj. Stroke. £375.

G. & L. "Grand Rapids" No. 25 Horizontal Spindle Surface Grinder. £275.

Speedax No. 2 Riveter. £35.

Jos. Heap 1in. Tangential Screwing Machine. £165.

Lang 84in. S.S. & S.C. Lathe. T.T. A.G.H. £695.

Van-Norman 22L Hori-Vert. Milling Machine. £695.

Archdale 18in. Vert. Milling Machine. Fixed head. £250.

Brown & Sharpe 2A Universal Mill, with high speed vertical head. £625.

Colchester "Mascot" 84in. x 4ft. 6in. S.S. & S.C. Lathe. £328.

Abwood Vertical Spindle Surface Grinder. £225.

Edwards 6ft. x 14g. Heavy Universal Edging, Bending and Folding Machine. £120.

All machines mot. 400-440/3/50.

**K·E·N·T MACHINERY &
ENGINEERING CO.**

Datchelor Place, London, S.E.5.

Telephone: ROD 4149.

LEONARD ROTH

**ABBOT STREET,
KINGSLAND HIGH STREET,
DALSTON JUNCTION,
LONDON, E.8.**

TERMS ARRANGED

Tel.: CLImond 0518/4

CARDIFF 7in. S.S.S.C. Lathe. A.G.H., 40in. between centres, 9in. 3-jaw and 10in. 4-jaw chucks, steadies, faceplate, etc. 400/3/50. £595.

FRATT & WHITNEY S.S.S.C. Lathe. A.G.H., 60in. between centres, 18in. hollow mandrel, 84in. 3-jaw and 12in. 4-jaw chucks, faceplate, 3-point steady. 400/3/50. £175.

GRIMSTON ELEKTRISKA Geared Head Drilling Machine. Pedestal type, 400/3/50. £50.

REINECKER A.G. Horizontal Milling Machine. Table 3ft. 11in. by 18in. Dial Indexing. Motorised 400/3/50 and auto pump. £195.

**WE HOLD BIG STOCKS OF LATHES,
SHAPERS, MILLS, DRILLS, PRESSES,
ETC.**

PLEASE WRITE FOR LISTS

Two Belliss & Morcom 2,500
c.f.m. Compressors, 100 lbs. w.p., 550 h.p. motors, 6,600/3/50 supply. Used 4 years only. With inter. and after-cooler. Receiver, Switch panel. Available immediately.—**FRED WATKINS (ENGINEERING), LTD.,** Coleford, Glos. Phone: Coleford 2271/2/3.

Classified Advertisements (PLANT FOR SALE, contd.)

-BETTER TRY 600 FIRST!

for NEW AND USED MACHINE TOOLS

ASQUITH Model EGC 4ft. 0in. Arm Portable Plate Radial Drilling Machine. Spindle bored No. 5. M.T. 12 spindle speeds 16-430 r.p.m. 4 rates of power feed. Motor drive 400/3/50.

G.S.P. Model 48-S-25 9ft. 0in. Heavy Duty Radial Arm Drilling Machine. Spindle bored No. 6. M.T. 24 spindle speeds 8-1,725 r.p.m. 12 rates of feed. Working surface of base 109in. by 54in. Motor drive 400/3/50.

HASSE & WREDE 9in. All Gearing Head Sliding and Surfacing Straight Bed Lathe. Admits 40in. between centres. 12 spindle speeds 47.5 to 600 r.p.m. Motor drive 400/3/50.

HERBERT No. 98 Combination Turret Lathe, Flaming Bed. 4 1/2in. dia. Hollow Spindle. Arranged for screwcutting. 16 spindle speeds 14 to 403 r.p.m. Motor drive 400/3/50.

B.S.A. 9in. Chucking Auto. Spindle speeds by pick off gears 32.5 to 845 r.p.m. Fitted with square turret, front and rear tool slides. Motor drive 400/3/50.

CLEVELAND Model "A" 3 1/2in. Single Spindle Automatic Lathe. Max. bar capacity 3 1/2in. Turning length 7 1/2in. Stock feed 13 1/2in. Speeds by pick off gears 28-732 r.p.m. With quantity of equipment. Motor drive 400-440/3/50.

CINCINNATI 48in. Hydromatic Milling Machine. Table size 67in. by 18in. 8 spindle speeds by pick off gears 20 to 150 r.p.m. Hydraulic table feeds 0 to 40in. per minute. Motor drive 400/3/50.

CHURCHILL 12in. by 36in. Universal Grinding Machine. Swivelling table for taper grinding. Hand and Auto feed to hydroto bearing wheel head. Variable D.C. work head. Complete with chucks, steadies, coolant and internal spindle. Motor drive 400/3/50.

SYKES Model V.10 Gear Hobbing Machine. Capacity 14in. dia. Maximum stroke 2 1/2in. long. 8 cutter speeds 149 to 622 strokes per minute. Motor drive 400/3/50.

NOBLE & LUND 4 1/2in. Fluid-feed Cold Sawing Machine. With swivelling work vice, 3 blade speeds 40, 60 and 87ft. per minute, infinitely variable hydraulic feeds to saw blade. Motor drive 400/3/50.

RICHARDS 36in. Single Column Vertical Boring and Turning Mill. With 36in. dia. 4-jaw table having a maximum swing of 39 1/2in. dia. Hexagonal tool slide. 12 table speeds 6-11 to 121 r.p.m. Motor drive 20 h.p. 400/3/50.

MILWAUKEE Model 2H Vertical Milling Machine. Table 50in. by 10in. 16 spindle speeds 35 to 1,400 r.p.m. Power feeds all directions, including down feed to head. Motor drive 400/3/50.

**GEORGE COHEN
SONS & COMPANY LIMITED**
Sunbeam Road, London, N.W.10
Tel: Elgar 7222/7
Stanningley, Nr. Leeds.
Tel: Pudsey 2241

JUST PURCHASED! NOW IN STOCK AT OUR WELSH HARP SHOWROOMS

ARCHDALE 5ft. Radial Drill No. 5 M.T. Speeds, Elec. Coolant, low base with loose box table 3ft. by 4ft. by 2ft. 3in. Motorised 415/3/50. Nearly new condition.

BUTLER Super Shaper. 26in. Stroke, eight speeds 9 to 100 strokes per minute. Power feed to head, power and rapid traverses to table, Universal tilting and swivelling table, 16in. Vice, motorised 415/3/50. New condition.

BUTLER 12in. Precision Slotting Machine. 25in. rotary table, auto feed in all directions, four speeds to ram. Motorised 415/3/50. Excellent condition.

ROCKFORD 24in. Hydraulic Shaper. Power and Rapid Traverses to table, Universal tilting and swivelling table 14in. Vice. Motorised 415/3/50. First class condition.

THOMPSON Type F2 Surface Grinder. 24in. by 8in., Hydraulic Feed to table in both directions, with rapid traverse to wheel head. Built-in Coolant. Motorised 415/3/50. Excellent condition.

BROWN & SHARPE No. 5 Plain Grinder. 3in. swing by 18in. B/C. Longitudinal power feed to table, 6in. to 133in. per min. Cross feeds 0.00025in. to 0.0045in. Coolant. Motorised 415/3/50. Excellent condition.

CINCINNATI No. 2 Tool and Cutter Grinder, Universal workhead with full range of standard equipment. Motorised 415/3/50. Excellent condition.

CLIFTON & BAIRD 24in. Cold Saw. Hydraulic, with Bar Stand. Motorised 415/3/50. Good condition.

BROWN & SHARPE No. 2 (Standard) vertical Milling Machine. Table 54in. by 14in., power feeds and rapid traverses in all directions. Spindle speeds 30 to 1,200 r.p.m. with power feeds. Coolant, etc. Motorised 415/3/50. Excellent condition.

NORTON Universal Grinder 12in. by 36in. B/C Type C. Hydraulic feeds to table. 7in./144in. per min. D.C. Workhead. Elec. coolant. Motorised 415/3/50. Excellent condition.

ARCHDALE 18in. vertical Milling Machine, high speed, 79 to 2,000 r.p.m. Sliding head with sensitive and geared hand feeds. Table 40in. by 10in., longitudinal power feeds, elec. coolant. Motorised 415/3/50. Late type in first class condition.

ESSEX No. 32 Punch Shaping Machine. 1 1/2in. to 4 1/2in. stroke 36-52-65 strokes/min. Microscope, etc. Motorised 415/3/50. Late type in first class condition.

LANG Junior 17in. Surfacing, boring and S.C. lathes. Speeds 19 to 900 r.p.m. Hexagon turret with surfacing and sliding feeds. 16in. chuck, all turret tooling, coolant, etc. Motorised 415/3/50. Excellent condition.

PRATT & WHITNEY Toolroom Lathe. 12in. swing by 30in. Speeds 18 to 525 r.p.m. Camlock spindle, S.S. & S.C., A.G.H., Norton gearbox, well equipped. Motorised 415/3/50. Excellent condition.

CORONA 15 EX and 15 AX four-spindle drills, pole change motors, speeds 4 from 470 to 1,465 r.p.m. Table 46in. by 16in. R. & F. No. 2 Morse Taper spindles. Hand Feed. Very good condition.

A. LAWRENCE & CO. (Machine Tools) LTD.
Welsh Harp, Edgware Road, N.W.2. Telephone: GLA 0033

C.V.A. No. 8 Single Spindle
Automatic Lathes, 2 machines. Reconditioned in 1954. With third slide. £500 each to clear.—BOX Z558, MACHINERY, Clifton House, Euston Road, N.W.1.

Colchester Mascot (New), 8in.
height by 54in. between centres S.S. & S.C. Gap Bed Centre Lathe. Motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook Southampton. Tel.: Southampton 73101.

WARD No. 7 Combination Turret Lathe
A.C. motor drive. Covered bed. With front and back toolposts, automatic ball chuck and bar feed.

WARD No. 8 Combination Turret Lathe
A.C. motor drive, 4 1/2in. H.S. With taper turning attachment, 12in. three-jaw chuck.

HERBERT No. 95 Combination Turret Lathe
A.C. motor drive, 4 1/2in. H.S. Very well equipped with chucks, toolholders, etc.

Robinson

4/6, Minerva Road, Park Royal,
LONDON, N.W.10.
Telephone: ELGar 4841-4842.

Milling Machines. Cincinnati
4/36 Hydromatic Serial 4009/1 and Serial 4012/1, excellent condition. Archdale 24in. Production Mill with Autocycle (1946). ROUCAUD 40in. x 10in. Plain Horizontal with Autocycle (1952). Edgwick Horizontal 40in. x 10in. Cincinnati 80in. x 8in. Wadkin LXA 36in. x 12in. Vertical. Pallas Model HO Plain 30in. x 8in. Pallas Model HOO Plain 22in. x 7 1/2in. Senior Model M1 Plain h.d.—TATE MACHINE TOOL CO. LTD., 6, North End Parade (opp. Olympia), London, W.14. Telephone: Fulham 6583 (3 lines).

Archdale 4ft. Radial Drilling Machine. Low base, elevating arms. Spindle bored No. 4 M.T. Single pulley drive.—ALBERT EDWARDS (MACHINERY), LTD., 79/89, Pentonville Road, London, N.1. Phone: Terminus 0167/8/9.

Gang Slitting Machine For Sale.
With separate strip coiling unit. Capacity 14 s.w.g. Width between housings 20in. Diameter of cutter shaft 3in. Two pairs of cutters. Motor drive 400/3/50.—F. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1. or 41, Water Street, Birmingham, 3.

Ward No. 7 Capstan, Covered
bed, 415/3/50, Ball chuck, Bar feed.—exceptional order.—C. DUGARD, LTD Denmark Villas, Hove 82471.

When answering advertisements kindly mention MACHINERY.

O2

Classified Advertisements (PLANT FOR SALE, contd.)

Shapers. Invicta 6MR 24in.
Shaper (nearly new), £425. Newey 14in.—
TATE MACHINE TOOL CO., LTD., 6, North
End Parade (opp. Olympia), London, W.14.
Telephone: Fulham 6563 (3 lines).

No. 4 Cincinnati Plain Milling
Machine. Dial type. High speed
S.C. motor drive 400/3/50. Table 74in. by 16in.
Speeds 15-1,500 r.p.m. Auto feeds all ways.—
LEE & HUNT, LTD., Crocus Street, Nottingham.
Tel.: 94240.

ACBARS LIMITED

57a, HOLBORN VIADUCT,
LONDON, E.C.1.

Telephone: Central 2287. Telegrams: Acfrb. Cent. London

AVAILABLE FROM STOCK
All machines listed below are at our
Works in Sutherland Walk, Wal-
worth Road, S.E.17.

AUTOMATICS

INDEX 18 Auto.
HERBERT Auto. Junior.
HERBERT 3A Chucking Auto.
ACME-GRIDLEY, Type R, 4-spindle, 3in.
capacity.
ACME-GRIDLEY, Type R, 4-spindle, 1 1/2in.
capacity. (2 machines.)
WICKMAN 4mm. Swiss Type.
BECHLER 7mm. Swiss.
RYDERMATIC No. 12 Multi Tool Lathes.

BORERS

New GRAFFENSTADEN AF.075 Horizontal
Borer, 3in. dia. travelling spindle,
17 1/2in. dia. faceplate.

GRINDERS

ABWOOD Vertical Spindle Surface.
BROWN & SHARPE No. 2 Surface Grinder.
JONES & SHIPMAN Fig. 62M Plain Cyl.,
8in. dia. by 10in.
LANDIS 10in. by 18in. Plain Grinder.
CHURCHILL 24in. by 10in. Universal.
BRYANT 16C 16in. Internal Grinder.
SMART & BROWN Internal Grinder.
ROWLAND three wheel Carbide Tool
Grinder and Capper.

CAPSTAN LATHES

HERBERT No. 0 1/2in. collet cap. (2).
MURAD 3in. Capstan Lathe.
SOUTHWARK No. 2 1 1/2in. Capstan Lathe.
DRUMMOND Type K Capstan Lathes (2).
GISHOLT No. 4 Friction Head Capstan.
LIBBY 4R 2in. Capstan Lathe. Bar feed.
BARDONS & OLIVER No. 5 Capstan Lathe.
HERBERT No. 7 Turret Lathe.
FOSTER No. 28 Turret Lathe.

CENTRE LATHES

SOAG OXFORD 65in. Centre Lathe.
SOUTHBEND 13in. swing taper turning.
WILLSON 8 1/2in. A.G.H. Lathe.
CARDIFF 8 1/2in. by 48in. Lathe.

MILLERS

HERBERT No. 1 Horizontal.
VICTORIA HO Plain.
New VICTORIA U1 and U2 Universal.
ARCHDALE 20in. Horizontal Mills (3).
ARCHDALE 28in. Horizontal Mill.
RICHMOND VHM Vertical Mill.
New VICTORIA V2 Vertical.
HOLROYD T117 Thread Miller.
HELLER Automatic Thread Millers (4).

MISCELLANEOUS

TAYLOR No. 1 Cutting-off Machine for
Tubes and Bars.
JONES & SHIPMAN 2-spindle Pillar Drill,
with No. 3 M.T. spindle, power feed.
New ESSEX 18 Bandaw.
New RICHMOND SR2 3ft. Radial Drill.
All Machines motorised 400/3/50 unless
otherwise stated.

NEW MITCHELL LATHE

16 1/2in. centre by 24ft. bed.
Admit 17ft. 9in. between centres,
4 1/2in. hollow spindle, swing in gap
6 1/2in. diameter by 18 1/2in. wide.

F. J. EDWARDS LTD.,

359-361 Euston Road,
London, N.W.1

EUston 4681 and 3771

40 Ton Double-sided Power

Press. Stroke 13in. 400/3/50.—HICKS
MACHINERY, LTD., 26, Addison Place,
London, W.11. Tel.: PARK 2333.

Bullard 24in. Vertical Boring

Machine. With slide head. M/D 400/3/50.
—ALBERT EDWARDS (MACHINERY), LTD.,
79/89, Pentonville Road, London, N.1. Phone:
Terminus 0167/8/9.

SHAPERS.

ROCKFORD HY-DRAULIC SHAPER.

28in. stroke. Var. speed ram 15-150 per
min. Var. feed. Hydraulic control all
ways. Table movement 180 deg. each way.
Quadrant insert in table 15 deg. each way.
Fully motorised 400-440/3/50. Push button
control. This machine has been rebuilt to
close limits and is virtually as new.

BOX Z646, MACHINERY,
Clifton House, Euston Road, N.W.1.



New & Used Machine Tools

J. & S. 4ft. Radial Drill. No. 4 M.T. Low
base, box table. Power elevation to
arm. Mot. 400/3/50.
CINCINNATI No. 2 Tool and Cutter
Grinder. Mot. 400/3/50.
DENHAM Heavy Duty A.G.H. Gap bed
Centre Lathe, 11in. centre height,
9ft. 6in. between, 44in. swing in gap.
4 1/2in. H.M. Motorised 400/3/50.
BROWN & SHARPE No. 13 Universal
and Tool Grinder.
ELECTRISKA 1 1/2in. cap. Geared 27in.
Column Drilling Machine. (New.)
POLLARD 4 Spindle Drill. No. 2 M.T.
Mot.
EDWARDS 4ft. by 14g. Universal Swing
Beam Folder.
BLISS No. 20 Power Press, 1 1/2in. stroke.
NORTON Hori. Spindle Surface Grinder,
36in. table with 24in. by 8in. mag. chuck.
ARCHDALE 14in. Horizontal Mill, 26in.
by 8in. table, 3 available.
FALLAS HO Horizontal Mill, 30 by 7 table.
Motorised 400/3/50.

STRAIGHT & VINES LTD.

MINT STREET, BOROUGH,
LONDON, S.E.1.

Telephone: HOP 4364.

Richmond (New) SR2 4ft. 0in.

Radial Drilling Machine, No. 3 M.T., rise
and fall tilting table. Motorised 400/3/50.—
SOUTHERN ENGINEERING & MACH-
INERY CO., Connaught Buildings, Tanners
Brook, Millbrook, Southampton. Tel.: South-
ampton 73107.

THE SPOT TO WATCH!

FOR GOOD CLASS SECOND-HAND MACHINES AT LOW COST

HERBERT 3A (Chucking) Automatic.
GIDDINGS & LEWIS 25T Hor. Borer.
BULLARD 24in. Borer. Converted M/D.
WARD 1A, 2A Capstans.
HERBERT No. 1, 2S, 2B, 4S Capstans.
HERBERT No. 4 Pre-optive Capstan.
WARNER & SWASEY No. 4 Pre-optive
Capstan.
WARNER & SWASEY No. 2 and No. 5
Capstans.
GISHOLT No. 4 Capstan.
FALLAS No. 2 Surface Grinder.
NORTON 18in. x 6in. Surface Grinder.
CHURCHILL HDY Internal Grinder.
HEALD 72A Internal Grinder.
WOTAN Internal Grinder.
PRECIMAX 10in. x 48in. Plain Grinder.
CHURCHILL 6in. x 18in. Semi-Universal
Grinder.
MAXNOVA Profilomatic Type "V" Copy-
ing Lathe.
HOLBROOK Model "C" No. 10 S.S. &
S.C. Lathe.
HOLBROOK 8in. x 36in. S.S. & S.C. Lathe.

CHURCHILL-REDMAN 8in. x 30in.
A.G.H. Gap Bed Lathe.
KARGER No. 24in. S.S. & S.C. Lathe.
HOGARTH 7in. x 40in. A.G.H. S.S. & S.C.
Lathe.
VOLMAN 7in. x 60in. A.G.H. Gap Bed
S.S. & S.C. Lathe.
KELLER Die-Sinking Machine, Mod. GG1210.
Ser. No. 7578.
CINCINNATI 3/36 Hydromatic Duplex
Mill.
ARCHDALE 30in. Vertical Mill.
WADKIN Vertical Mill, 2,100-3,100 r.p.m.
CINCINNATI No. 3 and No. 4 Vertical
Mills.
ADCOCK & SHIPLEY No. 3 Hor. Mill.
CINCINNATI No. 4 Hor. Mill.
CINCINNATI Hydrotel Mod. EM. 28in.
Vertical Mill.
EDGWICK No. 1 Speedmill.
WERNER Type 2201 Plain Mills.
VULCAN Mark I Routing Machine.
Variable Speed "H" Gear Drives. 3 h.p.
All machines motorised 400/3/50 unless other-
wise stated.

Phone:

EDGWARE
- 4488/9 -

E.H. JONES
(MACHINE TOOLS) LTD

Phone:

B'ham. Midland
5593

48, HIGH STREET, EDGWARE, MIDDX

When answering advertisements kindly mention MACHINERY.

RING BELLS for machine tools

LEEDS 63-7398

HENDEY 7in. S.S. & S.C. Lathe. A.G.H. Admits 30in. between centres. 12 speeds 19 to 598 r.p.m. M.D. 400/3/50.

KEARNS Model OA Horizontal Borer with facing head. Over size table. Wartime machine.

HERBERT Junior Chucking Auto with air chuck, knee tools, etc. 6in. swing. Reconditioned. M.D. 400/3/50.

POLLARD 28AE Vertical Drill. Spindle to column 14in. No. 5 M.T. T-slotted table and base. Speeds 37 to 508 r.p.m. M.D. 380/3/50.

New **KERRY** 125 A.G. 1 1/2in. Pillar Drill. Spindle No. 3 M.T. Nine speeds 70 to 1,000 r.p.m. Three rates of power feed. T-slotted table and base. M.D. 400/3/50.

CHURCHILL No. 1 Planetary Type Internal Grinder. Cap with largest internal spindle 10in. dia. by 18in. length. Hydraulic operation with four internal grinding spindles, dust extraction unit, etc. Reconditioned.

MINIMUS Gear Hobber. Will take blanks up to 2 1/2in. dia. by 2 1/2in. length. Design similar to Mikron 79. M.D. 400/3/50.

ASQUITH 28in. Heavy Duty Vertical Miller. Table 48in. by 14in. Speeds 33 to 500 r.p.m. Power all ways. M.D. 440/3/50.

WARD 3A Capstan. Speeds 59 to 1,155 r.p.m. A.G.H. Collet cap. 1 1/2in. Reconditioned. M.D. 400/3/50.

WARD 2A Capstan. Six speeds to 1,531 r.p.m. Collet cap. 1 1/2in. Reconditioned. M.D. 400/3/50.

BARDONS & OLIVER No. 3 Capstan. A.G.H. 12 speeds 38 to 1,271 r.p.m. M.D. 400/3/50.

JONES & SHIPMAN Fig. 137 Universal Precision Grinder. Centre height 5in. Admits 24in. between workhead and tail stock. Elevating and swivelling wheel head, steadies, diamond dresser, internal spindle, etc. M.D. 400/3/50.

OLDFIELD & SCHOFIELD No. 0 Straightening Press. Cap 19 tons. Max. stroke 5 1/2in. M.D. 400/3/50.

CLIFTON & BAIRD 24in. Automatic Cold Saw. Admits 24in. blades to cut 8in. rounds. Hydraulic clamping. Automatic hydraulic infeed for continuous cutting. M.D. 400/3/50.

New **MANCHESTER** Rapidor Medium and Light Duty Hacksaws. Cap 6in. by 6in. M.D. 400/3/50.

OHIO 32in. Heavy Duty Dreadnought Crank Shaper. V-belt drive from 10 h.p. motor 440/3/50.

B.S.A. 4in. Single Spindle Bar Auto. Long stroke 2in. 3rd slide, bar feed and other equipment. M.D. 400/3/50.

New **D.S.T.** Viceroy Double-ended Grinders. Size wheels 12in. by 1 1/2in. by 4in. and 10in. by 1in. by 4in. M.D. 400/3/50.

JONES & SHIPMAN Fig. 310 Tool and Cutter Grinder. Cap 8in. by 16in., with elevating and swivelling wheelhead, internal spindle, universal cutter head, chuck, etc. M.D. 400/3/50.

SWIFT 12 1/2in. S.S. & S.C. Gap Bed Lathe. A.G.H. Admits 7ft. between centres and 45in. in gap. Spindle bore 3 1/2in. M.D. 400/3/50.

MILWAUKEE 2H Vertical Miller. Table 50in. by 10in. Long traverse 28in. Rapid power three ways. 16 speeds 35 to 1,400 r.p.m. M.D. 400/3/50.

ARCHDALE 18in. High Speed Vertical Miller. Table 40in. by 10in. Speeds 79 to 2,000 r.p.m. M.D. 400/3/50.

LENNOX Throatless Rotary Shear. Driven by 1-h.p. motor 440/3/50.

CHURCHILL H.B.A. Internal Grinder. Max. stroke inside water guard 12in. dia. Hydraulic. Fully automatic. Reconditioned. M.D. 400/3/50.

H. BELL (Machine Tools) LTD., Walter Street, LEEDS 4.

Woodhouse & Mitchell (New)

Turret Milling Machine, table 36in. by 9in., power feed table, slotting head, coolant pump and lighting. Motorised 400/3/50.—**SOUTHERN ENGINEERING & MACHINE** CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

LATHES.

LANG 7in. CENTRE LATHE.

All geared headstock. Spindle speeds 12-57 to 908 r.p.m. Screwcutting, surfacing and sliding 4-way tool post. 9in. 3-lav chuck. Swing 14in. Admits between centres 30in. Motorised 400-440/3/50. Excellent condition.

BOX Z615, MACHINERY,
Clifton House, Euston Road, N.W.1.

G. M. BUCKINGHAM LTD.

MACHINE TOOLS GIVEN AWAY

All customers purchasing new or used machines from us during the next few weeks may select, absolutely free of charge from our extensive range, any additional machine or equipment, up to the value of one-tenth of the amount spent, or receive equal credit against further purchases.

For example, should you buy a new Lathe at £350, a new Bench Drill value £35 could be yours for nothing. Similarly, a plant order total value £5,500 to £6,000, would entitle you to a new 7 1/2in. Lathe, value £550-£600 at no cost whatever.

Most popular makes are offered under this scheme.

Favourable H.P. terms are, of course, available as usual.

Take advantage of this offer now—it obviously cannot be extended indefinitely.

8, Clarendon Ave., Leamington Spa.

Telephone 1215.

HARRY KIRK

can recommend the following modern quality machines from STOCK:

SCRIVENER No. 2 Centreless Grinding

Machine with control cycle.

SAFAG No. 118 Type 3 Motorised Pinion Cutter.

CHURCHILL Model RBY 24in. Rotary Surface Grinding Machine.

KEARNS No. 2 HORIZONTAL BORING, MILLING, DRILLING AND FACING

MACHINE, 3in. sliding spindle, 30in. dia. facing cap. Size of top table 48in. by 48in.

SWIFT 4ft. RADIAL DRILLING

MACHINE. Elevating arm, box table.

HERBERT No. 4 Automatic Chucking

Lathe.

PARKINSON No. 3J UNIVERSAL MILLING MACHINE.

PRATT & WHITNEY 12in. STROKE

SLOTING MACHINE. Tilting ram.

MODERN OPTICAL PROFILE GRINDING MACHINE.

LANG JUNIOR CENTRE LATHE. Capacity 6 1/2in. centre height by 30in. between centres.

CHURCHILL-REDMAN HEAVY DUTY

SHAPING MACHINE. 24in. stroke, swivelling vice, 10 h.p. motor.

BUTLER 8in. STROKE SLOTING

MACHINE, with tilting table.

B.S.A. 9in. SINGLE SPINDLE CHUCKING

ACTOMATIC. Complete with air-operated chuck.

KITCHEN & WADE VERTICAL FINE

BORING MACHINE. 14in. stroke. Compound table.

KITCHEN & WADE HEAVY DUTY

PILLAR DRILL. No. 5 Morse. Speeds 22-1,000 r.p.m.

CHURCHILL 12in. by 36in. UNIVERSAL

HYDRAULIC GRINDING MACHINE.

Further details from

HARRY KIRK

ENGINEERING LTD.

BRANDON ROAD WORKS, BRANDON

ROAD, COVENTRY.

'Phone: WALSGRAVE-ON-SOWE 2213/4'

Drills. Denbigh 1 1/2in. Pillar

Drill (nearly new). Kitchen & Wade E26 4ft. Radial (new).—TATE MACHINE TOOL CO., 6, North End Parade (opp. Olympia), London, W.14. Telephone: Fulham 6563 (3 lines).

C.E.M

PROGRESS 4E Pillar Drill. New.

PACERA MF6 Pillar Drill, 1 1/2in. cap.

LITTLEJOHN 5in. Precision Lathe. New.

SEDGWICK 10ft. x 1/2in. Univ. Bending and Folding M/c. New.

SEDGWICK 6ft. x 1/2in. Univ. Bending and Folding M/c.

CINCINNATI No. 2 Dial Type Horiz. Mill.

ACME-GRIDLEY 4-spindle Automatic, 3 1/2in. bar M/c.

Fully detailed stock lists available.

CHARLES E. MATTHEWS (MACHINE TOOLS) LTD.

34, Gladstone Road,

Croydon, Surrey.

Tel.: THOrnton Heath 1783.

Heald 81 Gagematic Internal

Grinder in excellent condition. Will accept reasonable offer.—BOX Z601, MACHINERY, Clifton House, Euston Road, N.W.1.

Norton Foot Presses For Sale.

Good used machines on stands. Type FPL. Stroke 2in. centre to back 3 1/2in., tee slotted bed 10in. by 6 1/2in., hole in bed 8in. diameter, weight 2 1/2 cwt.—Photo, etc., from P. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1. Euston 4681; or 41, Water Street, Birmingham, 3. Central 7606.

TWO B.S.A. 9in. Chucking Automatics.

Each with front and rear toolposts, 9in. Coventry air chuck, combination toolholders, pick-off gears, etc. Spindle speeds 23 to 845 r.p.m. Motor drive 415/3/50.

ROTH

4/6, Minerva Road, Park Royal,

LONDON, N.W.10.

Telephone: ELGar 4841-4842.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

Wickman 5-spindle Auto. 11in.
capacity, 1947 machine. Any inspection
welcomed.—Phone Byfleet 3252.

Dean, Smith & Grace 7in.
height x 4ft. 6in. between centres S.S. &
S.C. Gap Bed Lathe, motorised 400/3/50.—
**SOUTHERY ENGINEERING & MACHIN-
ERY CO.** Connaught Buildings, Tanners
Brook, Millbrook, Southampton. Tel.: South-
ampton 75101.

Archdale 28in. Horizontal Miller
with vertical milling attachment, 400/3/50.—
HICKS MACHINERY LTD. 26, Addison
Place, London, W.11. Tel.: PARK 2335.



HIGH CLASS VERTICAL BORERS IN STOCK

SINGLE COLUMN TYPES

WEBSTER & BENNETT 48in. Maxpower
type, max. swing 52in., h.p. main motor
30 h.p., rapid traverse motor 3 h.p.
HARTMANN 43in. hexagon turret head on
cross rail, side head with sq. T.H., max.
swing 43in., h.p. motor 15.
MILES 40in. (as above), max. swing 40in.
h.p. motor 25.
WEBSTER & BENNETT 36in. Rapid Production
Type, max. swing 38in., h.p. motor 15.
BULLARD 36in. Spiral Drive (1943), max.
swing 38in., h.p. motor 30.

DOUBLE COLUMN TYPES

RICHARDS 36in., 2 T.H., screwcutting, 2.5-60
r.p.m. table speeds.
A.W. CRAVEN 48in., 2 T.H. on cross rail,
2-45 r.p.m. table speeds.
SONDERMAN & STIER 72in. type KD20,
2 T.H. on cross rail, max. swing 81in.,
0.8-32 r.p.m. table speeds.
RICHARDS 72in., 2 T.H. on cross rail, max.
swing 74in., 1.9-25 r.p.m. table speeds.
RICHARDS 9ft., two tool heads on cross rail,
max. swing 10ft., h.p. motor 25.

INSPECTION INVITED

It's Cheaper to Buy Now

Full details from:

SOAG MACHINE TOOLS LTD.,
JUXON STREET, LAMBETH, LONDON, S.E.1
Phone: REliance 7201
Grams: "Sotocolmaz," London, S.E.11.

- 2—HERBERT 3A Chucking Autos.
- 2—HERBERT JUNIOR Chucking Autos.
- 2—WARD 3A Capstan Lathes.
- 2—WARD 2A Capstan Lathes.
- 1—DISKUS Surface Grinder.

All machines fully equipped, motorised
400-440/3/50.

**TRIPLEX ENGINEERING CO.
(GLOUCESTER) LTD.,**
EASTERN AVENUE, GLOUCESTER.
Gloucester 26211.

WIDDOWSON

NEW BROADBENT 5ft. Vertical Boring and
Turning Mill, swing 70in. diameter. Ex-stock.

JUNGENTHAL KEI200 4ft. Swing Single
Column Turret Type Vertical Boring and
Turning Mill, with side head, 20 h.p. motor,
speeds 5-6 to 180 r.p.m.

SWIFT 4ft. Radial Drilling Machine, No. 4
Morse Taper Spindle, speeds 42 to 1,500 r.p.m.
JONES & SHIPMAN 20in. High Speed
Pillar Drilling Machine, No. 3 Morse Taper
Spindle.

FELLOWS No. 61 Spur Gear Shaping Machine,
capacity 35in. dia. external, 24in. dia. internal.

ADAMS U.S.A. No. 5 Horizontal Gear Hobbing
and Thread Milling capacity, 10in. dia., 49in.
long.

JONES & SHIPMAN 138. 10in. x 27in.
Universal Grinding Machine, good equipment.

CHURCHILL OSB 60in. x 8in. Hydraulic
Horizontal Spindle Surface Grinding Machine,
magnetic chuck.

CHURCHILL OSB 40in. x 8in. Hydraulic
Horizontal Spindle Surface Grinding Machine.

CHURCHILL NB 18in. x 6in. Hydraulic
Horizontal Spindle Surface Grinding Machine.

SWIFT 15in. Centres Heavy Duty All Geared
Gap Bed S.S. & S.C. Lathe, admit 10ft.
bet. -en centres.

SWIFT 13in. Centres High Speed All Geared
Gap Bed S.S. & S.C. Lathe, admit 6ft. between
centres, speeds 8-900 r.p.m.

HOLBROOK Model "C" 16 in. Centres
High Speed Tool Room Lathes, admit 36in.
between centres, speeds 26 to 1,200 r.p.m.

WARD No. 7 Combination Turret Lathe,
swing 16in. dia. over bed covers, excellent
equipment including bar feed gear.

MINGANTI Type 20-40P Hydraulic
Pre-Selector Bar Feed and Chucking Capstan
Lathe, fully equipped.

WARD, HAGGAS & SMITH 36in. Swing
Heavy Duty Boring and Surfacing Lathe.
Modern Machine.

CINCINNATI No. 3 OH Dial Type Horizontal
Milling Machine, table 62in. x 15in.,
backlash eliminator. As New.

ARCHDALE 28in. Plain Manufacturing Milling
Machine, table 49in. x 13in.

MILWAUKEE 4K Heavy Duty Vertical
Milling Machine, table 82in. x 18in., speeds
13-1,300 r.p.m.

MILWAUKEE 4H Heavy Duty Vertical Milling
Machine, table 74in. x 15in.

CINCINNATI No. 2 Dial Type High Speed
Vertical Milling Machine, table 52in. x
12in., power down feed head, speeds 20 to
1,500 r.p.m.

OSTER Model 326 6in. capacity Six-chaser
Pipe Screwing and Cutting-off Machine.
Unused.

CLIFTON & BAIRD No. 2 Hydraulic Heavy
Duty Cold Circular Sawing Machine, capacity
8in.

HERBERT

WIDDOWSON

& SONS LTD.
CANAL STREET, NOTTINGHAM

'PHONE 42061.

When answering advertisements kindly mention MACHINERY.



REGENT Power Operated Open End Guillotine
Shearing Machine. Undercrank type. Arranged
motor drive for 400/3/50. Complete
with one spare pair of blades. Capacity
49in. x 16 s.w.g. Depth of gap 2in. Fitted
with automatic sheet hold-down and front,
back and side gauges.

RUSHWORTH Open Ended Power Guillotine
Undercrank type. Fitted with automatic
sheet hold-down and adjustable gauges.
Complete with one spare pair of blades.
Capacity 6ft. x 14 s.w.g. Length of blades
74in. Depth of gap 2in.

QUICKWORK No. 321. Motorised Rotary
Shearing Machine with circle cutting attach-
ment. Arranged motor drive for 400-440/3/50.
Capacity 14 s.w.g. mild steel. Cuts circles
from 6in. to 60in. diameter. Weight ap-
proximately 18 cwt.

BRADLEY & CRAVEN Power Geared Open
Ended Guillotine Shearing Machine. Under-
crank type. Capacity 84in. x 4in. Gap in
open ends 4in. Fitted with automatic sheet
hold-down and adjustable gauges.

BARHOPE Power Operated Double Geared
Open Ended Guillotine Shearing Machine.
Overcrank type. Arranged motor drive for
400/3/50. Capacity mild steel 4ft. x 4in.
Weight approximately 50 cwt.

BESCO High Duty Double Geared Guillotine
Shearing Machine. Overcrank type. Model
R. Capacity 120in. x 4in. mild steel.
Treadle operated clutch. Arranged motor
drive for 400-440/3/50. Depth of gap 6in.
Weight approximately 110 cwt.

Photographs of the above are available.

MACHINE TOOLS, NEW AND USED,
Of Every Description. Attractive Prices.

F. J. EDWARDS LTD.

359-361, EUSTON RD., LONDON, N.W.1

Telephone: EUSTON 4681-3771.

And at Lansdowne House, 41, Water St.
Birmingham, 3. Telephone: Central 7606-8

STEDALL SPOT Machine Tool

New Radial Drills.

RICHMOND S.R.2

36in. by 1 1/2 in. cap... £560

PACERA A8/A10.

24in. by 1 1/2 in. cap. Articulated £220

ARBOGA S12R

27 1/2 in. by 1 in. cap... £328

Immediate delivery.—Prices include

3-phase electrical equipment.

Stedall Machine Tool Co.

145-157 ST. JOHN ST. CLERKENWELL E.C.1

Phone: CLERKENWELL 1010

Sheet Metal. Brookes 8ft. by
4in. Bending and Folding Machine.
Beeco 4ft. x 16 s.w.g. Foot Guillotine. BESCO
Type F. Size No. 4 4ft. Slip Bending Rolls.—
TATE MACHINE TOOL CO., LTD., 6, North
End Parade (opp. Olympia), London, W.14.
Telephone: Fulham 6563 (3 lines).

Classified Advertisements (PLANT FOR SALE, contd.)



PIDGEN BROS. LIMITED

HELMET ROW, OLD STREET, LONDON, E.C.1.

Telephone: CLerkenwell 6841

ALL MACHINES MOTORISED FOR 3 PHASE SUPPLY UNLESS OTHERWISE STATED

AUTOMATICS**CONOMATIC** 4 Spindle.**CAPSTANS**

HERBERT No. 4. Bar feed.
WARD No. 8 Combination. Serial R.
WARD 2A and 3A. Serial M.
GISHOLT No. 4 Simplified. 2in. cap.
DRUMMOND Model K, 1 1/2in. Bar feed.
HILLE R.H. 15 1/2in. Bar feed.
ACCURATOOL 1/2in. Bar feed.
WARNER & SWASEY No. 2, 1in. Bar feed.
HERBERT No. 7 Combination Turret.
ACME SW Universal Turret, 2in. Bar feed.
LIBBY 4A, 2in. Bar feed.
MURAD 1/2in. Bar feed.
HAHN & KOLB RM25. 1in. bar. Unused.
SOUTHWARK No. 2. 1 1/2in. Bar feed.

DRILLS

HERBERT Type B. Bench.
CORONA 13CX 2 Spindle No. 2 M.T.
ARCHDALE 5ft. Radial, 3in. cap.
JONES & SHIPMAN 2-sp., 15in., No. 2 M.T.
GRIMSTON Electrica.
JONES & SHIPMAN 15in. Speed Drill-Max.
HERBERT Type H Junior Pillar.
CORONA 12AX, 1/2in. cap.
BOLEY Cluster Type.
15in. HERBERT Type C, No. 3 M.T.

ENGRAVERS

ALEXANDER No. 1, 3 Dim.
T.T. & H. Type C.
T.M.A. Type G.3 and G.2.
LIENHARDT Type 3R and 2.
T.T.H. Multi-etcher.

FLING AND SAWING MACHINES

WICKSTEED 6in. Hack saw.
EDGWICK Filer.
RAPIDOR No. 1 Hack saw.
WICKSTEED Cold Saw No. 1, 6in.

FOLDERS

BESCO 4ft. x 18 Gauge Cramp.
BESCO 3ft. x 18 in. No. 5 Angle Bender.
KEETONA 4ft. x 14 g. Cramp.

GEAR CUTTERS

SYKES HV14 Hobber.
MAXICUT 7in. x 2in. x 6 D.P.
RAPIDOR No. 1 1/2, 2 1/2in. dia. gears.
FELLOWS "Hourglass."

Snow P24 Hydraulic Surface

Grinding Machine, 24in. x 8in. capacity,
motorised 400/3/50.—SOUTHERN ENGI-
NEERING & MACHINERY CO., Connaught
Buildings, Tamers Brook, Millbrook, Southamp-
ton. Tel.: Southampton 73101.

Several Herbert 2S Capstans,

1 1/2in. capacity from £150 ex works.—BOX
2576, MACHINERY, Clifton House, Euston Road,
N.W.1.

30in. Archdale Vertical Column

Drilling Machine with quick-acting
compound table. Flange-mounted motor. 5 h.p.
400-440/3/50. Speeds 60-1,500 r.p.m. Spindle
bored No. 5 M.T. Post-war machine.—LEE &
HUNT, LTD., Crocus Street, Nottingham.
Tel.: 84246.

Precimax Hydraulic Plain Cylind-

dricial Grinder. Type M.P.L. 6/24. Plume
feed. Mot.—WILCOX & CO., Barr Street,
Birmingham 19. NORTHERN 1234/5.

Spot Welder. General Purpose

and production. 15 kVA ratings. Foot
operated. Perfect condition. Offers.—AIR
EXCHANGERS, LTD., Princess Street,
Colchester, Essex.

Ward No. 2A Capstan Lathe,

motorised, with automatic ball chuck,
bar feed, perfect condition. £320.—BOX 2548,
MACHINERY, Clifton House, Euston Road,
N.W.1.

GRINDERS (Cylindrical)

TRUVOX 2 1/2 x 18.
FRANCIS 6 x 7.
PRECIMAX MPB 10 x 48.
MYFORD MG12. New.
PRECIMAX MPH Plain. 10 x 24.
PRECIMAX U.P.J.—Universal. 12 x 40.
NORTON 6 x 18 Hyd. Type C.
NORTON 10 x 36. Type C.

GRINDERS (Miscellaneous)

NEWALL No. 2, 3/4 Thread.
LE BLOND No. 2. T. & C.
JONES & SHIPMAN 310. T. & C.
J. & S. 12in. x 24in. 305 T. & C.
EXCEL T. & C.
JONES & SHIPMAN Carbide.
HERBERT HUNT No. 4 Drill.

GRINDERS (Surface)

JONES & SHIPMAN 540 18 x 6 cap.
SNOW Table, 20in.
CHURCHILL OSB, 40in. x 18in.
WRIGHT 8in. Table.
ROBOT 18 x 6.
SNOW P24, 24in. x 8in. Hyd.
ABWOOD 18 x 6 Vertical.
GRINDERS (Internal)
SMART & BROWN.
SAAKE Model V11, jig.

GUILLOTINE

KEETONA 4ft. x 14G. Power.

HONERS

KITCHEN & WADE Hydraulic.
SUNNEN Type LB.
BARNES No. 2 Horiz.

KEYSEATER

CARTER & WRIGHT No. 2, 24in. x 1 1/2in.

LATHES

COUTHURST Surfacing and Boring.
EDWARDS 12in. Spinning.
WILLSON 7 1/2in. x 3in. S.S. & S.C.
BRADFORD 8in. S.S. & S.C.
RYDERMATIC No. 12 Multi Tool.
CARDIFF 7in. x 60in.
DENHAM 5 1/2in. S.S. & S.C.
LEBLOND 1 1/2in. x 16in. Prod.
SOAG-OXFORD 6 1/2in. x 24in. S.S. & S.C.
SOUTHBEND 9in. (Workshop), 14in.
LEBLOND Regal 10in. swing.

MILLERS (Horizontal)

U.S. (Whitney Type) Production.
KEMPSMITH No. 1G and 2G.
BROWN & SHARPE No. 12 and 000 prod.
CINCINNATI 08 and 1-18 Prod.
BROWN & SHARPE No. 2 Univ. Light.
STRANDSTRAND No. 00 Rigidmill.
BURKE. Table 16 x 3 1/2.
ARCHDALE 28in. Mir. and G.P.
CINCINNATI 3-24 Hyd. and 2 M.H.
HERBERT 15. Table 18in. x 8 1/2in.

MILLERS (Vertical)

MILWAUKEE 4H. Table 74in. x 15 1/2in.
CLEVELAND No. 1. Table 22 x 8.
RICHMOND VHM. Table 26 x 8.
VICTORIA V2. Table 40 x 10.
ARCHDALE 30in. Table 48 x 12 1/2.
HERBERT 155. Table 50 x 10 1/2.

PRESSES (Power)

BLISS No. 8.
BESCO TWO Bench, 4 ton.
O. & S. 30 tons straightening.
BESCO EB4, 40 tons. New.
TAYLOR & CHALLENGE 82, 10 tons.
RHODES No. 19. 10 ton.
SCHULER VZZ, 15 tons d/s gripper feed.

RIVETERS

HIGHSPEED Hammer 4A, 1/2in.
ROTORVET No. 5 Hammer.
TURNER RM 14/12.
TURNER inc. RS2A Spinning.

SCREWING MACHINES

OSTER 1in.-6in. Pipes No. 326.
ATLAS No. 2. 3in.-6in. (Unused.)

SHAPERS

24in. ROCKFORD Hyd.

TAPPERS

HERBERT No. 2 Flash.
HULLER No. 2, 1/2in. Cap.
SUPERIOR 1/2in.
JONES No. 26. 2 B.A.-jin.
THIEL Nos. 3 and 4.
J. & S. Electrocap, 1/2in.

THREAD MILLERS

FACKS Plain, cap. 3in. x 1/2in.
REINECKER 8 x 72in.
LEES BRADNER Mod. 40. 6 1/2in. H.M.
HANSON WHITNEY, 8in. x 40in.

Betts Slotter; 12in. Stroke, 29 1/2in.

dia. table built on motor drive, little used.
—A. McNAMARA & CO. New Line, Bacup,
Lancs. Phone: Bacup 946.

Lumsden Model LE92 Vertical

Spindle Grinder, 48in. magnetic rotary
table, 50 h.p., 415/3/50 motor.—C. DUGARD,
LTD., Denmark Villas, Hove 32471.

Herbert 3A Chucking Auto.,

M/d 400/3/50.—ALBERT EDWARDS
(MACHINERY), LTD., 79/89, Pentonville Road,
London, N.1. Phone: Terminus 0167/8/9.

Welding. B.O.C. 36in. Oxygen

Cutting Machine.—TATE MACHINE
TOOL CO., LTD., 6, North End Parade (opp.
Olympia), London, W.14. Telephone: Fulham
6563 (3 lines).



4/6, Minerva Road, Park Royal,
LONDON, N.W.10.

Telephone: ELGar 4841-4842.

TAYLOR & CHALLENGE B.3 Inclinable

Power Press, 40 tons pressure, 2in. stroke,
with roll feed and tie rods.

TAYLOR & CHALLENGE No. 1220 In-

clinable Power Press, 20 tons pressure
3in. stroke. With automatic guards.

TAYLOR & CHALLENGE No. 1220 In-

clinable Power Press, 20 tons pressure,
blanking stroke 1/2in.

TAYLOR & CHALLENGE B.1 1/2 Non-

inclinable Power Press, 10 tons pressure,
blanking stroke 1/2in.

Taylor & Challen B.3 Geared

Press, 40 ton. 6in. stroke. Fitted dial
feed. Motorised.—WILCOX & CO., Barr
Street, Birmingham 19. NORTHERN 1234/5.

New Process No. 1 Welding

Machine, 16 kVA. Throat distance 15in.
Can be used for spot or projection welding.
£190.—BOX 2552, MACHINERY, Clifton House,
Euston Road, N.W.1.

GRINDERS.**BROWN & SHARPE No. 13 TOOL**

AND CUTTER GRINDER.

Admits 8in. dia. x 24in. between centres.
Swivelling live workhead 160 deg. rotation.
Micro adjustment to wheelhead slide. Fine
and coarse hand feeds to table. Indepen-
dent motorised coolant tank. Motorised
400-440/3/50. Push Button starters. Extra
equipment available. New condition
having been rebuilt.

BOX 2561, MACHINERY,
Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



NEW MACHINE TOOLS FROM STOCK

GRANOF OF HALIFAX 11in. Gap Bed Lathe, by 8ft. 0in. b.c. Hole in spindle 31in. dia. 400-440/3/50.

MITCHELL OF KEIGHLEY 8 1/2in. Gap Bed Lathe by 5ft. 3in. b.c. 400-440/3/50.

MITCHELL OF KEIGHLEY 10 1/2in. Gap Bed Lathe by 5ft. 6in. b.c. 400-440/3/50.

MITCHELL OF KEIGHLEY 12 1/2in. Gap Bed Lathe by 6ft. 0in. b.c. 400-440/3/50.

EXCEL No. 3/12 Hydraulic Horizontal Spindle Surface Grinding Machine. Capacity 24in. by 8in. Coolant equipment. Motorised 400-440/3/50.

VICTORIA V2 Vertical Milling Machine. Spindle speeds 32-1,050 r.p.m. Table 45in. by 11in. Table traverse 29 1/2in. 400-440/3/50.

VICTORIA U2 Universal Milling Machine. Spindle speeds 30-1,010 r.p.m. Table 45in. by 11in. Longitudinal traverse 30in. 400-440/3/50.

USED MACHINE TOOLS

WORTON Horizontal Spindle Hydraulic Surface Grinding Machine, with hydraulic cross feed head. Capacity 48in. by 10in. Complete with D.C. magnetic chuck and generator. Coolant pump and fittings. 400-440/3/50.

HERBERT No. 4 Capstan Lathe, with draw-back collet, and power feed to turret slide. 400-440/3/50.

NEWALL Hydraulic "XL" 6in. by 15in. Plain Grinding Machine. 400-440/3/50.

NEWALL Type L 10in. by 24in. Plain Grinding Machine. 400-440/3/50.

LE BLOND A.G.H. 8. & 8 Lathe, 15in. dia. swing. 400-440/3/50.

HULLER No. 5 Vertical Tapping Machine. 400-440/3/50.

POLLARD 21A Single Spindle Vertical Production Drilling Machine.

WICKSTEED Hydraulic 28in. Cold Sawing Machine. 400-440/3/50.

ARCHDALE 18in. High Speed Vertical Milling Machine. Table size 38in. by 10in. Spindle speeds 79-2,000 r.p.m. 400-440/3/50.

DEAN, SMITH & GRACE 12in. Gap Bed Lathe by 5ft. 6in. b.c. 400-440/3/50.

BROWN & SHARPE No. 2 Light Plain Milling Machine, with dividing head, and universal vertical head. 400-440/3/50.

ARCHDALE 20in. Horizontal Plain Milling Machine, longitudinal feed 20in. 400-440/3/50.

WE UNDERTAKE REBUILDING OF ALL TYPES OF MACHINE TOOLS.

CENTAUR TOOL WORKS,
EYRE STREET, SPRING HILL,
BIRMINGHAM, 18

Tel.: EDGbaston Grange:
1118 & 1119 Capetan, Birmingham

Lathes. New Colchester 6in.
Student Centre Lathe. Colchester 6in. Student (straight bed), nearly new, with equipment, collets, etc., £235. Lang 10in. x 3ft. 6in. S.S. & S.C. Centre Lathe, 10 h.p. motor. Harrison 7in. S.S. & S.C. Centre Lathe, £225. Mitchell 6 1/2in. S.S. & S.C. Centre Lathe (1962). Wilson 7 1/2in. Centre Lathe.—TATE MACHINE TOOL CO., LTD., 6, North End Parade (opp. Olympia), London, W.14. Telephone: Fulham 6563 (3 lines).

G. M. BUCKINGHAM LTD.

MACHINE TOOLS GIVEN AWAY

All customers purchasing new or used machines from us during the next few weeks may select, absolutely free of charge from our extensive range, any additional machine or equipment, up to the value of one-tenth of the amount spent, or receive equal credit against further purchases.

For example, should you buy a new Lathe at £350, a new Bench Drill value £35 could be yours for nothing. Similarly, a plant order total value £5,500 to £6,000, would entitle you to a new 7 1/2in. Lathe, value £550-600 at no cost whatever.

Most popular makes are offered under this scheme.

Favourable H.P. terms are, of course, available as usual.

Take advantage of this offer now—it obviously cannot be extended indefinitely.

8, Clarendon Ave., Leamington Spa.

Telephone 1215.



HAVE CAPACITY AVAILABLE
FOR REBUILDING MACHINE
TOOLS UP TO A CAPACITY
OF 30 TONS.

INVITE ENQUIRIES FOR
THIS CLASS OF WORK
AT THE FOLLOWING
ADDRESS



**The Newall Used
Machine Division**

Oundle Road Works,
ORTON LONGUEVILLE,
PETERBOROUGH
Telephone 6116

GEAR HOBBERS.

**MIKROW 100 GEAR HOBBING
MACHINE.**

Rebuilt. Motorised 400/3/50.

BOX Z625, MACHINERY,
Clifton House, Euston Road, N.W.1.

25kW Induction Heater Unit by

Wild Barfield, in excellent order. Inspection invited South London area.—For further details write BOX Z609, MACHINERY, Clifton House, Euston Road, N.W.1.

Reed Prentice No. 5 Vertical

Miller, knee-less type; 72in. x 18in. table; 400/3/50; weight about 6 1/2 tons.—A. McNAMARA & CO., New Line, Bacup, Lancs. Phone: Bacup 946.

Edgwick 9in. All-g geared Multi-

tool lathe, overhauled, motorised, also Taylor taper turning lathe, mot. Cabinet type.—C. L. THOMAS, LTD., 15, Park Avenue, Solihull 1281.

Thiel Punch-Shaping Machine

for sale. In excellent condition.—ROLLS SWITCHES, LTD., Pyrford Road, West Byfleet. Tel.: Byfleet 3252.

Cincinnati 1/18 Production Miller

A.G.H. Table 41in. x 10in. Mot.—WILCOX & CO., Barr Street, Birmingham 19. Northern 1234/5.

Grinders: The Following Ma-

chines were purchased new in 1956 and are now available having only had approximately six months use. Scrivener No. 2G motorised centreless Grinder. Newall/Keighley 15in. motorised Internal Grinder and Newall/Keighley 8in. motorised Internal Grinder.—Apply Mr. D. WILSON, SOUTHERN INSTRUMENTS, LTD., Frimley Road, Camberley, Telephone 3401.

No. 3U "Adcock & Shipley"

motorised all-g geared Universal Milling Machine. Table 50in. by 12in., has long. travel of 30in. Spindle speeds 20-1,400 r.p.m. Auto feed 1in.-50in. per min. all movements. Rapid traverse by separate motor. Good equipment. Post war machine.—LEE & HUNT, LTD., Crocus Street, Nottingham. Tel.: 84246.

Cincinnati 2 M.H. Plain Hor.

Milling machine in excellent condition. Cheap to clear.—BOX Z591, MACHINERY, Clifton House, Euston Road, N.W.1.

Myford (New) MG:12 5in. x 12in.

Cylindrical Grinding Machine, with swivel workhead, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Index Model ON8 Single-spindle

high speed, Automatic Lathe, 400/3/50.—HICKS MACHINERY LTD., 26, Addison Place, London, W.11. Tel.: PARK 2333.

Samsonwerke Surface Grinder,

Table 24in. x 8in., mag. chuck 400/3/50.—C. DUGARD, LTD., Denmark Villas, Hove 3247 1.

Horizontal Boring. Dickinson

3in. Travelling Spindle Horizontal Borer No. 5 M.T., 45in. x 28in. main table, 10 h.p. motor for 400/3/50 cycles A.C. supply, £595.—TATE MACHINE TOOL CO., LTD., 6, North End Parade (opp. Olympia), London, W.14. Telephone: Fulham 6563 (3 lines).

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

Cashmores

**Selection of Machine Tools
from Stock or Early Delivery.**

DRILLING MACHINE

POLLARD Model 28AE Heavy Duty Drilling Machine, 2in. capacity, No. 5 M.T. spindle, compound table 24in./55 cycles, 9 spindle speeds 37/508 r.p.m., motorised 400/3/50 supply.

LATHES

FAIRBAIN 17in. Centre Heavy Duty Lathe, 18ft. 0in. between centres, spindle speeds 1/152 r.p.m., motorised 400/3/50 cycles.
New MITCHELL 12in. Centre Gap Bed Lathe, admit 8ft. 9in. between centres, motorised 400/3/50 cycles.
HOLBROOK Model B Type No. 17 S.S. & S.O. Lathe, swing over bed 14in. dia., admit 42in. between centres, range of spindle speeds 10-525 r.p.m., motorised 400/3/50 cycles.
New MITCHELL 10in. Lathe, 7ft. 5in. between centres, motorised 400/3/50 cycles.
SMALLPIECE No. 0WSL Multi-cut Production Lathe, motorised 400/3/50 cycles.
WARD No. 2A Capstan Lathe, power feed to saddle and turret, ball chuck and bar feed, motorised 400/3/50 cycles.
WARD No. 3A Capstan Lathe, arranged for chuck work, six spindle speeds 54-1,050 r.p.m., motorised 400/3/50 cycles supply.

VERTICAL BORING MACHINE

WALDRICH Single Column Type Vertical Turret Lathe, fitted pentagon turret on cross rail, side head, maximum swing 70in. dia., motorised 400/3/50 cycles.

GRINDING MACHINES

CHURCHILL Model VKA Vertical Spindle Surface Grinding Machine, working surface of table 72in. by 16in., 18in. dia. segmental grinding wheel, magnetic chuck, hydraulic feed to table, motorised 400/3/50 cycles supply.
SNOW Model P24 Horizontal Spindle Hydraulic Surface Grinder, table 24in. by 8in., motorised 400/3/50 cycles.
NEWALL 6in. by 18in. Hydraulic Plain Cylindrical Grinding Machine, D.C. variable speed workhead, speeds 365-3,000 r.p.m., built-in A.C./D.C. rectifier for supplying current to workhead, hydraulic feed to table, motorised 400/3/50 cycles.
NEWALL 10in. by 48in. Hydraulic Plain Grinder, Model L, motorised 400/3/50 cycles.
REINICKER 22in. by 66in. Hydraulic Plain Grinder, motorised 400/3/50 cycles.
OROUTT 20in. Hydraulic Spline Shaft Grinder, motorised 400/3/50 cycles.

MILLING MACHINES

New VICTORIA Model U2 Universal Miller, table 45in. by 11in., motorised 400/3/50 cycles.
New VICTORIA Model V2 Vertical Miller, table 45in. by 11in., motorised 400/3/50 cycles.
BOLEY Heavy Duty Universal Miller, table 55in. by 14in., motorised 400/3/50 cycles.

PLANING MACHINE

LOUDON 10ft. by 4ft. by 4ft. All Electric Spiral Drive Planing Machine, three toolboxes, Ward Leonard drive.

SLOTTING MACHINE

MUIR 30in. Stroke Slotting Machine, 50in. by 50in. table, motorised 400/3/50 cycles.

MISCELLANEOUS

PLATT No. 2 Size Five Throw Forging and Swaging Machine, capacity 4in. dia. steel tubes, the third and fifth blocks are fitted with self-contained power-driven wedge elevating motion, motorised 400/3/50 supply.
HUBBELL 24in. Hydraulic Cold Metal Sawing Machine, cut up to 8in. rounds, motorised 400/3/50 cycles.
MASSEY 2 cwt. and 1 cwt. Slide Type Pneumatic Power Hammers, motorised 400/3/50 cycles.
CLYDE 5 Ton Three Motor Overhead Travelling Crane, span 34ft., floor controlled, totally enclosed gearing, motorised 400/3/50 cycles supply.

JOHN CASHMORE LTD.
GREAT BRIDGE, STAFFS. Tel.: Tipton 2181/7
(Also at NEWPORT, MON.)

MILLING MACHINES.

CINCINNATI No. 3 VERTICAL MILLER DIAL TYPE.

High speed series. 21-spindle speeds 18-1,300 r.p.m. 16 feeds 1in. to 20in. per min. Speeds and feeds indexed automatically through hydraulic system, with dual control. Table 62in. x 15in. Working surface 54in. x 10in. Quick rise and fall cross and longitudinal traverse. Built-in coolant system. Motorised 400-440/3/50. Push button starter.

CINCINNATI 1-18 PRODUCTION MILLING MACHINE.

Automatic hydraulic 2-way cycle. Working surface 10in. x 35in. 8 spindle speeds 75 to 500 r.p.m. 16 feeds 1in. to 40in. per min. Quick traverse 300ft. per min. Fully motorised 400-440/3/50. Push button starters.

WANDERER UNIVERSAL MILL.

Quick traverse all ways. Dial type change 9 spindle speeds 96-1,500 r.p.m. 12 feeds 1in. to 15in. per min. Table 31in. x 9in. Dividing head etc. Coolant pump. Fully motorised 400-440/3/50. Power traversing: longitudinal 24in., cross 8in.

VAN NORMAN No. 6 RAM TYPE MILLING MACHINE.

9 spindle speeds 80-1,450 r.p.m. Table 30in. x 6in. Vert. head 90 deg. adjustment and rotates through 360 deg. Motorised 400-440/3/50. Push button starters. Equipment: Dividing head, etc. IDEAL FOR PROTOTYPE OR MOULD MAKING.

THE ABOVE MACHINES HAVE BEEN
REBUILT TO CLOSE LIMITS.

BOX Z635, MACHINERY,
Clifton House, Euston Road, N.W.1.

Denbigh C4 Horizontal Semi-

Universal Milling Machine, table 46in. by 10in. Motorised 400/3/50. Two machines available, one with Richmond High Speed Milling Head.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Jones & Shipman 3-spindle

Drilling Machine. Spindles No. 3 M.T. Flange mounted motors, 400/3/50 2 off.—ALBERT EDWARDS (MACHINERY) LTD. 79/80, Pentonville Road, London, N.1. Phone: Terminus 0167/8/9.


Saws. 6in. by 6in. Power Hack-

saw (new), £55. Grob Bandsaw with Brazing, £85.—TATE MACHINE TOOL CO. LTD., 6, North End Parade (opp. Olympia), London, W.14. Telephone: Fulham 5563 (3 lines).

Herbert No. 9S Combination

Turret Lathe, well equipped, 400/3/50. £300.—A. McNAMARA & CO., New Line, Bacup, Lancs. Phone: Bacup 946.

Herbert Hor. Broach. 56in. stroke 10 h.p., 400/3/50 Motor.—C. DUGARD, LTD., Denmark Villas, Hove 32471



USED LATE TYPE MACHINES

LATHES

LANG, Late Type 8in. centre by 54in., in gap, 25in. Norton Feed Box, Camlock Nose, heavy duty, motorised.
SELECTA A.G.H. 6in. centre by 42in., gap 25in., Norton feed box, motorised.
WILSON 7in. by 40in., gap bed, motorised.
BERRY A.G.H. 6in. centre by 32in., in gap 36in., motorised.
MITCHELL 7in. by 42in. by 25in., gap, A.G.H., motorised.
CHURCHILL CUB Lathe, 6in. by 24in., A.G.H., mot. 415/3/50.

CAPSTANS AND AUTOS

HERBERT 2D, bar feed, dead length chuck, motorised.
WICKMAN Auto., cap. 10mm., motorised.
WARD 2A, A.G.H., bar feed, motorised.
WARD No. 7 A.G.H. Bar feed, ball chuck, etc., motorised.

WARD 1A Capstans, 1in. collet cap. H.S. range up to 4,130 r.p.m. Ball chuck, bar feed, mot. coolant pump, 400-440/3/50 A.C.
HERBERT 15 Capstans, 1in. collet cap. Draw-in collet and bar feed, 16 speeds 18/4,020 r.p.m. Hand feed turret and cross slide. Mot. coolant pump, 415/3/50.
HERBERT No. 0 Capstans, 1in. cap. Dead length air chucks, 12 speeds 92/6,000 r.p.m. mot. coolant pump, 415/3/50.
BOLEY & LEINEN Precision Capstan, Model S.R.26. Collet cap. 1in., mot. 415/3/50.

MILLING MACHINES

WADKIN High-speed Vert. Mill, table 12in. by 36in., mot. 415/3/50.
LEITHARD Engraver, ratio 0-0 to 20-1, mot. ARCHDALE 23in., table 49in. by 13in., mot. in base.
ARCHDALE 20in. Horizontal, Table 40in. by 10in. Dial type speed change 30 to 615 r.p.m. Dial feed. Mot. 415/3/50.
ARCHDALE 18in. High-speed Vertical W330, Table 34in. by 10in., 6 speeds 500/2,000 r.p.m. Mot. 415/3/50.

GRINDING MACHINES

CHURCHILL No. 2 Centreless, New unused. Bargain price.
ABRAVIE Surface, No. 3, motorised, 24in. by 8in.
CHURCHILL Hyd. Vert. Surface (plough), cap. 18in. by 36in., segmental wheel 18in. dia. Humphrey mag. chuck, 12in. by 36in. Mot. 415/3/50.
LANDIE Hydraulic Cylindrical Grinder, 12in. by 42in., mot., reconditioned.
NEWALL Hydraulic Cylindrical Grinder, 12in. by 24in., mot.
E.S. Internal Grinder, 4in. to 14in. dia., int. cap. Power feed to table, auto. sizing feeds, mot. 415/3/50. Late type machine, ex. con.
OLIVETTI Automatic Hydraulic Cylindrical Grinder, Type R4/1200, 14in. swing by 38in. between centres. Plunge cut. Mot. 415/3/50.

SHAPING MACHINES

ALBA 24in., motorised.
BERRY 14in. Shaper, gearbox drive, mot.
PRATT & WHITNEY Slotter, 6in. stroke, tilting ram.

PRESSES AND SHEET METAL, ETC.

RHODES Stagger Press, 25 ton, throat 24in.
OLIVER Quick Work Shear, cap. 1in., throat 30in.
RHODES Fluidised Hydraulic Guillotine, 6ft. by 14ft. Gauge, Micro stops.
THERMIG Muffle Furnace, 15in. by 24in. by 12in., has heated pyrometer 1,000 deg. C. T. & C. B14 and B2, motorised.
RHODES 40 ton inc., motorised.
BLISS No. 5, late type, motorised. £100.

DRILLING MACHINES

ASQUITH Radial OD1, 4ft. 6in., motorised.
ASQUITH Radial LDE 3ft. 6in., motorised.
PROGRESS Pillar 4E, motorised.

WILLIAM URQUHART

Head Office—
1023, Garratt Lane, London, S.W.17
Showrooms—
Ace Works, Plough Lane, Tooting, S.W.17
Phone: WIMbledon 6341

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

MIDLAND

HERBERT No. 0 Capstan Lathe. Bar feed.

ACME GRIDLEY 1in. cap. Six spindle Bar Auto. Bar feed, collets, tooling and live spindle.

WARD 3A and 7 Capstans. Bar feeds.

HERBERT Junior Chucking Auto. Very well equipped.

WARD E.O. Capstan Lathe. Bar feed.

FISCHER K.D.M. 11/70 Copying Lathe. Automatic.

CHURCHILL REDMAN 24in. swing Surfacing and Boring Lathe.

DALE 10in. x 6ft. S.S. & S.C. Lathe. Well equipped.

BROWN & SHARPE No. 2 Universal Grinder. 14in. swing x 30in. b.c. Well equipped. Double Ended Centring Machine.

MILWAUKEE 2 C.E. Horizontal Miller. Vertical and slotting heads. Speeds to 2,000 r.p.m. As new. 1954.

HOLBROOK 9in. x 3ft. 6in. Tool-room Lathe. Taper turning and relieving attachment.

BIERNATZKI Heavy Duty Horizontal Miller. Speeds 29 to 1,500 r.p.m. Quick power all ways. New condition. 1952.

THIEL 12in. Metal Bandsaw.

HERBERT No. 21 Combination Turret Lathe. 34in. swing. 7in. hollow spindle. Screwcutting and taper-turning.

4ft. 6in. x 4in. swing Beam Hand Folder.

COLCHESTER Mascot 8in. x 4ft. 6in. b.c. S.S. & S.C. Gap Bed Lathe. Speeds 25 to 410 r.p.m. Well equipped.

ASQUITH 4ft. 6in. L.D.R. Radial Drill.

G.S.P. 5ft. Radial Drill.

ARCHDALE 5ft. Radial Drill.

KOLB 4ft. Radial Drill.

PROGRES 24in. x 9ft. b.c. Gap Bed S.S. & S.C. Lathe.

TAYLOR & CHALLEN B.3 40-ton Open Fronted Power Press.

ORMEROD 22in. Heavy Duty Shaper.

Motor driven compressors 150 lbs. and 200 lbs.

THE MIDLAND MACHINE TOOL CO

BRADLEY, BILSTON, STAFFS. Bilston 42471/7

Brown & Sharpe No. 5 Plain Cylindrical Grinder, 18in. b.c., 415/3/50.—**C. DUGARD, LTD.**, Denmark Villas, Hove 32471.

1,000 ton
HYDRAULIC DRAWING PRESS
Blankholder 80in. x 60in.
Self-contained Oil Hydraulic
Pump Unit.

Many other Hydraulic
Presses, Single & Double
Action Of All Types.

REED BROTHERS
(ENGINEERING) LIMITED
REPLANT WORKS,

Woolwich Industrial Estate.

London S.E.18

Telephone: Woolwich 7611/6

Nassovia Model V.11 3-Dimensional Hydraulic Diesinker. Cap. 27 1/2 in. x 19 1/2 in. With 24in. Rotary Table. Nearly new machine available for quick sale at low price.—**BOX 2521, MACHINERY, Clifton House, Euston Road, N.W.1.**

VICTORIA U2 Universal Milling Machine. 415/3/50. Table W.S. 40in. x 10in. 16 spindle speeds 25-900 r.p.m. With dividing heads, swivel vice, pump, etc.

CINCINNATI 1/18 Horizontal Production Milling Machine. Table W.S. 35in. x 10in. Spindle speeds 50-1,500 r.p.m. Automatic table cycle in either direction. Motor drive 415/3/50.

VAN NORMAN Plain Horizontal Milling Machine. 415/3/50. Table W.S. 64in. x 14in. 18 spindle speeds 25-1,250 r.p.m.

R. O. H. M.

4/6, Minerva Road, Park Royal,
LONDON, N.W.18.

Telephone: ELGar 4841-4842.

Kerry 125 (New) Pillar Drilling
Machine, 1 1/2 in. capacity, power feed, Motorised 400/3/50.—**SOUTHERN ENGINEERING & MACHINERY CO.**, Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Denham 7in. A.G.H. Centre
Lathe, 36in. R.C. Gap bed. M/d 400/3/50.—**ALBERT EDWARDS (MACHINERY), LTD.**, 79/89, Pentonville Road, London, N.1. Phone: Terminus 0167/8/9.

Lathes, Ward, Haggas & Smith
60in. Surfacing, and Boring Lathe (Good condition).—**TATE MACHINE TOOL CO., LTD.**, 6, North End Parade (opp. Olympia), London, W.14. Telephone: Fulham 6563 (3 lines).



ADCOCK & SHIPLEY No. 3 Horiz. Milling M/c. Table 48in. x 13in. Power feeds all ways. Var. dial speed change, 20-1,400 r.p.m. Price £375.

CINCINNATI 1/12 Automatic Milling M/c. Ex. Cond. £250.

VICTORIA M2 Horiz. Milling M/c. Power feeds all ways. Table 40in. x 12in. Price £275.

CINCINNATI No. 4 Horiz. Milling M/c. Power feeds all ways. Table 68in. x 16in. Price £150.

BROWN & SHARPE No. 13 Univ. Tool and Cutter Grinder. Reconditioned throughout. £225.

BRYANT No. 16 Hyd. Internal Grinder. Complete with full equip. Ex. Cond. Price £425.

NORTON 6in. x 18in. Hyd. Plain Cyl. Grinder. £150.

WARD 3A O-size spindle, 1957 M/c. Full equip.

1954 **WARD** 2C Capstan, full equip.

THE CAUSEWAY, EGHAM, SURREY.

Tel. Egham 3155/6.

Berry Thread Milling Machine, 6in. centre, admits B/C 1 1/2 in. 6in., hollow spindle 2 1/2 in., 3 speeds 1-1 1/2 r.p.m., mot. 400/3/50, compensator for leadscrews longer than 1 1/2 in. £450.

Cincinnati 08 Automatic cycle horiz. production Milling Machine. Table 18in. by 6in., 10 speeds 75-1,100 r.p.m. Mot. 400/3/50. £300.—**BOX 2560, MACHINERY, Clifton House, Euston Road, N.W.1.**

Knight No. 20 Vertical Milling
and Semi-Jig Boring Machine, table 33 1/2 in. x 9 in., motorised 400/3/50.—**SOUTHERN ENGINEERING & MACHINERY CO.**, Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.


When answering advertisements kindly mention **MACHINERY**.

Classified Advertisements (PLANT FOR SALE, contd.)

RING BELLS for machine tools

LEEDS 63-7398

Jones & Shipman 1051EF
precision universal production grinder, 10in. x 27in. B. centres complete with all equipment including clarifying unit, 1857 machine. As new. No reasonable offer refused.
—DORAN ENGINEERING CO., LTD., March End, Wednesfield, Staffs. Telephone: Wolverhampton 31050.



NEW MACHINES EX STOCK FOR IMMEDIATE DELIVERY

COLCHESTER Lathes, Mascot, 8in. by 60in. TRIUMPH 7 1/2in. by 45in.
STUDENT 6in. by 24in.
CHIPMASTER 5in. by 24in.
"ACE" Bench Lathe, 4 1/2in. centres by 23in., between, Norton feed box and on cabin. stand. 415/3/50.
ROBLING Lathe, Model 600/2, 5 1/2in. centres by 24in. between, 1,920 r.p.m. accuracy 0.0002in. 415/3/50 A.C.
PFEIFFER Precision Toolroom Lathe, Model P.12, 9in. centres by 44in. between, 1,000 r.p.m., Norton feed box, 187 threads Whitworth, metric and module, turning accuracy 0.002mm. 415/3/50 A.C.
TROGLIA Lathe, Model TPM20, 10 1/2in. centres by 76in. between 3 1/2in. in cap. 850 r.p.m., Norton feed box, 187 threads Whitworth, metric and module. 415/3/50 A.C.
GRANVILLE SENIOR 3 1/2in./4in. H.D. Bench Centre Lathe 21in. b.c. Motorised.
ASTRA 6in. Stroke Slotting Machine, 4 speeds to ram, compound table. Mot. 415/3/50.
SENIOR M.1 Horizontal Milling Machines. Table 25in. by 6 1/2in. W/S. long. power feed, spindle speeds 12, 50/1,650 r.p.m., coolant pump. Motorised 415/3/50.
P.T.V. Universal Mill, Model 51, Table 39 1/2in. by 8 1/2in., power feed, 60/1,200. Dividing heads, etc. 415/3/50.
P.T.V. Vertical Mill, Model IV, Table 39in. by 8 1/2in., power feed all directions, swivel head, rise and fall, speeds 60/1,400, dial change. 415/3/50.
ASTRA Vertical Mill, Table 23in. by 8in., hand feeds to table in all directions. No. 8 Morse spindle. Motorised 415/3/50.
FIVE STAR Tool and Cutter Grinder, capacity 5in. by 12 1/2in., with motorised workhead for external and internal grinding. 415/3/50.

PLEASE ADDRESS YOUR ENQUIRIES TO DEPARTMENT "P."

WILLIAM URQUHART
1023-1027 Garratt Lane, London, S.W.17
'Phone: WIMbleton 6341

HEALD No. 45 Single-end Borematic, Complete with 4-Head Style 14-16A heads, 1940.

CINCINNATI 5/60 Hydromatic 60in. Traverse to Table speeds 17 to 127. 15 h.p. 400/3/50, 1941.

KEARNS No. 2 Patent Horizontal Borer, 3in. spindle, 36in. facing speeds 3.1/246, screwcutting, 1942.

CHURCHILL Model OSV Vertical Spindle Surface Grinder, Capacity 40in. x 10in. Hydraulic, 1942.

BOX 2592, MACHINERY,
Clifton House, Euston Road, N.W.1.

Bench Type Spot Welder up to 5 kVA, with Thyatron Contactor and four-way heat control, £175. Suitable for fine wire assemblies, etc.—BOX 2592, MACHINERY, Clifton House, Euston Road, N.W.1.

Milling Machines. Milwaukee
No. 4K, Vertical Mill, High speed series, Table 80in. x 16in. Longitudinal stroke 42in. 27 spindle speeds 12 to 1,200 r.p.m. 27 feeds 1/4in. to 15in. per min. Quick traverse all directions. Dial type gear change. Power feeds to vert. head. Built-in coolant system. Fully motorised 15 h.p. 400-440/3/50. Push button starters. In new condition.—BOX 2594, MACHINERY, Clifton House, Euston Road, N.W.1.

Asquith U.G.D. Type Vertical
Drill, compound table, 400/3/50.—BOX 2598, MACHINERY, Clifton House, Euston Road, N.W.1.

Webster & Bennett Type 3DH
36in. Hydraulic Vertical Boring Mill, fully motorised; table speeds 9/200 r.p.m. built 1954.

Webster & Bennett type D—36in Vertical Boring Mill with Murray control, fully motorised table speeds 8.6/192 r.p.m.—built 1947. Kitchen & Wade type H5 Horizontal Drilling, Boring and Tapping machine, 2 1/2in. spindle, cap. 2 1/2in. drill with separate table, 5 ft. 6in. x 3ft. 6in., having remote control for rapid traverse, built 1953.

LOUIS DEMERY & SONS, LTD., 32, Hereford Street, Sheffield 1. 'Phone: 24936.

Victoria U2 Miller, Dividing
head, vertical and slotting atts. Rotary table, vice, etc., almost new condition.—C.J. THOMAS, LTD., 18, Park Avenue, Solihull 1281.

AUCTIONS

By Order of Messrs. URQUHART LINDSAY & ROBERTSON ORCHAR, LTD.

BLACKNESS WORKS
DUNDEE

HENRY BUTCHER & CO.

are instructed to offer for SALE BY AUCTION in LOTS at BLACKNESS WORKS, DUNDEE, on

TUESDAY, 11th NOVEMBER, 1958, AND DAY FOLLOWING at 11 a.m. EACH DAY, the

PLANT, MACHINERY, TOOLS & EQUIPMENT

including

S.S. & S.C., CAPSTAN and TURRET LATHES by D.S.M., Herbert, Mitchell, Holbrook, Southend, Ward, Pratt & Whitney CYLINDRICAL, SURFACE, AND TOOL AND CUTTER GRINDERS
by Cincinnati, Churchill, Exel, Lumeden and Wickman
RADIAL, BENCH and PILLAR DRILLING MACHINES

PRATT & WHITNEY No. 3B JIG BORER ULRO 25ft. x 5ft. PLANING MACHINE SHAPING AND SLOTTING MACHINES HORIZONTAL AND VERTICAL BORES PUNCHING, SHEARING AND CROPPING MACHINES

GUILLOTINES; BENDING ROLLS; POWER HAMMERS; ARC WELDING SETS; HYDRAULIC PRESSES OVERHEAD TRAVELLING CRANES HORIZONTAL AND VERTICAL MILLING MACHINES

WEIGHING MACHINES ELECTRIC MOTORS AND FURNACES AIR COMPRESSORS

800 kVA TRANSFORMERS BAR STRAIGHTENING AND TESTING MACHINES; POWER HACKSAWS DRAWING OFFICE, LABORATORY CANTEN AND OFFICE FURNITURE LORRIES; CARS; MOBILE CRANES; AUTO TRUCKS

ENGINEERS' TOOLS AND EQUIPMENT NOTE.—The Industrial Works at Dundee will be offered for SALE BY AUCTION at THE ROYAL HOTEL, DUNDEE, on TUESDAY, 4th NOVEMBER, 1958, at 11 a.m.

Catalogues (when ready), price 6d. each, may be obtained of: Messrs. HENRY BUTCHER & CO., Auctioneers, Valuers & Surveyors of Factories, Plant & Equipment, 73, Chancery Lane, London, W.C.2. Telephone: HOLborn 8411 (8 lines).

SHOULDER & SON

By Order
of the



Minister
of Supply

Sale by Auction at

MELTON MOWBRAY

(15 miles from Leicester; 18 miles from Nottingham; 16 miles from Grantham; 20 miles from Stamford)

MACHINE TOOLS; ENGINE SPARES; LIFTING EQUIPMENT; STEEL WIRE ROPE; RADAR TRAILER VANS; STORES; GRAMOPHONE RECORDERS AND CINE PROJECTORS now lying

at TECHNICAL STORES DEPOT, OLD DALBY (6 miles Melton; 12 from Nottingham; 15 from Leicester; and near Old Dalby L.M.S. Railway Station).

GENERAL STORES SUB-DEPOT, BOUGHTON, nr NEW OLLERTON, NOTTS. (8 miles from Mansfield; 16 miles Nottingham 12 miles Newark)

TECHNICAL STORES SUB-DEPOT, QUENIBOROUGH

(On main road midway Melton and Leicester), including:

17 Ward No. 7 Turret Lathes; Centre Lathes, 3 1/2 to 8in.; Cincinnati and other Horizontal and Vertical Millers; Shapers; Paddon Re-boring M/c.s.; Arc Welders; Pillar and Bench Drills; Portable El. Drills, Saws, Sanders and Grinders; Pedestal, Bench and Flex-shaft Grinders; Valve Refacers and Seat Grinders; Hacksaaws; Magnetic Chucks; Welding Kits; Circular Saw Bench; Saw Blades; Plane and Moulding Iron Grinders; Diamond mounted Wheel Dressers; Oxy-Acet. Pantograph Cutting M/c.; Gramophones, Projectors, and Photographic and Cine Spares; Cotton Sheet and Blanketing; Steel Wire Rope; Lifting Jacks; Chain Pulley Blocks; Portable Runways; Wood Rollers, Beams and Skids; Slings; Truck Spares; Platform Trucks; Paint, Varnish Soft Soap, Whiting; Cartons, Bags, Packing Cases, Paint Canisters; Radar Trailer Vans. WHICH WILL BE SOLD BY AUCTION BY

SHOULDER & SON

on WEDNESDAY and THURSDAY, NOVEMBER 5th and 6th, 1958, at 10.30 a.m. prompt each day AT THEIR AUCTION ASSEMBLY ROOMS, 1, NORMAN STREET, MELTON MOWBRAY.

ON VIEW: Thursday, Monday and Tuesday, October 30th and November 3rd and 4th, and on mornings of sale.

CATALOGUES, 1s. each (P.O. only, no stamps), obtainable from the Auctioneers, Dept. 12, 1 and 3, Norman Street, Melton Mowbray. Tel. 3081 (2 lines).

When answering advertisements kindly mention MACHINERY.

SITUATIONS VACANT

If you do not wish your reply to any Box No. advertisement in this section to be forwarded to certain firms, please advise us. Your reply will then be destroyed, but you will not be notified as this would disclose the identity of the advertiser.

Assembly Departmental

Manager required by S.W. London Company manufacturing Electricity Meters of all types. Applicants must have had similar experience, controlling approx. 250 employees, responsible to Works Manager. Must be conversant with modern methods, time study and possess a background relating to accurate electro-mechanical instrument assembly and be able to ensure quality results against scheduled requirements. The appointment carries an attractive salary with a contributory pension scheme, good conditions, full encouragement by top management to the person selected showing initiative and obtaining the desired results. Age 35/45.—Write, with full particulars of experience, BOX 3, SMITH METERS, LTD., Rowan Road, Streatham Vale, London, S.W.16.

London Machine Tool Merchants

require Salesman to deal with orders, correspondence, etc. Salary £500/700 plus commission, according to experience.—BOX Z566, MACHINERY, Clifton House, Euston Road, N.W.1.

Designer Wanted to Develop

range of Hydraulic-Electric Lifting Machines, etc. Location South-West Wales.—Full details including education, qualifications experience, age, salary, to BOX Z569, MACHINERY, Clifton House, Euston Road, N.W.1.

Setter/Improver Wanted, for

Swiss type automatics, N.W.10 area.—BOX Z605, MACHINERY, Clifton House, Euston Road, N.W.1.

Machine Shop Manager Re-

quired by firm in the Leeds area engaged in precision forging. Applicant must be conversant with milling machines, shapers, planers, grinders, autos, etc. A knowledge of toolmaking and fitting also required. Forging and upsetting experience is an advantage, and candidate must be accustomed to the control of skilled and semi-skilled labour. In reply, please state fully past experience and range of salary required.—BOX Z501, MACHINERY, Clifton House, Euston Road, N.W.1.

Production Engineer Requires

Assistant. Old-established Light Engineering Co., N.W. London District, offers excellent opportunity with interesting work for keen young Production Engineer (H.N.C. Standard preferred) with experience of tool design and production methods on the manufacture of small precision mechanisms.—Write full details of education, experience and present salary in confidence, to WORKS MANAGER, BOX "F.Y.", c/o J. W. VICKERS & CO., LTD., 7, Great Winchester Street, E.C.2.

TECHNICAL SALES—INDUSTRIAL OILS

Applications are invited for a senior position on the outside Technical Sales Staff of a well-known oil firm, specialising in products for the metal working industry. This is an important post on the Sales Director's staff and commands a substantial starting salary.

The successful applicant will be a man of wide relevant experience and outstanding ability with a keen pioneering sense. He will be expected eventually to take over Midlands area Sales Managership. Machine shop and sales experience indispensable as also is residence in the area.

Preferred age 40 to 45 years.

Apply in strict confidence to BOX Z590, MACHINERY, Clifton House, Euston Road, N.W.1.

DEVELOPMENT ENGINEER

A progressive South Yorkshire Company with Nationally recognised reputation for high quality products require the services of an Engineer of outstanding ability with a wide experience of Carbide Tool Design and Application.

Duties will include Development design projects, Investigation and Demonstration at Customers' Works with both established and experimental grades. Improving production techniques, and the Commercial application of all aspects of Tool Manufacture.

A wide engineering background based on extensive machine shop experience, coupled with a sound knowledge of Sales Techniques, is essential.

Salary offered will reflect the high level of responsibility involved.

Applications, giving full details of qualifications, experience and present salary (in confidence), to The Personnel Manager, BOX Z587, MACHINERY, Clifton House, Euston Road, N.W.1.

Working Foreman for Swiss and

Turret Auto Division, with considerable practical experience of setting. Can designing an advantage. Good rates and excellent prospects.—Apply in writing, stating full details to NEUBURGER PRODUCTS, LTD., Rushgrove Parade, N.W.9.

Highly Paid Secure and Interest-

ing posts are always available for technically trained men. Find out how you can put some letters after your name by preparing at home in "No Pass—No Fee" terms for A.M.I.Mech.E., A.M.I.Prod.E., A.M.S.E., City and Guilds, etc., etc. Full details of exams and hundreds of courses in all branches of Engineering, Draughtsmanship and Management, the benefits of our Employment Dept., and unique record of 96 per cent. successes, are given in "Engineering Opportunities"—valuable 144-page Guide which will reveal many chances you are now missing. Write for your copy today (stating subject of interest)—FREE and without obligation.—B.I.E.T., Dept. 548, Wright's Lane, London, W.8.

MACHINE SHOP MANAGER

with wide and comprehensive experience of light production engineering is offered a unique opportunity to establish and develop a Production Engineering Company, by an old-established General Engineering Firm in S.E. London area, who for many years have been sub-contracting this class of work.

Workshop space (about 2,000 square feet to start), with all services, is immediately available. The successful applicant would be responsible for engaging labour and equipping the shop. The parent company has some machine tools, small tools, etc., available if desired.

Initially the appointment would entail much work "on the floor," and only those prepared to get their hands dirty need apply.—BOX Z557, MACHINERY, Clifton House, Euston Road, N.W.1.

WHEN YOU WANT . . .

- TO BUY OR SELL PLANT OR MATERIAL
- WORK FOR A SLACK DEPARTMENT
- AGENCIES OR PARTNERSHIPS
- MEN FOR EXECUTIVE POSITIONS

A SMALL ADVERTISEMENT IN "MACHINERY"
BRINGS RESULTS

**WIGAN AND DISTRICT MINING AND
TECHNICAL COLLEGE**

Applications are invited for a post as Assistant Grade II in Mechanical Engineering. Duties will commence as soon as possible. Candidates should hold a degree in Mechanical Engineering or equivalent qualification, have practical experience in industry or teaching. Salary scale £650 × £25—£1,025 per annum with additions for qualifications and experience.

Further particulars and application form will be sent by the undersigned. Last date for receipt of applications: Friday, 7th November, 1958.

E. C. SMITH, Principal.

October, 1958.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (SITUATIONS VACANT, contd.)

N.W. London firm manufacturing precision equipment require a planning and production engineer aged between 30 and 40. Applicant must have experience in small batch production. Only top rate men capable of holding down a four figure salary need apply.

Box Z 543, MACHINERY,
Clifton House, Euston Road, N.W.1.

REPRESENTATIVES

Slip Gauge Manufacturers Wish to appoint Agent for Greater London. Must have good standing with and at present making regular calls upon buyers of precision small tools.—Write, giving full particulars, in confidence, to BOX Z540, MACHINERY, Clifton House, Euston Road, N.W.1.

Technical Representative Re-quired for Scotland by well-known established Machine Tool Company. Salary and expense allowance. Car provided. Applicants should have thorough knowledge of practical engineering.—Write stating age, experience and qualifications to BOX Z606, MACHINERY, Clifton House, Euston Road, N.W.1.

Free Lance Sales Representative required to sell Swiss machines in Northern England area to present customers and also to open new accounts. These are small precision machines and have been sold in the United Kingdom for the past thirty years. Details required—when replying—of types of products sold at the present moment, business contacts, previous experience, commission required, etc.—BOX Z607, MACHINERY, Clifton House, Euston Road, N.W.1.

Freelance Agents Required for the sale of well-introduced machine tools and workshop equipment, in all areas except Birmingham and Yorkshire. Liberal commission and mileage allowance. Workshop experience required, car owner preferred.—BOX Z445, MACHINERY, Clifton House, Euston Road, N.W.1.

Agents Required for Precision gauge and toolmakers, specialising in form grinding and spline gauges.—BOX Z553, MACHINERY, Clifton House, Euston Road, N.W.1.

Barrel Finishing. Agents Re-quired in all areas for our compounds and media.—GRANATT CHEMICAL AND ENGINEERING CO., Austin Road, Battersea, London, S.W.11. MACaulay 7723.

MACHINE TOOL SALESMAN

Vacancy occurs in Well-known Machine Tool House for Junior Salesman to operate in the North Birmingham Area. Applicant must have engineering background and preference given to man with established connections. Full details in confidence.

BOX Z570, MACHINERY,
Clifton House,
Euston Road, N.W.1.

Experienced Machine Tool Representative for West Midland area required by renowned Company.—Full details of experience, age, salary required to BOX Z559, MACHINERY, Clifton House, Euston Road, N.W.1.

Springs. Manufacturers of High quality springs and presswork for the Aircraft, Electronic and Instrument Trades situated in the Midlands, require Representatives. The applicants must have established connections and if successful the position will be progressive, as this Company is expanding. Pension scheme. Please reply giving details of experience and present salary.—BOX Z583, MACHINERY, Clifton House, Euston Road, N.W.1.

Agent or Free Lance Technical Representative required on commission for medium sized well-established London Company of Precision Engineers and Toolmakers, to introduce work for well equipped machine shop and toolroom. A.I.D. and A.R.B. approved. Workmanship and deliveries guaranteed. Prices highly competitive. An opportunity for a first class man with live connections who can produce results. Attractive commission will be offered. All replies in strictest confidence to General Manager.—BOX Z595, MACHINERY, Clifton House, Euston Road, N.W.1.

Representative Required for Surrey, Kent and Sussex, initially to work on a free lance basis. Products include Vertical Drilling Machines, Tool Grinders and associated equipment, with a rapidly developing special machine section.—Please state products now represented, details of previous experience, etc., to BOX Z593, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanted, Free Lance Representa-tives already calling on the Engineering and Plastics Industries to sell Hydraulic Presses and Hydraulic Equipment. Only experienced men with technical experience and established connections.—Write BOX Z600, MACHINERY, Clifton House, Euston Road, N.W.1.

SITUATIONS WANTED

Works Manager, 38, Seeks Pro-gressive post, 22 years' experience all departments light precision engineering, including toolroom, drawing office, sales, buying, estimating and production. Present position responsible for running company manufacturing press tools, jigs, fixtures and moulds to the trade, also precision parts. Would consider position as technical representative.—BOX Z533, MACHINERY, Clifton House, Euston Road, N.W.1.

Engineer, 40, Over 20 Years extensive experience in light engineering including automatics, capstans, etc. Seeks change in responsible position.—BOX Z585, MACHINERY, Clifton House, Euston Road, N.W.1.

Senior Machine Tool Correspon-dent many years experience Sales Department and Showroom control seeks position of responsibility.—BOX Z575, MACHINERY, Clifton House, Euston Road, N.W.1.

Senior Estimator/Planner with practical tool design and workshop experience, light/medium engineering, seeks post preferably South Coast area. Would accept responsibility as Works Manager with small progressive firm.—BOX Z574, MACHINERY, Clifton House, Euston Road, N.W.1.

Method Planning Development Engineer and Automatic Cam Designer (34), apprenticeship trained with technical background. Experienced in production engineering and applied automation, desires position in South Wales.—BOX Z602, MACHINERY, Clifton House, Euston Road, N.W.1.

Mechanical Designer. Experi-enced in special purpose machines, general tooling, industrial gas turbines, aero engines, automotive design, etc. Formerly Chief Draughtsman, recently returned from U.S.A. Desires position in machine design.—BOX Z445, MACHINERY, Clifton House, Euston Road, N.W.1.

Advertiser, Age 34 Years, Very wide experience of all aspects of new and secondhand machine tool merchandising, including management, inspection, valuation, sales, advertising, etc., etc., seeks responsible position inside or out. First class references.—BOX Z541, MACHINERY, Clifton House, Euston Road, N.W.1.

Chief Inspector, I.E.M.E., A.I.D., A.R.B. approved, desires similar position London District.—BOX Z536, MACHINERY, Clifton House, Euston Road, N.W.1.

Engineer (46), Administrative grade, seeks supervisory position. Indentured apprentice. Positions held: Production Shop Foreman, Toolroom Foreman, Planning and Methods, Production Development Engineer. Present salary £1,025. (Own mobile home).—BOX Z549, MACHINERY, Clifton House, Euston Road, N.W.1.

Chief Engineer Works Manager. 47. A.M.I.P.E. desires change. Extensive experience of factory automation and batch production for precision mechanical, electrical, pneumatic equipment. Introduced on of new products covering design, development and production, patents, etc.—BOX Z610, MACHINERY, Clifton House, Euston Road, N.W.1.

REPRESENTATIVES

Traveller, With Many Years' experience, selling capacity for Automatics, Capstans and C/H Machines. Area covered Northern, Midlands, London and Southern Counties.—BOX Z490, MACHINERY, Clifton House, Euston Road, N.W.1.

Press Tools, Jigs, Fixtures: advertiser nationwide connection wishes to represent first class company, part extensive allowance and commission.—BOX Z565, MACHINERY, Clifton House, Euston Road, N.W.1.

RECEIVED TOO LATE FOR CLASSIFICATION

PLANT WANTED

One Secondhand Corona 16MX 12 spindle adjustable shoe drilling machine.—BOX Z603, MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Diprofil

POWER OPERATED



FILING ...
LAPPING ...
SCRAPING ...
GRINDING ...
HONING ...
ENGRAVING ...
MILLING ... SAWING



(TAYLOR)

Screw and Plain PLUG and RING GAUGES



BROOKS & WALKER LTD..

47 Great Eastern St., London, E.C.2. SHO 7633

Telex No. 23674

Midlands Office : Swan Lane, Coventry. Tel.: 64246

Branches throughout the Country

INDEX TO ADVERTISERS

[illegible]

Nitrided

**DIE-SET PILLARS AND BUSHES
GUIDE PINS AND BUSHES
for INJECTION AND PRESSURE MOULDS**



Nitrided pins and bushes are essential in any die or mould operating under heat! Nitrided cases do not soften! Nitrided parts are not self tempering! Nitrided parts stay hard indefinitely ... even through repeated cycles up to 500° C.




BRITISH AERO COMPONENTS LTD
MONTAGUE ROAD WARWICK, ENGLAND

Tel. Warwick 320 Telegrams 'Aeroparts' Warwick

PLAIN C • SHOULDER • SPECIAL • FORM • MULTI-DIAMETER



*work ground on
B.S.A. centreless
grinders has an
excellent finish
and a high degree
of diametrical
and cylindrical
accuracy*




No. 4 machine equipped for automatic sizing-control and automatic feed. Vibratory type hopper. Special bolts $7/16" \times 2\frac{7}{8}"$ (11 mm x 73 mm) long are ground to a tolerance of 0.0005" (0.012 mm). Production: 700 bolts per hour. Sizing-control incorporates automatic grinding wheel head feed-compensation.

No. 4 MACHINE

Work diameter: $1/16"$ to $3"$
(1.58 to 76 mm)
Grinding wheel Speed: 1270 rpm
Control wheel Speeds: 4
Width of wheels: $4"$ (101 mm) or
 $5"$ (127 mm)
Main motor: 10 h.p.

* (With special equipment
work down to 0.010"
(0.254 mm) dia. can be
accommodated).



No. 8 machine equipped for bar grinding. Bar steadies for B.S.A. centreless grinders accommodate work from $1/16"$ to $3"$ (1.58 to 76 mm) lengths up machine, diameter diameter No. 4

